

# TYPICAL SECTION GENERATOR HELP

As the name implies, the purpose of this document is to provide help in using the Missouri Department of Transportation's (MoDOT) configuration for creating proposed cross-sections inside of GEOPAK Road using the Typical Section Generator. The philosophy used in creating this help is to provide useful information with a minimum amount of repetition. This has impacted the structure of the document and the use of extensive cross-references, which are available only if used in electronic form.

The document is divided into chapters and appendices. There is one chapter for each typical section. What is drawn is controlled by graphical elements in various MicroStation Files (DGN's), variables that are globally defined for the entire proposed cross-section run, and variables that are redefinable within the run using a station range or other parameter. Each chapter gives a brief description of what the typical section can draw and lists the graphical elements, the globally defined variables, and the redefinable variables that are used by that typical section. The appendices give detailed information on particular subjects, most of which are used by more than one typical section.

Because the information needed for using any of the typical sections is spread over both its chapter and a number of appendices, links are available to quickly find information within the electronic document and allow you to easily return to the previous location. You may navigate through the document by clicking on items in the Table of Contents (located on next page) or on any of the other blue text in the document. The program's **Back** and **Forward** buttons can also be used to navigate to recently viewed pages.

## Table of Contents

Divided New Pavement Typical Section (DNPavt) .....	3
Divided Reconstruction Typical Section (DRecon) .....	9
Draw Right of Way Lines (DrwROW) .....	15
Existing Features (ExFeat) .....	17
New Construction Left And Reconstruction Right Typical Section (NLtRRt) .....	19
New Construction Right And Reconstruction Left Typical Section (NRtRLt) .....	25
Proposed Paved Ditches (PDitch) .....	31
Trace Existing Sub Layers (SubLay) .....	33
Undivided New Pavement Typical Section (UNPavt) .....	35
Undivided Reconstruction Typical Section (URECon) .....	41
Appendix 1 Scanned Graphic Elements .....	47
Appendix 2 Define Variables .....	55
Appendix 3 Redefinable Variables .....	63
Appendix 4 Existing Features .....	109
Appendix 5 Pavement .....	118
Appendix 6 Reconstruction .....	123
Appendix 7 Rural Shoulders .....	124
Appendix 8 Curbing With Urban Shoulders (U1 & U2) .....	129
Appendix 9 Standard Side Slopes (No Special Profiles) .....	135
Appendix 10 Special Ditches (Using Profiles to Set Ditch Elevation) .....	143
Appendix 11 Medians .....	145
Appendix 12 Match Lines .....	146
Appendix 13 Rock Benches .....	149
Appendix 14 Sidewalk .....	151
Appendix 15 Retaining Walls .....	153
Appendix 16 Tapering Procedures .....	157
Appendix 17 Gore Areas .....	163
Appendix 18 Levee and Optional Interception Ditch .....	169
Appendix 19 Profile Grade Report Text .....	170
Appendix 20 Troubleshooting Redefinable Variable Syntax Errors .....	172

## Divided New Pavement Typical Section (DNPavt)

This typical section draws proposed cross sections for divided new pavement projects. It works for both rural and urban sections or a combination of the two. It draws bituminous and concrete [Pavement](#), [Rural Shoulders](#), [Curbing With Urban Shoulders \(U1 & U2\)](#), [Standard Side Slopes](#), and [Special Ditches](#).


This typical section resolves rural and or urban [Medians](#) including stepped barrier and retaining wall medians. There are a total of seven types of medians to choose from. The detailed options are covered later in this document.

This typical section is for new construction only. All dimensions are in master units of feet.

**IMPORTANT:** Set the proposed cross section run "Tolerance" value to 0.01. This is required for the criteria to work correctly.

**IMPORTANT:** Always include the proposed shape clusters in order from left to right. The left shape cluster should always be listed before the right shape cluster.

Divided New Construction  
Rural or Urban



Bituminous Or Concrete Pavement  
Shoulders, Curb and Gutter, or Both

The rest of this section lists the scanned graphic elements, globally defined variables, and redefinable variables used by this typical section. The appendices, which can be reached through the links in the [Table of Contents](#), give additional information.

**Scanned Graphic Elements**

The typical section scans design files for the following types of graphic elements. Click on an individual type to find out information about which Design and Computation Manager item is used for each item in that type.

**ELEMENT TYPE**

[Right of Way](#)  
[Existing Ground](#)  
[Pavement and Shoulder](#)  
[Curb and Gutter](#)  
[Curb](#)  
[Gutter](#)  
[Concrete Barrier Curb and Guardrail](#)  
[Roadside](#)  
[Side Slope and Drainage](#)

**DGN DRAWING FILE**

Right of Way DGN  
Cross-Section DGN  
Proposed Plan DGN  
Proposed Plan DGN  
Proposed Plan DGN  
Proposed Plan DGN  
Proposed Plan DGN  
Proposed Plan DGN  
GEOPAK Lines DGN

IF ANY OF THE ABOVE TYPES OF ELEMENTS DO NOT APPLY TO YOUR JOB YOU MUST STILL SPECIFY A VALID DESIGN FILE OR ELSE AN ERROR WILL OCCUR. THE CRITERIA FILES WILL NOT PROCESS AN ELEMENT IF IT DOESN'T EXIST.

## **DEFINE VARIABLES**

The typical section uses the following globally define variables. Click on an individual variable for further information.

### **DGN File**

[Right of Way DGN](#)  
[Cross Section DGN](#)  
[Proposed Plan DGN](#)  
[GEOPAK Lines DGN](#)

### **Tapers File**

[Left Tapers File Name](#)  
[Right Tapers File Name](#)

### **Plot Scale**

[XS Scale](#)  
[Plan View Scale](#)  
[Plan View Flow Arrow Scale](#)

### **GPB Element**

[Survey Baseline Name](#)  
[Left Special Ditch Profiles and Right Special Ditch Profiles](#)  
[Left Ditch Alignment and Right Ditch Alignment](#)  
[Left Match Line Profiles and Right Match Line Profiles](#)  
[Left Sidewalk Profiles and Right Sidewalk Profiles](#)  
[Left Interception Special Ditch Profiles and Right Interception Special Ditch Profiles](#)  
[Median Ditch Profiles](#)  
[Ramp Chain Names](#)  
[Match Line Chain Names](#)  
[Left Top of Wall Profiles and Right Top of Wall Profiles](#)  
[Left Top of Footing Profiles and Right Top of Footing Profiles](#)  
[Median Top of Footing Profiles](#)

### Redefinable Variables

The typical section uses the following redefinable variables, which can have different values within the same run based on station range or another user-defined parameter. Click on an individual variable for further information. They are listed in the order they have in the run dialog box.

#### Right of Way Buffer Width:

[\\_d\\_ROW\\_Buffer\\_Width](#)

#### Pavement Structure

<a href="#">_s_PavementType</a>	<a href="#">_d_PavementLayer3Thick</a>	<a href="#">_d_RockFillBaseThickness</a>
<a href="#">_d_NormalPavementSlope</a>	<a href="#">_d_PavementLayer4Thick</a>	<a href="#">_s_RockFillBaseDaylight</a>
<a href="#">_d_PavementLayer1Thick</a>	<a href="#">_d_Aggbase1Thickness</a>	<a href="#">_s_RockFillBaseDaylightHSS</a>
<a href="#">_d_PavementLayer2Thick</a>	<a href="#">_d_Aggbase2Thickness</a>	<a href="#">_d_CompensatingDepth</a>

#### Underdrain

<a href="#">_s_DrawLeftUnderdrain</a>	<a href="#">_d_UnderdrainHeight</a>	<a href="#">_d_UnderdrainWidth</a>
<a href="#">_s_DrawRightUnderdrain</a>		

#### Outside Shoulder

<a href="#">_s_OutsideShoulderType</a>	<a href="#">_d_NormalOutsideShoulderSlope</a>	<a href="#">_d_ShoulderLayer3Thick</a>
<a href="#">_d_OutsideShoulderWidth</a>	<a href="#">_d_ShoulderLayer1Thick</a>	<a href="#">_d_ShoulderLayer4Thick</a>
<a href="#">_d_OutsideShoulderSearchDistance</a>	<a href="#">_d_ShoulderLayer2Thick</a>	<a href="#">_s_ExtensionSlope</a>
<a href="#">_s_LabelShoulderElevations</a>		

#### Median

<a href="#">_s_MedianShoulderType</a>	<a href="#">_s_MedianType</a>	<a href="#">_d_StdMedianDitchDepth</a>
<a href="#">_d_MedianShoulderWidth</a>	<a href="#">_d_MedianSlope1</a>	<a href="#">_d_MedianDitchWidth</a>
<a href="#">_d_MedianShoulderSearchDistance</a>	<a href="#">_d_MedianSlope1Width</a>	<a href="#">_d_PavedMedianThickness</a>
<a href="#">_d_NormalMedianShoulderSlope</a>	<a href="#">_d_MedianSlope2</a>	<a href="#">_d_MaxPavedMedianWidth</a>

**Curb and Gutter**

\_d\_CurbSearchDistance

\_d\_IntegralCurbHeight

\_s\_GutterSlopeInSuper

**U2 Shoulder**

\_d\_U2ShoulderSearchDistance

\_d\_U2ShoulderSlope

\_d\_U2ShoulderAggbaseThickness

\_d\_U2ShoulderWidth

\_d\_U2ShoulderThickness

**Berm and Sidewalk**

\_d\_BermSlope\_Left

\_d\_BermWidth\_Left

\_d\_SidewalkSlope

\_d\_BermSlope\_Right

\_d\_BermWidth\_Right

\_d\_SidewalkThickness

**Standard Ditch**

\_d\_DitchForeSlope1\_Left

\_d\_DitchForeSlope2\_Left

\_d\_DitchWidth\_Left

\_d\_DitchForeSlope1\_Right

\_d\_DitchForeSlope2\_Right

\_d\_DitchWidth\_Right

\_d\_DitchForeSlope1Width\_Left

\_d\_StandardDitchDepth\_Left

\_d\_DitchBackSlope\_Left

\_d\_DitchForeSlope1Width\_Right

\_d\_StandardDitchDepth\_Right

\_d\_DitchBackSlope\_Right

**Fill Slope**

\_d\_FillSlope1\_Left

\_d\_FillSlope1Width\_Left

\_d\_FillSlope2\_Left

\_d\_FillSlope1\_Right

\_d\_FillSlope1Width\_Right

\_d\_FillSlope2\_Right

**Force Closed Slope**

\_s\_LeftForceClosingSlopes

\_d\_LeftForcedCutSlope

\_d\_RightForcedCutSlope

\_s\_RightForceClosingSlopes

\_d\_LeftForcedFillSlope

\_d\_RightForcedFillSlope

**Right of Way Constrained Slope**

\_s\_LeftROWConstrainedSlope

\_s\_RightROWConstrainedSlope

**Special Ditch Label:**

\_s\_SpecialDitchLabel

**Draw Ditches in Plan View:**

[\\_s\\_DrawDitchesInPlanView](#)

**Rock Benching**

[\\_d\\_BenchingBackSlope](#)  
[\\_d\\_BenchWidth](#)

[\\_d\\_BenchHeight](#)

[\\_s\\_TopBenchWidth](#)

**Chain Search Distance**

[\\_d\\_RampChainSearchDistance](#)

[\\_d\\_MatchLineChainSearchDistance](#)

**Entrance**

[\\_d\\_EntrancePadWidth](#)  
[\\_d\\_EntranceVertCurveLength](#)  
[\\_d\\_Max\\_Type1\\_Driveway\\_Slope](#)  
[\\_d\\_Max\\_Type1\\_Roll\\_Over\\_Slope](#)

[\\_d\\_Max\\_Type2\\_Driveway\\_Slope](#)  
[\\_d\\_Max\\_Type2\\_Roll\\_Over\\_Slope](#)  
[\\_d\\_Max\\_Type3\\_Driveway\\_Slope](#)  
[\\_d\\_Max\\_Type3\\_Roll\\_Over\\_Slope](#)

[\\_d\\_Max\\_Type4\\_Driveway\\_Slope](#)  
[\\_d\\_Max\\_Type4\\_Roll\\_Over\\_Slope](#)  
[\\_d\\_Max\\_Type5\\_Driveway\\_Slope](#)  
[\\_d\\_Max\\_Type5\\_Roll\\_Over\\_Slope](#)

**Retaining Wall**

[\\_d\\_DepthBelowProposedGroundInCut](#)  
[\\_d\\_HeightAboveExistGroundInCut](#)  
[\\_d\\_DepthBelowExistGroundInFill](#)  
[\\_d\\_HeightAbovePropGroundInFill](#)  
[\\_d\\_WallWidth](#)

[\\_s\\_WallHeight](#)  
[\\_d\\_BackWallHeightInCut](#)  
[\\_d\\_BackFootingWidth](#)  
[\\_d\\_TotalFootingWidth](#)  
[\\_d\\_FootingThickness](#)

[\\_d\\_KeyOffset](#)  
[\\_d\\_KeyWidth](#)  
[\\_d\\_KeyHeight](#)  
[\\_d\\_AdjacentWallSearchDistance](#)

**Levee and Interception Ditch**

[\\_s\\_LeveeAdjacentToDitch](#)  
[\\_d\\_LeveeHeight](#)

[\\_d\\_LeveeForeslope](#)  
[\\_d\\_LeveeBackslope](#)

[\\_d\\_InterceptionDitchWidth](#)  
[\\_d\\_InterceptionDitchBackslope](#)

**Non-Standard Curb and Gutter**

[\\_d\\_GutterSlope](#)  
[\\_d\\_GutterWidth](#)  
[\\_d\\_CurbFaceWidth](#)

[\\_d\\_TopCurbWidth](#)  
[\\_d\\_CurbHeight](#)

[\\_d\\_GutterThickness](#)  
[\\_d\\_GutterBaseSlope](#)



## Divided Reconstruction Typical Section (DRecon)


This typical section draws proposed cross sections for divided [Reconstruction](#) projects. It works for both rural and urban sections or a combination of the two. It draws up to two overlay layers and an optional widening with bituminous or concrete [Pavement](#) using either a "match existing" or "crown correction" approach. It draws bituminous and concrete [Pavement](#), [Rural Shoulders](#), [Curbing With Urban Shoulders \(U1 & U2\)](#), [Standard Side Slopes](#), and [Special Ditches](#).

This typical section resolves rural and or urban [Medians](#) including stepped barrier and retaining wall medians. There are a total of seven types of medians to choose from. The detailed options are covered later in this document.

This typical section is for reconstruction only. All dimensions are in master units of feet.

**IMPORTANT:** Set the proposed cross section run "Tolerance" value to 0.01. This is required for the criteria to work correctly.

**IMPORTANT:** Always include the proposed shape clusters in order from left to right. The left shape cluster should always be listed before the right shape cluster.



The rest of this section lists the scanned graphic elements, globally defined variables, and redefinable variables used by this typical section. The appendices, which can be reached through the links in the [Table of Contents](#), give additional information.

**Scanned Graphic Elements**

The typical section scans design file for the following types of graphic elements. Click on an individual type to find out information about which Design and Computation Manager item is used for each item.

<b><u>ELEMENT TYPE</u></b>	<b><u>DGN DRAWING FILE</u></b>
<a href="#">Right of Way</a>	Right of Way DGN
<a href="#">Reconstruction Existing Edge of Pavement</a>	Existing TOPO DGN
<a href="#">Existing Ground</a>	Cross-Section DGN
<a href="#">Saw Cut</a>	Proposed Plan DGN
<a href="#">Pavement and Shoulder</a>	Proposed Plan DGN
<a href="#">Curb and Gutter</a>	Proposed Plan DGN
<a href="#">Curb</a>	Proposed Plan DGN
<a href="#">Gutter</a>	Proposed Plan DGN
<a href="#">Concrete Barrier Curb and Guardrail</a>	Proposed Plan DGN
<a href="#">Roadside</a>	Proposed Plan DGN
<a href="#">Side Slope and Drainage</a>	GEOPAK Lines DGN

IF ANY OF THE ABOVE TYPES OF ELEMENTS DO NOT APPLY TO YOUR JOB YOU MUST STILL SPECIFY A VALID DESIGN FILE OR ELSE AN ERROR WILL OCCUR. THE CRITERIA FILES WILL NOT PROCESS AN ELEMENT IF IT DOESN'T EXIST.

## **DEFINE VARIABLES**

The typical section uses the following globally define variables. Click on an individual variable for further information.

### **DGN File**

[Existing TOPO DGN](#)  
[Right of Way DGN](#)  
[Cross Section DGN](#)  
[Proposed Plan DGN](#)  
[GEOPAK Lines DGN](#)

### **Tapers File**

[Left Tapers File Name](#)  
[Right Tapers File Name](#)

### **Plot Scale**

[XS Scale](#)  
[Plan View Scale](#)  
[Plan View Flow Arrow Scale](#)

### **GPK Element**

[Survey Baseline Name](#)  
[Left Special Ditch Profiles and Right Special Ditch Profiles](#)  
[Left Ditch Alignment and Right Ditch Alignment](#)  
[Left Match Line Profiles and Right Match Line Profiles](#)  
[Left Sidewalk Profiles and Right Sidewalk Profiles](#)  
[Left Interception Special Ditch Profiles and Right Interception Special Ditch Profiles](#)  
[Median Ditch Profiles](#)  
[Ramp Chain Names](#)  
[Match Line Chain Names](#)  
[Left Top of Wall Profiles and Right Top of Wall Profiles](#)  
[Left Top of Footing Profiles and Right Top of Footing Profiles](#)  
[Median Top of Footing Profiles](#)

### Redefinable Variables

The typical section uses the following redefinable variables, which can have different values within the same run based on station range or another parameter. Click on an individual variable for further information. They are listed in the order they have in the run dialog.

#### Right of Way Buffer Width:

[\\_d\\_ROW\\_Buffer\\_Width](#)

#### Pavement Structure

<a href="#">_s_PavementType</a>	<a href="#">_d_PavementLayer3Thick</a>	<a href="#">_d_RockFillBaseThickness</a>
<a href="#">_d_NormalPavementSlope</a>	<a href="#">_d_PavementLayer4Thick</a>	<a href="#">_s_RockFillBaseDaylight</a>
<a href="#">_d_PavementLayer1Thick</a>	<a href="#">_d_Aggbase1Thickness</a>	<a href="#">_s_RockFillBaseDaylightHSS</a>
<a href="#">_d_PavementLayer2Thick</a>	<a href="#">_d_Aggbase2Thickness</a>	<a href="#">_d_CompensatingDepth</a>

#### Underdrain

<a href="#">_s_DrawLeftUnderdrain</a>	<a href="#">_d_UnderdrainHeight</a>	<a href="#">_d_UnderdrainWidth</a>
<a href="#">_s_DrawRightUnderdrain</a>		

#### Reconstruction

<a href="#">_s_OverlayType</a>	<a href="#">_s_OverlayOffsetLocation</a>	<a href="#">_d_OverlayThickness2</a>
<a href="#">_s_WideningSlope</a>	<a href="#">_d_OverlayThickness1</a>	

#### Outside Shoulder

<a href="#">_s_OutsideShoulderType</a>	<a href="#">_d_NormalOutsideShoulderSlope</a>	<a href="#">_d_ShoulderLayer3Thick</a>
<a href="#">_d_OutsideShoulderWidth</a>	<a href="#">_d_ShoulderLayer1Thick</a>	<a href="#">_d_ShoulderLayer4Thick</a>
<a href="#">_d_OutsideShoulderSearchDistance</a>	<a href="#">_d_ShoulderLayer2Thick</a>	<a href="#">_s_ExtensionSlope</a>
<a href="#">_s_LabelShoulderElevations</a>		

#### Median

<a href="#">_s_MedianShoulderType</a>	<a href="#">_s_MedianType</a>	<a href="#">_d_StdMedianDitchDepth</a>
<a href="#">_d_MedianShoulderWidth</a>	<a href="#">_d_MedianSlope1</a>	<a href="#">_d_MedianDitchWidth</a>
<a href="#">_d_MedianShoulderSearchDistance</a>	<a href="#">_d_MedianSlope1Width</a>	<a href="#">_d_PavedMedianThickness</a>
<a href="#">_d_NormalMedianShoulderSlope</a>	<a href="#">_d_MedianSlope2</a>	<a href="#">_d_MaxPavedMedianWidth</a>

**Curb and Gutter**

[\\_d\\_CurbSearchDistance](#) [\\_d\\_IntegralCurbHeight](#) [\\_s\\_GutterSlopeInSuper](#)

**U2 Shoulder**

[\\_d\\_U2ShoulderSearchDistance](#) [\\_d\\_U2ShoulderSlope](#) [\\_d\\_U2ShoulderAggbaseThickness](#)  
[\\_d\\_U2ShoulderWidth](#) [\\_d\\_U2ShoulderThickness](#)

**Berm and Sidewalk**

[\\_d\\_BermSlope\\_Left](#) [\\_d\\_BermWidth\\_Left](#) [\\_d\\_SidewalkSlope](#)  
[\\_d\\_BermSlope\\_Right](#) [\\_d\\_BermWidth\\_Right](#) [\\_d\\_SidewalkThickness](#)

**Standard Ditch**

[\\_d\\_DitchForeSlope1\\_Left](#) [\\_d\\_DitchForeSlope2\\_Left](#) [\\_d\\_DitchWidth\\_Left](#)  
[\\_d\\_DitchForeSlope1\\_Right](#) [\\_d\\_DitchForeSlope2\\_Right](#) [\\_d\\_DitchWidth\\_Right](#)  
[\\_d\\_DitchForeSlope1Width\\_Left](#) [\\_d\\_StandardDitchDepth\\_Left](#) [\\_d\\_DitchBackSlope\\_Left](#)  
[\\_d\\_DitchForeSlope1Width\\_Right](#) [\\_d\\_StandardDitchDepth\\_Right](#) [\\_d\\_DitchBackSlope\\_Right](#)

**Fill Slope**

[\\_d\\_FillSlope1\\_Left](#) [\\_d\\_FillSlope1Width\\_Left](#) [\\_d\\_FillSlope2\\_Left](#)  
[\\_d\\_FillSlope1\\_Right](#) [\\_d\\_FillSlope1Width\\_Right](#) [\\_d\\_FillSlope2\\_Right](#)

**Force Closed Slope**

[\\_s\\_LeftForceClosingSlopes](#) [\\_d\\_LeftForcedCutSlope](#) [\\_d\\_RightForcedCutSlope](#)  
[\\_s\\_RightForceClosingSlopes](#) [\\_d\\_LeftForcedFillSlope](#) [\\_d\\_RightForcedFillSlope](#)

**Right of Way Constrained Slope**

[\\_s\\_LeftROWConstrainedSlope](#) [\\_s\\_RightROWConstrainedSlope](#)

**Special Ditch Label:**

[\\_s\\_SpecialDitchLabel](#)

**Draw Ditches in Plan View:**

[\\_s\\_DrawDitchesInPlanView](#)

**Rock Benching**

[\\_d\\_BenchingBackSlope](#)  
[\\_d\\_BenchWidth](#)

[\\_d\\_BenchHeight](#)

[\\_s\\_TopBenchWidth](#)

**Chain Search Distance**

[\\_d\\_RampChainSearchDistance](#)

[\\_d\\_MatchLineChainSearchDistance](#)

**Entrance**

[\\_d\\_EntrancePadWidth](#)  
[\\_d\\_EntranceVertCurveLength](#)  
[\\_d\\_Max\\_Type1\\_Driveway\\_Slope](#)  
[\\_d\\_Max\\_Type1\\_Roll\\_Over\\_Slope](#)

[\\_d\\_Max\\_Type2\\_Driveway\\_Slope](#)  
[\\_d\\_Max\\_Type2\\_Roll\\_Over\\_Slope](#)  
[\\_d\\_Max\\_Type3\\_Driveway\\_Slope](#)  
[\\_d\\_Max\\_Type3\\_Roll\\_Over\\_Slope](#)

[\\_d\\_Max\\_Type4\\_Driveway\\_Slope](#)  
[\\_d\\_Max\\_Type4\\_Roll\\_Over\\_Slope](#)  
[\\_d\\_Max\\_Type5\\_Driveway\\_Slope](#)  
[\\_d\\_Max\\_Type5\\_Roll\\_Over\\_Slope](#)

**Retaining Wall**

[\\_d\\_DepthBelowProposedGroundInCut](#)  
[\\_d\\_HeightAboveExistGroundInCut](#)  
[\\_d\\_DepthBelowExistGroundInFill](#)  
[\\_d\\_HeightAbovePropGroundInFill](#)  
[\\_d\\_WallWidth](#)

[\\_s\\_WallHeight](#)  
[\\_d\\_BackWallHeightInCut](#)  
[\\_d\\_BackFootingWidth](#)  
[\\_d\\_TotalFootingWidth](#)  
[\\_d\\_FootingThickness](#)

[\\_d\\_KeyOffset](#)  
[\\_d\\_KeyWidth](#)  
[\\_d\\_KeyHeight](#)  
[\\_d\\_AdjacentWallSearchDistance](#)

**Levee and Interception Ditch**

[\\_s\\_LeveeAdjacentToDitch](#)  
[\\_d\\_LeveeHeight](#)

[\\_d\\_LeveeForeslope](#)  
[\\_d\\_LeveeBackslope](#)

[\\_d\\_InterceptionDitchWidth](#)  
[\\_d\\_InterceptionDitchBackslope](#)

**Non-Standard Curb and Gutter**

[\\_d\\_GutterSlope](#)  
[\\_d\\_GutterWidth](#)  
[\\_d\\_CurbFaceWidth](#)

[\\_d\\_TopCurbWidth](#)  
[\\_d\\_CurbHeight](#)

[\\_d\\_GutterThickness](#)  
[\\_d\\_GutterBaseSlope](#)

Draw Right of Way Lines (DrwROW)

This typical section searches the right of way drawing for any instances of both existing and proposed right of way lines. If any are found, their location is drawn and labeled on the cross sections. The following plan view elements are searched for:

- Existing Right of Way

Existing Right of Way Controlled Access

Proposed Right of Way

Proposed Right of Way Controlled Access

Proposed Right of Way Permanent Easement
- Existing Right of Way Temporary Access

Existing Right of Way No Right of Access

Proposed Right of Way Temporary Access

Proposed Right of Way No Right of Access

Proposed Right of Way Temporary Easement

**IMPORTANT:** Set the proposed cross section run "Tolerance" value to 0.01. This is required for the criteria to work correctly.

Label Right of Way Locations

Multiple Instances Allowed



The rest of this section lists the scanned graphic elements, globally defined variable, and redefinable variable used by this typical section. The appendices, which can be reached through the links in the [Table of Contents](#), give additional information.

### Scanned Graphic Elements

The typical section scans a design file for the following types of graphic elements. Click on an individual type to find out information about which Design and Computation Manager item is used for each item.

<u>ELEMENT TYPE</u>	<u>DGN DRAWING FILE</u>
<a href="#">Right of Way</a>	Right of Way DGN

IF ANY OF THE ABOVE TYPES OF ELEMENTS DO NOT APPLY TO YOUR JOB YOU MUST STILL SPECIFY A VALID DESIGN FILE OR ELSE AN ERROR WILL OCCUR. THE CRITERIA FILES WILL NOT PROCESS AN ELEMENT IF IT DOESN'T EXIST.

### DEFINE VARIABLES

The typical section uses the following globally define variables. Click on an individual variable for further information.

**DGN File**  
[Right of Way DGN](#)

**Plot Scale**  
[XS Scale](#)

### Redefinable Variables

The typical section uses the following redefinable variable, which can have different values within the same run based on station range or another parameter.

#### **Right of Way Line Height**

This is the height of the line in master units drawn to represent the location of existing and proposed right of way. The number **MUST** be greater than zero.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    \_d\_RightofWayLineHeight = 10
}
```



## Existing Features (ExFeat)

This typical section searches a plan view drawing for certain existing features. The following existing features are drawn if found:


Existing Pavement  
Existing Paved Surfaces  
Existing Buildings

Existing Paved Shoulder  
Existing Sidewalks  
Existing Railroads

Existing Curb and Gutter  
Existing Paved Ditches  
Existing Wall

It handles multiple instances of the above listed items with the following restriction. There must be an even number of edges of paved surfaces in the plan view. If an odd number of pavement edges or sidewalk edges are found, a warning message is drawn stating **"Irregular Pavement Found"** and no pavement will be drawn for pavement and **"Irregular Sidewalk Found"** if an odd number of sidewalk edges are found. In other words the criteria must be able to find two lines to connect. If there are an odd number of lines found, there is not a way for the criteria to determine which two lines are to be connected.

**IMPORTANT:** Set the proposed cross section run "Tolerance" value to 0.01. This is required for the criteria to work correctly.



The rest of this section lists the scanned graphic elements, globally defined variables, and redefinable variables used by this typical section. [Appendix 4 Existing Features](#) gives additional information on using this typical section.

**Scanned Graphic Elements**

The typical section scans design file for the following types of graphic elements. Click on an individual type to find out information about which Design and Computation Manager item is used for each item.

**ELEMENT TYPE**

[Draw Existing Features](#)

**DGN DRAWING FILE**

[Existing Topo DGN](#)

IF ANY OF THE ABOVE TYPES OF ELEMENTS DO NOT APPLY TO YOUR JOB YOU MUST STILL SPECIFY A VALID DESIGN FILE OR ELSE AN ERROR WILL OCCUR. THE CRITERIA FILES WILL NOT PROCESS AN ELEMENT IF IT DOESN'T EXIST.

**DEFINE VARIABLES**

The typical section uses the following globally define variables. Click on an individual variable for further information.

**DGN File**

[Existing TOPO DGN](#)

**Plot Scale**

[XS Scale](#)

**Redefinable Variables**

The typical section uses the following redefinable variables, which can have different values within the same run based on station range or another parameter. Click on an individual variable for further information. They are listed in the order they have in the run dialog.

**Existing Feature**

<a href="#">_d_ExistingFeatureLineHeight</a>	<a href="#">_s_ShowPavedSurface</a>	<a href="#">_s_ShowCurbandGutter</a>	<a href="#">_d_ExistPavedDitchThick</a>
<a href="#">_s_ShowShoulders</a>	<a href="#">_s_ShowBuildings</a>	<a href="#">_d_ExistPavtThick</a>	<a href="#">_d_ExistPavedSurfaceThick</a>
<a href="#">_s_ShowSidewalk</a>	<a href="#">_s_ShowRailroadTracks</a>	<a href="#">_d_ExistShouldThick</a>	<a href="#">_d_ExistCurbGutterThick</a>
<a href="#">_s_ShowPavedDitch</a>	<a href="#">_s_ShowRetainingWall</a>	<a href="#">_d_ExistSidewalkThick</a>	<a href="#">_d_ExistCurbGutterWidth</a>

**Curb Search Distance**

[\\_d\\_CurbSearchDistance](#)

### New Construction Left And Reconstruction Right Typical Section (NLtRRt)


This typical draws cross sections for divided projects where the left side is new [Pavement](#) and the right side is [Reconstruction](#). It works for both rural and urban sections or a combination of the two. For the left shape cluster, it draws both bituminous and concrete new pavement structure. For the right shape cluster, it draws up to two overlay layers and an optional widening with bituminous or concrete pavement using either a "match existing" or "crown correction" approach. It draws bituminous and concrete [Pavement](#), [Rural Shoulders](#), [Curbing With Urban Shoulders \(U1 & U2\)](#), [Standard Side Slopes](#), and [Special Ditches](#).

This typical section resolves rural and or urban [Medians](#) including stepped barrier and retaining wall medians. There are a total of seven types of medians to choose from. The detailed options are covered later in this document.

All dimensions are in master units of feet.

**IMPORTANT:** Set the proposed cross section run "Tolerance" value to 0.01. This is required for the criteria to work correctly.

**IMPORTANT:** Always include the proposed shape clusters in order from left to right. The left shape cluster should always be listed before the right shape cluster.



The rest of this section lists the scanned graphic elements, globally defined variables, and redefinable variables used by this typical section. The appendices, which can be reached through the links in the [Table of Contents](#), give additional information.

**Scanned Graphic Elements**

The typical section scans design file for the following types of graphic elements. Click on an individual type to find out information about which Design and Computation Manager item is used for each item.

**ELEMENT TYPE**

[Right of Way](#)  
[Reconstruction Existing Edge of Pavement](#)  
[Existing Ground](#)  
[Saw Cut](#)  
[Pavement and Shoulder](#)  
[Curb and Gutter](#)  
[Curb](#)  
[Gutter](#)  
[Concrete Barrier Curb and Guardrail](#)  
[Roadside](#)  
[Side Slope and Drainage](#)

**DGN DRAWING FILE**

Right of Way DGN  
Existing TOPO DGN  
Cross-Section DGN  
Proposed Plan DGN  
Proposed Plan DGN  
Proposed Plan DGN  
Proposed Plan DGN  
Proposed Plan DGN  
Proposed Plan DGN  
Proposed Plan DGN  
GEOPAK Lines DGN

IF ANY OF THE ABOVE TYPES OF ELEMENTS DO NOT APPLY TO YOUR JOB YOU MUST STILL SPECIFY A VALID DESIGN FILE OR ELSE AN ERROR WILL OCCUR. THE CRITERIA FILES WILL NOT PROCESS AN ELEMENT IF IT DOESN'T EXIST.

## **DEFINE VARIABLES**

The typical section uses the following globally define variables. Click on an individual variable for further information.

### **DGN File**

[Existing TOPO DGN](#)  
[Right of Way DGN](#)  
[Cross Section DGN](#)  
[Proposed Plan DGN](#)  
[GEOPAK Lines DGN](#)

### **Tapers File**

[Left Tapers File Name](#)  
[Right Tapers File Name](#)

### **Plot Scale**

[XS Scale](#)  
[Plan View Scale](#)  
[Plan View Flow Arrow Scale](#)

### **GPB Element**

[Survey Baseline Name](#)  
[Left Special Ditch Profiles and Right Special Ditch Profiles](#)  
[Left Ditch Alignment and Right Ditch Alignment](#)  
[Left Match Line Profiles and Right Match Line Profiles](#)  
[Left Sidewalk Profiles and Right Sidewalk Profiles](#)  
[Left Interception Special Ditch Profiles and Right Interception Special Ditch Profiles](#)  
[Median Ditch Profiles](#)  
[Ramp Chain Names](#)  
[Match Line Chain Names](#)  
[Left Top of Wall Profiles and Right Top of Wall Profiles](#)  
[Left Top of Footing Profiles and Right Top of Footing Profiles](#)  
[Median Top of Footing Profiles](#)

### Redefinable Variables

The typical section uses the following redefinable variables, which can have different values within the same run based on station range or another parameter. Click on an individual variable for further information. They are listed in the order they have in the run dialog.

#### Right of Way Buffer Width:

[\\_d\\_ROW\\_Buffer\\_Width](#)

#### Pavement Structure

<a href="#">_s_PavementType</a>	<a href="#">_d_PavementLayer3Thick</a>	<a href="#">_d_RockFillBaseThickness</a>
<a href="#">_d_NormalPavementSlope</a>	<a href="#">_d_PavementLayer4Thick</a>	<a href="#">_s_RockFillBaseDaylight</a>
<a href="#">_d_PavementLayer1Thick</a>	<a href="#">_d_Aggbase1Thickness</a>	<a href="#">_s_RockFillBaseDaylightHSS</a>
<a href="#">_d_PavementLayer2Thick</a>	<a href="#">_d_Aggbase2Thickness</a>	<a href="#">_d_CompensatingDepth</a>

#### Underdrain

<a href="#">_s_DrawLeftUnderdrain</a>	<a href="#">_d_UnderdrainHeight</a>	<a href="#">_d_UnderdrainWidth</a>
<a href="#">_s_DrawRightUnderdrain</a>		

#### Reconstruction

<a href="#">_s_OverlayType</a>	<a href="#">_s_OverlayOffsetLocation</a>	<a href="#">_d_OverlayThickness2</a>
<a href="#">_s_WideningSlope</a>	<a href="#">_d_OverlayThickness1</a>	

#### Outside Shoulder

<a href="#">_s_OutsideShoulderType</a>	<a href="#">_d_NormalOutsideShoulderSlope</a>	<a href="#">_d_ShoulderLayer3Thick</a>
<a href="#">_d_OutsideShoulderWidth</a>	<a href="#">_d_ShoulderLayer1Thick</a>	<a href="#">_d_ShoulderLayer4Thick</a>
<a href="#">_d_OutsideShoulderSearchDistance</a>	<a href="#">_d_ShoulderLayer2Thick</a>	<a href="#">_s_ExtensionSlope</a>
<a href="#">_s_LabelShoulderElevations</a>		

#### Median

<a href="#">_s_MedianShoulderType</a>	<a href="#">_s_MedianType</a>	<a href="#">_d_StdMedianDitchDepth</a>
<a href="#">_d_MedianShoulderWidth</a>	<a href="#">_d_MedianSlope1</a>	<a href="#">_d_MedianDitchWidth</a>
<a href="#">_d_MedianShoulderSearchDistance</a>	<a href="#">_d_MedianSlope1Width</a>	<a href="#">_d_PavedMedianThickness</a>
<a href="#">_d_NormalMedianShoulderSlope</a>	<a href="#">_d_MedianSlope2</a>	<a href="#">_d_MaxPavedMedianWidth</a>

**Curb and Gutter**

\_d\_CurbSearchDistance

\_d\_IntegralCurbHeight

\_s\_GutterSlopeInSuper

**U2 Shoulder**

\_d\_U2ShoulderSearchDistance

\_d\_U2ShoulderSlope

\_d\_U2ShoulderAggbaseThickness

\_d\_U2ShoulderWidth

\_d\_U2ShoulderThickness

**Berm and Sidewalk**

\_d\_BermSlope\_Left

\_d\_BermWidth\_Left

\_d\_SidewalkSlope

\_d\_BermSlope\_Right

\_d\_BermWidth\_Right

\_d\_SidewalkThickness

**Standard Ditch**

\_d\_DitchForeSlope1\_Left

\_d\_DitchForeSlope2\_Left

\_d\_DitchWidth\_Left

\_d\_DitchForeSlope1\_Right

\_d\_DitchForeSlope2\_Right

\_d\_DitchWidth\_Right

\_d\_DitchForeSlope1Width\_Left

\_d\_StandardDitchDepth\_Left

\_d\_DitchBackSlope\_Left

\_d\_DitchForeSlope1Width\_Right

\_d\_StandardDitchDepth\_Right

\_d\_DitchBackSlope\_Right

**Fill Slope**

\_d\_FillSlope1\_Left

\_d\_FillSlope1Width\_Left

\_d\_FillSlope2\_Left

\_d\_FillSlope1\_Right

\_d\_FillSlope1Width\_Right

\_d\_FillSlope2\_Right

**Force Closed Slope**

\_s\_LeftForceClosingSlopes

\_d\_LeftForcedCutSlope

\_d\_RightForcedCutSlope

\_s\_RightForceClosingSlopes

\_d\_LeftForcedFillSlope

\_d\_RightForcedFillSlope

**Right of Way Constrained Slope**

\_s\_LeftROWConstrainedSlope

\_s\_RightROWConstrainedSlope

**Special Ditch Label:**

\_s\_SpecialDitchLabel

**Draw Ditches in Plan View:**

[\\_s\\_DrawDitchesInPlanView](#)

**Rock Benching**

[\\_d\\_BenchingBackSlope](#)  
[\\_d\\_BenchWidth](#)

[\\_d\\_BenchHeight](#)

[\\_s\\_TopBenchWidth](#)

**Chain Search Distance**

[\\_d\\_RampChainSearchDistance](#)

[\\_d\\_MatchLineChainSearchDistance](#)

**Entrance**

[\\_d\\_EntrancePadWidth](#)  
[\\_d\\_EntranceVertCurveLength](#)  
[\\_d\\_Max\\_Type1\\_Driveway\\_Slope](#)  
[\\_d\\_Max\\_Type1\\_Roll\\_Over\\_Slope](#)

[\\_d\\_Max\\_Type2\\_Driveway\\_Slope](#)  
[\\_d\\_Max\\_Type2\\_Roll\\_Over\\_Slope](#)  
[\\_d\\_Max\\_Type3\\_Driveway\\_Slope](#)  
[\\_d\\_Max\\_Type3\\_Roll\\_Over\\_Slope](#)

[\\_d\\_Max\\_Type4\\_Driveway\\_Slope](#)  
[\\_d\\_Max\\_Type4\\_Roll\\_Over\\_Slope](#)  
[\\_d\\_Max\\_Type5\\_Driveway\\_Slope](#)  
[\\_d\\_Max\\_Type5\\_Roll\\_Over\\_Slope](#)

**Retaining Wall**

[\\_d\\_DepthBelowProposedGroundInCut](#)  
[\\_d\\_HeightAboveExistGroundInCut](#)  
[\\_d\\_DepthBelowExistGroundInFill](#)  
[\\_d\\_HeightAbovePropGroundInFill](#)  
[\\_d\\_WallWidth](#)

[\\_s\\_WallHeight](#)  
[\\_d\\_BackWallHeightInCut](#)  
[\\_d\\_BackFootingWidth](#)  
[\\_d\\_TotalFootingWidth](#)  
[\\_d\\_FootingThickness](#)

[\\_d\\_KeyOffset](#)  
[\\_d\\_KeyWidth](#)  
[\\_d\\_KeyHeight](#)  
[\\_d\\_AdjacentWallSearchDistance](#)

**Levee and Interception Ditch**

[\\_s\\_LeveeAdjacentToDitch](#)  
[\\_d\\_LeveeHeight](#)

[\\_d\\_LeveeForeslope](#)  
[\\_d\\_LeveeBackslope](#)

[\\_d\\_InterceptionDitchWidth](#)  
[\\_d\\_InterceptionDitchBackslope](#)

**Non-Standard Curb and Gutter**

[\\_d\\_GutterSlope](#)  
[\\_d\\_GutterWidth](#)  
[\\_d\\_CurbFaceWidth](#)

[\\_d\\_TopCurbWidth](#)  
[\\_d\\_CurbHeight](#)

[\\_d\\_GutterThickness](#)  
[\\_d\\_GutterBaseSlope](#)



### New Construction Right And Reconstruction Left Typical Section (NRtRLt)


This typical draws cross sections for divided projects where the right side is new [Pavement](#) and the left side is [Reconstruction](#). It works for both rural and urban sections or a combination of both. For the right shape cluster, it draws both bituminous and concrete new pavement structure. For the left shape cluster, it draws up to two overlay layers and an optional widening with bituminous or concrete pavement using either a "match existing" or "crown correction" approach. It draws bituminous and concrete [Pavement](#), [Rural Shoulders](#), [Curbing With Urban Shoulders \(U1 & U2\)](#), [Standard Side Slopes](#), and [Special Ditches](#).

This typical section resolves rural and or urban [Medians](#) including stepped barrier and retaining wall medians. There are a total of seven types of medians to choose from. The detailed options are covered later in this document.

All dimensions are in master units of feet.

**IMPORTANT:** Set the proposed cross section run "Tolerance" value to 0.01. This is required for the criteria to work correctly.

**IMPORTANT:** Always include the proposed shape clusters in order from left to right. The left shape cluster should always be listed before the right shape cluster.



The rest of this section lists the scanned graphic elements, globally defined variables, and redefinable variables used by this typical section. The appendices, which can be reached through the links in the [Table of Contents](#), give additional information.

**Scanned Graphic Elements**

The typical section scans design file for the following types of graphic elements. Click on an individual type to find out information about which Design and Computation Manager item is used for each item.

**ELEMENT TYPE**

- [Right of Way](#)
- [Reconstruction Existing Edge of Pavement](#)
- [Existing Ground](#)
- [Saw Cut](#)
- [Pavement and Shoulder](#)
- [Curb and Gutter](#)
- [Curb](#)
- [Gutter](#)
- [Concrete Barrier Curb and Guardrail](#)
- [Roadside](#)
- [Side Slope and Drainage](#)

**DGN DRAWING FILE**

- [Right of Way DGN](#)
- [Existing TOPO DGN](#)
- [Cross-Section DGN](#)
- [Proposed Plan DGN](#)
- [Proposed Plan DGN](#)
- [Proposed Plan DGN](#)
- [Proposed Plan DGN](#)
- [Proposed Plan DGN](#)
- [Proposed Plan DGN](#)
- [Proposed Plan DGN](#)
- [GEOPAK Lines DGN](#)

IF ANY OF THE ABOVE TYPES OF ELEMENTS DO NOT APPLY TO YOUR JOB YOU MUST STILL SPECIFY A VALID DESIGN FILE OR ELSE AN ERROR WILL OCCUR. THE CRITERIA FILES WILL NOT PROCESS AN ELEMENT IF IT DOESN'T EXIST.

## **DEFINE VARIABLES**

The typical section uses the following globally define variables. Click on an individual variable for further information.

### **DGN File**

[Existing TOPO DGN](#)  
[Right of Way DGN](#)  
[Cross Section DGN](#)  
[Proposed Plan DGN](#)  
[GEOPAK Lines DGN](#)

### **Tapers File**

[Left Tapers File Name](#)  
[Right Tapers File Name](#)

### **Plot Scale**

[XS Scale](#)  
[Plan View Scale](#)  
[Plan View Flow Arrow Scale](#)

### **GPK Element**

[Survey Baseline Name](#)  
[Left Special Ditch Profiles and Right Special Ditch Profiles](#)  
[Left Ditch Alignment and Right Ditch Alignment](#)  
[Left Match Line Profiles and Right Match Line Profiles](#)  
[Left Sidewalk Profiles and Right Sidewalk Profiles](#)  
[Left Interception Special Ditch Profiles and Right Interception Special Ditch Profiles](#)  
[Median Ditch Profiles](#)  
[Ramp Chain Names](#)  
[Match Line Chain Names](#)  
[Left Top of Wall Profiles and Right Top of Wall Profiles](#)  
[Left Top of Footing Profiles and Right Top of Footing Profiles](#)  
[Median Top of Footing Profiles](#)

### Redefinable Variables

The typical section uses the following redefinable variables, which can have different values within the same run based on station range or another parameter. Click on an individual variable for further information. They are listed in the order they have in the run dialog.

#### Right of Way Buffer Width:

[\\_d\\_ROW\\_Buffer\\_Width](#)

#### Pavement Structure

<a href="#">_s_PavementType</a>	<a href="#">_d_PavementLayer3Thick</a>	<a href="#">_d_RockFillBaseThickness</a>
<a href="#">_d_NormalPavementSlope</a>	<a href="#">_d_PavementLayer4Thick</a>	<a href="#">_s_RockFillBaseDaylight</a>
<a href="#">_d_PavementLayer1Thick</a>	<a href="#">_d_Aggbase1Thickness</a>	<a href="#">_s_RockFillBaseDaylightHSS</a>
<a href="#">_d_PavementLayer2Thick</a>	<a href="#">_d_Aggbase2Thickness</a>	<a href="#">_d_CompensatingDepth</a>

#### Underdrain

<a href="#">_s_DrawLeftUnderdrain</a>	<a href="#">_d_UnderdrainHeight</a>	<a href="#">_d_UnderdrainWidth</a>
<a href="#">_s_DrawRightUnderdrain</a>		

#### Reconstruction

<a href="#">_s_OverlayType</a>	<a href="#">_s_OverlayOffsetLocation</a>	<a href="#">_d_OverlayThickness2</a>
<a href="#">_s_WideningSlope</a>	<a href="#">_d_OverlayThickness1</a>	

#### Outside Shoulder

<a href="#">_s_OutsideShoulderType</a>	<a href="#">_d_NormalOutsideShoulderSlope</a>	<a href="#">_d_ShoulderLayer3Thick</a>
<a href="#">_d_OutsideShoulderWidth</a>	<a href="#">_d_ShoulderLayer1Thick</a>	<a href="#">_d_ShoulderLayer4Thick</a>
<a href="#">_d_OutsideShoulderSearchDistance</a>	<a href="#">_d_ShoulderLayer2Thick</a>	<a href="#">_s_ExtensionSlope</a>
<a href="#">_s_LabelShoulderElevations</a>		

#### Median

<a href="#">_s_MedianShoulderType</a>	<a href="#">_s_MedianType</a>	<a href="#">_d_StdMedianDitchDepth</a>
<a href="#">_d_MedianShoulderWidth</a>	<a href="#">_d_MedianSlope1</a>	<a href="#">_d_MedianDitchWidth</a>
<a href="#">_d_MedianShoulderSearchDistance</a>	<a href="#">_d_MedianSlope1Width</a>	<a href="#">_d_PavedMedianThickness</a>
<a href="#">_d_NormalMedianShoulderSlope</a>	<a href="#">_d_MedianSlope2</a>	<a href="#">_d_MaxPavedMedianWidth</a>

**Curb and Gutter**

\_d\_CurbSearchDistance

\_d\_IntegralCurbHeight

\_s\_GutterSlopeInSuper

**U2 Shoulder**

\_d\_U2ShoulderSearchDistance

\_d\_U2ShoulderSlope

\_d\_U2ShoulderAggbaseThickness

\_d\_U2ShoulderWidth

\_d\_U2ShoulderThickness

**Berm and Sidewalk**

\_d\_BermSlope\_Left

\_d\_BermWidth\_Left

\_d\_SidewalkSlope

\_d\_BermSlope\_Right

\_d\_BermWidth\_Right

\_d\_SidewalkThickness

**Standard Ditch**

\_d\_DitchForeSlope1\_Left

\_d\_DitchForeSlope2\_Left

\_d\_DitchWidth\_Left

\_d\_DitchForeSlope1\_Right

\_d\_DitchForeSlope2\_Right

\_d\_DitchWidth\_Right

\_d\_DitchForeSlope1Width\_Left

\_d\_StandardDitchDepth\_Left

\_d\_DitchBackSlope\_Left

\_d\_DitchForeSlope1Width\_Right

\_d\_StandardDitchDepth\_Right

\_d\_DitchBackSlope\_Right

**Fill Slope**

\_d\_FillSlope1\_Left

\_d\_FillSlope1Width\_Left

\_d\_FillSlope2\_Left

\_d\_FillSlope1\_Right

\_d\_FillSlope1Width\_Right

\_d\_FillSlope2\_Right

**Force Closed Slope**

\_s\_LeftForceClosingSlopes

\_d\_LeftForcedCutSlope

\_d\_RightForcedCutSlope

\_s\_RightForceClosingSlopes

\_d\_LeftForcedFillSlope

\_d\_RightForcedFillSlope

**Right of Way Constrained Slope**

\_s\_LeftROWConstrainedSlope

\_s\_RightROWConstrainedSlope

**Special Ditch Label:**

\_s\_SpecialDitchLabel

**Draw Ditches in Plan View:**

[\\_s\\_DrawDitchesInPlanView](#)

**Rock Benching**

[\\_d\\_BenchingBackSlope](#)  
[\\_d\\_BenchWidth](#)

[\\_d\\_BenchHeight](#)

[\\_s\\_TopBenchWidth](#)

**Chain Search Distance**

[\\_d\\_RampChainSearchDistance](#)

[\\_d\\_MatchLineChainSearchDistance](#)

**Entrance**

[\\_d\\_EntrancePadWidth](#)  
[\\_d\\_EntranceVertCurveLength](#)  
[\\_d\\_Max\\_Type1\\_Driveway\\_Slope](#)  
[\\_d\\_Max\\_Type1\\_Roll\\_Over\\_Slope](#)

[\\_d\\_Max\\_Type2\\_Driveway\\_Slope](#)  
[\\_d\\_Max\\_Type2\\_Roll\\_Over\\_Slope](#)  
[\\_d\\_Max\\_Type3\\_Driveway\\_Slope](#)  
[\\_d\\_Max\\_Type3\\_Roll\\_Over\\_Slope](#)

[\\_d\\_Max\\_Type4\\_Driveway\\_Slope](#)  
[\\_d\\_Max\\_Type4\\_Roll\\_Over\\_Slope](#)  
[\\_d\\_Max\\_Type5\\_Driveway\\_Slope](#)  
[\\_d\\_Max\\_Type5\\_Roll\\_Over\\_Slope](#)

**Retaining Wall**

[\\_d\\_DepthBelowProposedGroundInCut](#)  
[\\_d\\_HeightAboveExistGroundInCut](#)  
[\\_d\\_DepthBelowExistGroundInFill](#)  
[\\_d\\_HeightAbovePropGroundInFill](#)  
[\\_d\\_WallWidth](#)

[\\_s\\_WallHeight](#)  
[\\_d\\_BackWallHeightInCut](#)  
[\\_d\\_BackFootingWidth](#)  
[\\_d\\_TotalFootingWidth](#)  
[\\_d\\_FootingThickness](#)

[\\_d\\_KeyOffset](#)  
[\\_d\\_KeyWidth](#)  
[\\_d\\_KeyHeight](#)  
[\\_d\\_AdjacentWallSearchDistance](#)

**Levee and Interception Ditch**

[\\_s\\_LeveeAdjacentToDitch](#)  
[\\_d\\_LeveeHeight](#)

[\\_d\\_LeveeForeslope](#)  
[\\_d\\_LeveeBackslope](#)

[\\_d\\_InterceptionDitchWidth](#)  
[\\_d\\_InterceptionDitchBackslope](#)

**Non-Standard Curb and Gutter**

[\\_d\\_GutterSlope](#)  
[\\_d\\_GutterWidth](#)  
[\\_d\\_CurbFaceWidth](#)

[\\_d\\_TopCurbWidth](#)  
[\\_d\\_CurbHeight](#)


[\\_d\\_GutterThickness](#)  
[\\_d\\_GutterBaseSlope](#)

## Proposed Paved Ditches (PDitch)

This typical section searches the proposed plan view for pairs of lines designating locations of paved ditches. There are three requirements that must be met for this typical section to function. The proposed cross sections except for the paved ditches must be completed. Secondly, the inside and outside edges of the paved ditch must be drawn in the proposed plan view. Lastly, there must be an even number of edges of paved ditches drawn. No ditches are drawn if an odd number of plan view paved ditch edges are found crossing the pattern line for the current cross section.

**IMPORTANT:** Set the proposed cross section run "Tolerance" value to 0.01. This is required for the criteria to work correctly.

Paved Ditches  
Undivided or Divided  
New Construction or Reconstruction



The rest of this section lists the scanned graphic elements, globally defined variables, and redefinable variable used by this typical section. The appendices, which can be reached through the links in the [Table of Contents](#), give additional information.

# Scanned Graphic Elements

The typical section scans a design file for the following types of graphic elements. Click on an individual type to find out information about which Design and Computation Manager item is used for each item.

## ELEMENT TYPE

[Paved Ditch](#)

## DGN DRAWING FILE

Proposed Plan DGN and Cross Section DGN

IF ANY OF THE ABOVE TYPES OF ELEMENTS DO NOT APPLY TO YOUR JOB YOU MUST STILL SPECIFY A VALID DESIGN FILE OR ELSE AN ERROR WILL OCCUR. THE CRITERIA FILES WILL NOT PROCESS AN ELEMENT IF IT DOESN'T EXIST.

# DEFINE VARIABLES

The typical section uses the following globally define variables. Click on an individual variable for further information.

## **DGN File**

[Cross Section DGN](#)

[Proposed Plan DGN](#)

# Redefinable Variables

The typical section uses the following redefinable variable, which can have different values within the same run based on station range or another parameter.

## **Proposed Paved Ditch Thickness**

This is the total thickness of the proposed paved ditches from the top of proposed ground to the bottom of the paved ditch.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    \_d\_PavedDitchThickness = 6/12
}
```



### Trace Existing Sub Layers (SubLay)

This typical section traces the existing sub layers while the sub layer is below existing ground. This is necessary when the sub layers were generated from a digital terrain model and some of the sub layer lines are drawn above the existing ground line in the cross section view. It draws a new line on top of the existing sub layer but it will only draw the line while the sub layer remains below the existing ground. Once these new lines are drawn, the original sub layer lines can be deleted and the newly generated lines can be utilized for earthwork purposes. The following sub layers are searched and traced if present:

Top of Rock  
Unsuitable Material

Sub Layer 1  
Sub Layer 2


Sub Layer 3  
Sub Layer 4

The typical section also optionally draws a top of rock line 100 feet below existing ground on those cross sections without a top of rock line when the line is present on only some of the cross sections.

**IMPORTANT:** Set the proposed cross section run "Tolerance" value to 0.01. This is required for the criteria to work correctly.

### Existing Sublayer Tracing

### Traces Sublayers When Below Ex Ground



The rest of this section lists the scanned graphic elements, globally defined variable, and redefinable variable used by this typical section. The appendices, which can be reached through the links in the [Table of Contents](#), give additional information.

## Scanned Graphic Elements

The typical section scans a design file for the following types of graphic elements. Click on an individual type to find out information about which Design and Computation Manager item is used for each item.

### ELEMENT TYPE

[Existing Ground](#)  
[Special Sub Layers](#)

### DGN DRAWING FILE

Cross Section DGN  
Cross Section DGN

IF ANY OF THE ABOVE TYPES OF ELEMENTS DO NOT APPLY TO YOUR JOB YOU MUST STILL SPECIFY A VALID DESIGN FILE OR ELSE AN ERROR WILL OCCUR. THE CRITERIA FILES WILL NOT PROCESS AN ELEMENT IF IT DOESN'T EXIST.

## DEFINE VARIABLES

The typical section uses the following globally define variable. Click on it for further information.

### **DGN File**

[Cross Section DGN](#)

## Redefinable Variables

The typical section uses the following redefinable variable, which can have different values within the same run based on station range or another parameter.

### **Draw Top of Rock**

Controls whether to draw the top of rock line when no top of rock is found on the current cross section. This has been implemented to allow the user to run earthwork when rock is present on some, but not all, of the cross sections. If rock is to be considered, a top of rock line must reside on ALL cross sections. If the variable is set to ^Yes^ and a rock line is NOT found on a section, a top of rock line will be drawn 100 feet below the existing ground. The options are ^Yes^ or ^No^. The carets "^" are required.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
  \_s\_DrawRockLine = ^Yes^
}
```

## Undivided New Pavement Typical Section (UNPavt)


This typical section draws proposed cross sections for undivided new pavement projects. It works for both rural and urban sections, or a combination of the two. It draws bituminous and concrete [Pavement](#), [Rural Shoulders](#), [Curbing With Urban Shoulders \(U1 & U2\)](#), [Standard Side Slopes](#), and [Special Ditches](#).

This typical section is for new construction only. All dimensions are in master units of feet.

**IMPORTANT:** Set the proposed cross section run "Tolerance" value to 0.01. This is required for the criteria to work correctly.

Undivided New Construction

Rural or Urban



Bituminous Or Concrete Pavement

Shoulders, Curb and Gutter, or Both

The rest of this section lists the scanned graphic elements, globally defined variables, and redefinable variables used by this typical section. The appendices, which can be reached through the links in the [Table of Contents](#), give additional information.

**Scanned Graphic Elements**

The typical section scans design file for the following types of graphic elements. Click on an individual type to find out information about which Design and Computation Manager item is used for each item.

**ELEMENT TYPE**

- [Right of Way](#)
- [Existing Ground](#)
- [Pavement and Shoulder](#)
- [Curb and Gutter](#)
- [Curb](#)
- [Gutter](#)
- [Concrete Barrier Curb and Guardrail](#)
- [Roadside](#)
- [Side Slope and Drainage](#)

**DGN DRAWING FILE**

- Right of Way DGN
- Cross-Section DGN
- Proposed Plan DGN
- Proposed Plan DGN
- Proposed Plan DGN
- Proposed Plan DGN
- Proposed Plan DGN
- Proposed Plan DGN
- GEOPAK Lines DGN

IF ANY OF THE ABOVE TYPES OF ELEMENTS DO NOT APPLY TO YOUR JOB YOU MUST STILL SPECIFY A VALID DESIGN FILE OR ELSE AN ERROR WILL OCCUR. THE CRITERIA FILES WILL NOT PROCESS AN ELEMENT IF IT DOESN'T EXIST.

## **DEFINE VARIABLES**

The typical section uses the following globally define variables. Click on an individual variable for further information.

### **DGN File**

[Right of Way DGN](#)  
[Cross Section DGN](#)  
[Proposed Plan DGN](#)  
[GEOPAK Lines DGN](#)

### **Tapers File**

[Left Tapers File Name](#)  
[Right Tapers File Name](#)

### **Plot Scale**

[XS Scale](#)  
[Plan View Scale](#)  
[Plan View Flow Arrow Scale](#)

### **GPK Element**

[Survey Baseline Name](#)  
[Left Special Ditch Profiles and Right Special Ditch Profiles](#)  
[Left Ditch Alignment and Right Ditch Alignment](#)  
[Left Match Line Profiles and Right Match Line Profiles](#)  
[Left Sidewalk Profiles and Right Sidewalk Profiles](#)  
[Left Interception Special Ditch Profiles and Right Interception Special Ditch Profiles](#)  
[Ramp Chain Names](#)  
[Match Line Chain Names](#)  
[Left Top of Wall Profiles and Right Top of Wall Profiles](#)  
[Left Top of Footing Profiles and Right Top of Footing Profiles](#)

### Redefinable Variables

The typical section uses the following redefinable variables, which can have different values within the same run based on station range or another user-defined parameter. Click on an individual variable for further information. They are listed in the order they have in the run dialog box.

#### Right of Way Buffer Width:

[\\_d\\_ROW\\_Buffer\\_Width](#)

#### Pavement Structure

<a href="#">_s_PavementType</a>	<a href="#">_d_PavementLayer3Thick</a>	<a href="#">_d_RockFillBaseThickness</a>
<a href="#">_d_NormalPavementSlope</a>	<a href="#">_d_PavementLayer4Thick</a>	<a href="#">_s_RockFillBaseDaylight</a>
<a href="#">_d_PavementLayer1Thick</a>	<a href="#">_d_Aggbase1Thickness</a>	<a href="#">_s_RockFillBaseDaylightHSS</a>
<a href="#">_d_PavementLayer2Thick</a>	<a href="#">_d_Aggbase2Thickness</a>	<a href="#">_d_CompensatingDepth</a>

#### Underdrain

<a href="#">_s_DrawLeftUnderdrain</a>	<a href="#">_d_UnderdrainHeight</a>	<a href="#">_d_UnderdrainWidth</a>
<a href="#">_s_DrawRightUnderdrain</a>		

#### Outside Shoulder

<a href="#">_s_OutsideShoulderType</a>	<a href="#">_d_NormalOutsideShoulderSlope</a>	<a href="#">_d_ShoulderLayer3Thick</a>
<a href="#">_d_OutsideShoulderWidth</a>	<a href="#">_d_ShoulderLayer1Thick</a>	<a href="#">_d_ShoulderLayer4Thick</a>
<a href="#">_d_OutsideShoulderSearchDistance</a>	<a href="#">_d_ShoulderLayer2Thick</a>	<a href="#">_s_ExtensionSlope</a>
<a href="#">_s_LabelShoulderElevations</a>		

#### Curb and Gutter

<a href="#">_d_CurbSearchDistance</a>	<a href="#">_d_IntegralCurbHeight</a>	<a href="#">_s_GutterSlopeInSuper</a>
---------------------------------------	---------------------------------------	---------------------------------------

#### U2 Shoulder

<a href="#">_d_U2ShoulderSearchDistance</a>	<a href="#">_d_U2ShoulderSlope</a>	<a href="#">_d_U2ShoulderAggbaseThickness</a>
<a href="#">_d_U2ShoulderWidth</a>	<a href="#">_d_U2ShoulderThickness</a>	

**Berm and Sidewalk**

<a href="#">_d_BermSlope_Left</a>	<a href="#">_d_BermWidth_Left</a>	<a href="#">_d_SidewalkSlope</a>
<a href="#">_d_BermSlope_Right</a>	<a href="#">_d_BermWidth_Right</a>	<a href="#">_d_SidewalkThickness</a>

**Standard Ditch**

<a href="#">_d_DitchForeSlope1_Left</a>	<a href="#">_d_DitchForeSlope2_Left</a>	<a href="#">_d_DitchWidth_Left</a>
<a href="#">_d_DitchForeSlope1_Right</a>	<a href="#">_d_DitchForeSlope2_Right</a>	<a href="#">_d_DitchWidth_Right</a>
<a href="#">_d_DitchForeSlope1Width_Left</a>	<a href="#">_d_StandardDitchDepth_Left</a>	<a href="#">_d_DitchBackSlope_Left</a>
<a href="#">_d_DitchForeSlope1Width_Right</a>	<a href="#">_d_StandardDitchDepth_Right</a>	<a href="#">_d_DitchBackSlope_Right</a>

**Fill Slope**

<a href="#">_d_FillSlope1_Left</a>	<a href="#">_d_FillSlope1Width_Left</a>	<a href="#">_d_FillSlope2_Left</a>
<a href="#">_d_FillSlope1_Right</a>	<a href="#">_d_FillSlope1Width_Right</a>	<a href="#">_d_FillSlope2_Right</a>

**Force Closed Slope**

<a href="#">_s_LeftForceClosingSlopes</a>	<a href="#">_d_LeftForcedCutSlope</a>	<a href="#">_d_RightForcedCutSlope</a>
<a href="#">_s_RightForceClosingSlopes</a>	<a href="#">_d_LeftForcedFillSlope</a>	<a href="#">_d_RightForcedFillSlope</a>

**Right of Way Constrained Slope**

<a href="#">_s_LeftROWConstrainedSlope</a>	<a href="#">_s_RightROWConstrainedSlope</a>
--	---

**Special Ditch Label:**

<a href="#">_s_SpecialDitchLabel</a>
--------------------------------------

**Draw Ditches in Plan View:**

<a href="#">_s_DrawDitchesInPlanView</a>
--

**Rock Benching**

<a href="#">_d_BenchingBackSlope</a>	<a href="#">_d_BenchHeight</a>	<a href="#">_s_TopBenchWidth</a>
<a href="#">_d_BenchWidth</a>		

**Chain Search Distance**

\_d\_RampChainSearchDistance

\_d\_MatchLineChainSearchDistance

**Entrance**

\_d\_EntrancePadWidth

\_d\_Max\_Type2\_Driveway\_Slope

\_d\_Max\_Type4\_Driveway\_Slope

\_d\_EntranceVertCurveLength

\_d\_Max\_Type2\_Roll\_Over\_Slope

\_d\_Max\_Type4\_Roll\_Over\_Slope

\_d\_Max\_Type1\_Driveway\_Slope

\_d\_Max\_Type3\_Driveway\_Slope

\_d\_Max\_Type5\_Driveway\_Slope

\_d\_Max\_Type1\_Roll\_Over\_Slope

\_d\_Max\_Type3\_Roll\_Over\_Slope

\_d\_Max\_Type5\_Roll\_Over\_Slope

**Retaining Wall**

\_d\_DepthBelowProposedGroundInCut

\_s\_WallHeight

\_d\_KeyOffset

\_d\_HeightAboveExistGroundInCut

\_d\_BackWallHeightInCut

\_d\_KeyWidth

\_d\_DepthBelowExistGroundInFill

\_d\_BackFootingWidth

\_d\_KeyHeight

\_d\_HeightAbovePropGroundInFill

\_d\_TotalFootingWidth

\_d\_AdjacentWallSearchDistance

\_d\_WallWidth

\_d\_FootingThickness

**Levee and Interception Ditch**

\_s\_LeveeAdjacentToDitch

\_d\_LeveeForeslope

\_d\_InterceptionDitchWidth

\_d\_LeveeHeight

\_d\_LeveeBackslope

\_d\_InterceptionDitchBackslope

**Non-Standard Curb and Gutter**

\_d\_GutterSlope

\_d\_TopCurbWidth

\_d\_GutterThickness

\_d\_GutterWidth

\_d\_CurbHeight

\_d\_GutterBaseSlope

\_d\_CurbFaceWidth




## Undivided Reconstruction Typical Section (URECon)

This typical section draws proposed cross sections for undivided [Reconstruction](#) projects. It works for both rural and urban sections or a combination of the two. It draws up to two overlay layers and an optional widening with bituminous or concrete [Pavement](#) using either a "match existing" or "crown correction" approach. It draws bituminous and concrete [Pavement](#), [Rural Shoulders](#), [Curbing With Urban Shoulders \(U1 & U2\)](#), [Standard Side Slopes](#), and [Special Ditches](#).

This typical section is for reconstruction only. All dimensions are in master units of feet.

**IMPORTANT:** Set the proposed cross section run "Tolerance" value to 0.01. This is required for the criteria to work correctly.

Divided Overlay / Reconstruction  
Rural or Urban



Bituminous Overlay With Optional Widening  
Crown Correction  
Match Existing  
Shoulders, Curb and Gutter, or Both

The rest of this section lists the scanned graphic elements, globally defined variables, and redefinable variables used by this typical section. The appendices, which can be reached through the links in the [Table of Contents](#), give additional information.

**Scanned Graphic Elements**

The typical section scans design file for the following types of graphic elements. Click on an individual type to find out information about which Design and Computation Manager item is used for each item.

**ELEMENT TYPE**

[Right of Way](#)  
[Reconstruction Existing Edge of Pavement](#)  
[Existing Ground](#)  
[Saw Cut](#)  
[Pavement and Shoulder](#)  
[Curb and Gutter](#)  
[Curb](#)  
[Gutter](#)  
[Concrete Barrier Curb and Guardrail](#)  
[Roadside](#)  
[Side Slope and Drainage](#)

**DGN DRAWING FILE**

Right of Way DGN  
Existing TOPO DGN  
Cross-Section DGN  
Proposed Plan DGN  
Proposed Plan DGN  
Proposed Plan DGN  
Proposed Plan DGN  
Proposed Plan DGN  
Proposed Plan DGN  
Proposed Plan DGN  
GEOPAK Lines DGN

IF ANY OF THE ABOVE TYPES OF ELEMENTS DO NOT APPLY TO YOUR JOB YOU MUST STILL SPECIFY A VALID DESIGN FILE OR ELSE AN ERROR WILL OCCUR. THE CRITERIA FILES WILL NOT PROCESS AN ELEMENT IF IT DOESN'T EXIST.

## **DEFINE VARIABLES**

The typical section uses the following globally define variables. Click on an individual variable for further information.

### **DGN File**

[Existing TOPO DGN](#)  
[Right of Way DGN](#)  
[Cross Section DGN](#)  
[Proposed Plan DGN](#)  
[GEOPAK Lines DGN](#)

### **Tapers File**

[Left Tapers File Name](#)  
[Right Tapers File Name](#)

### **Plot Scale**

[XS Scale](#)  
[Plan View Scale](#)  
[Plan View Flow Arrow Scale](#)

### **GPB Element**

[Survey Baseline Name](#)  
[Left Special Ditch Profiles and Right Special Ditch Profiles](#)  
[Left Ditch Alignment and Right Ditch Alignment](#)  
[Left Match Line Profiles and Right Match Line Profiles](#)  
[Left Sidewalk Profiles and Right Sidewalk Profiles](#)  
[Left Interception Special Ditch Profiles and Right Interception Special Ditch Profiles](#)  
[Ramp Chain Names](#)  
[Match Line Chain Names](#)  
[Left Top of Wall Profiles and Right Top of Wall Profiles](#)  
[Left Top of Footing Profiles and Right Top of Footing Profiles](#)

### Redefinable Variables

The typical section uses the following redefinable variables, which can have different values within the same run based on station range or another parameter. Click on an individual variable for further information. They are listed in the order they have in the run dialog.

#### Right of Way Buffer Width:

[\\_d\\_ROW\\_Buffer\\_Width](#)

#### Pavement Structure

<a href="#">_s_PavementType</a>	<a href="#">_d_PavementLayer3Thick</a>	<a href="#">_d_RockFillBaseThickness</a>
<a href="#">_d_NormalPavementSlope</a>	<a href="#">_d_PavementLayer4Thick</a>	<a href="#">_s_RockFillBaseDaylight</a>
<a href="#">_d_PavementLayer1Thick</a>	<a href="#">_d_Aggbase1Thickness</a>	<a href="#">_s_RockFillBaseDaylightHSS</a>
<a href="#">_d_PavementLayer2Thick</a>	<a href="#">_d_Aggbase2Thickness</a>	<a href="#">_d_CompensatingDepth</a>

#### Underdrain

<a href="#">_s_DrawLeftUnderdrain</a>	<a href="#">_d_UnderdrainHeight</a>	<a href="#">_d_UnderdrainWidth</a>
<a href="#">_s_DrawRightUnderdrain</a>		

#### Reconstruction

<a href="#">_s_OverlayType</a>	<a href="#">_s_OverlayOffsetLocation</a>	<a href="#">_d_OverlayThickness2</a>
<a href="#">_s_WideningSlope</a>	<a href="#">_d_OverlayThickness1</a>	

#### Outside Shoulder

<a href="#">_s_OutsideShoulderType</a>	<a href="#">_d_NormalOutsideShoulderSlope</a>	<a href="#">_d_ShoulderLayer3Thick</a>
<a href="#">_d_OutsideShoulderWidth</a>	<a href="#">_d_ShoulderLayer1Thick</a>	<a href="#">_d_ShoulderLayer4Thick</a>
<a href="#">_d_OutsideShoulderSearchDistance</a>	<a href="#">_d_ShoulderLayer2Thick</a>	<a href="#">_s_ExtensionSlope</a>
<a href="#">_s_LabelShoulderElevations</a>		

#### Curb and Gutter

<a href="#">_d_CurbSearchDistance</a>	<a href="#">_d_IntegralCurbHeight</a>	<a href="#">_s_GutterSlopeInSuper</a>
---------------------------------------	---------------------------------------	---------------------------------------

**U2 Shoulder**

<a href="#">_d_U2ShoulderSearchDistance</a>	<a href="#">_d_U2ShoulderSlope</a>	<a href="#">_d_U2ShoulderAggbaseThickness</a>
<a href="#">_d_U2ShoulderWidth</a>	<a href="#">_d_U2ShoulderThickness</a>	

**Berm and Sidewalk**

<a href="#">_d_BermSlope_Left</a>	<a href="#">_d_BermWidth_Left</a>	<a href="#">_d_SidewalkSlope</a>
<a href="#">_d_BermSlope_Right</a>	<a href="#">_d_BermWidth_Right</a>	<a href="#">_d_SidewalkThickness</a>

**Standard Ditch**

<a href="#">_d_DitchForeSlope1_Left</a>	<a href="#">_d_DitchForeSlope2_Left</a>	<a href="#">_d_DitchWidth_Left</a>
<a href="#">_d_DitchForeSlope1_Right</a>	<a href="#">_d_DitchForeSlope2_Right</a>	<a href="#">_d_DitchWidth_Right</a>
<a href="#">_d_DitchForeSlope1Width_Left</a>	<a href="#">_d_StandardDitchDepth_Left</a>	<a href="#">_d_DitchBackSlope_Left</a>
<a href="#">_d_DitchForeSlope1Width_Right</a>	<a href="#">_d_StandardDitchDepth_Right</a>	<a href="#">_d_DitchBackSlope_Right</a>

**Fill Slope**

<a href="#">_d_FillSlope1_Left</a>	<a href="#">_d_FillSlope1Width_Left</a>	<a href="#">_d_FillSlope2_Left</a>
<a href="#">_d_FillSlope1_Right</a>	<a href="#">_d_FillSlope1Width_Right</a>	<a href="#">_d_FillSlope2_Right</a>

**Force Closed Slope**

<a href="#">_s_LeftForceClosingSlopes</a>	<a href="#">_d_LeftForcedCutSlope</a>	<a href="#">_d_RightForcedCutSlope</a>
<a href="#">_s_RightForceClosingSlopes</a>	<a href="#">_d_LeftForcedFillSlope</a>	<a href="#">_d_RightForcedFillSlope</a>

**Right of Way Constrained Slope**

<a href="#">_s_LeftROWConstrainedSlope</a>	<a href="#">_s_RightROWConstrainedSlope</a>
--	---

**Special Ditch Label:**

<a href="#">_s_SpecialDitchLabel</a>
--------------------------------------

**Draw Ditches in Plan View:**

<a href="#">_s_DrawDitchesInPlanView</a>
--

**Rock Benching**

<a href="#">_d_BenchingBackSlope</a>	<a href="#">_d_BenchHeight</a>
<a href="#">_d_BenchWidth</a>	<a href="#">_s_TopBenchWidth</a>

**Chain Search Distance**

<a href="#">_d_RampChainSearchDistance</a>	<a href="#">_d_MatchLineChainSearchDistance</a>
--	---

**Entrance**

<a href="#">_d_EntrancePadWidth</a>	<a href="#">_d_Max_Type2_Driveway_Slope</a>	<a href="#">_d_Max_Type4_Driveway_Slope</a>
<a href="#">_d_EntranceVertCurveLength</a>	<a href="#">_d_Max_Type2_Roll_Over_Slope</a>	<a href="#">_d_Max_Type4_Roll_Over_Slope</a>
<a href="#">_d_Max_Type1_Driveway_Slope</a>	<a href="#">_d_Max_Type3_Driveway_Slope</a>	<a href="#">_d_Max_Type5_Driveway_Slope</a>
<a href="#">_d_Max_Type1_Roll_Over_Slope</a>	<a href="#">_d_Max_Type3_Roll_Over_Slope</a>	<a href="#">_d_Max_Type5_Roll_Over_Slope</a>

**Retaining Wall**

<a href="#">_d_DepthBelowProposedGroundInCut</a>	<a href="#">_s_WallHeight</a>	<a href="#">_d_KeyOffset</a>
<a href="#">_d_HeightAboveExistGroundInCut</a>	<a href="#">_d_BackWallHeightInCut</a>	<a href="#">_d_KeyWidth</a>
<a href="#">_d_DepthBelowExistGroundInFill</a>	<a href="#">_d_BackFootingWidth</a>	<a href="#">_d_KeyHeight</a>
<a href="#">_d_HeightAbovePropGroundInFill</a>	<a href="#">_d_TotalFootingWidth</a>	<a href="#">_d_AdjacentWallSearchDistance</a>
<a href="#">_d_WallWidth</a>	<a href="#">_d_FootingThickness</a>	

**Levee and Interception Ditch**

<a href="#">_s_LeveeAdjacentToDitch</a>	<a href="#">_d_LeveeForeslope</a>	<a href="#">_d_InterceptionDitchWidth</a>
<a href="#">_d_LeveeHeight</a>	<a href="#">_d_LeveeBackslope</a>	<a href="#">_d_InterceptionDitchBackslope</a>

**Non-Standard Curb and Gutter**

<a href="#">_d_GutterSlope</a>	<a href="#">_d_TopCurbWidth</a>	<a href="#">_d_GutterThickness</a>
<a href="#">_d_GutterWidth</a>	<a href="#">_d_CurbHeight</a>	<a href="#">_d_GutterBaseSlope</a>
<a href="#">_d_CurbFaceWidth</a>		

Appendix 1
Scanned Graphic Elements

The criteria search for the following graphic elements in design files. They are grouped in categories based on how the elements are used so that you may be able to find the information quickly without having to look at each individual entry. These elements must be drawn in the designated file using the Design and Computation Manager item shown in the D&C Path list for each element.

Right of Way

Used by Draw Right of Way Lines ([DrwROW](#)) & all pavement typ. sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

ELEMENT	DGN DRAWING FILE	REQUIREMENT
Existing Right of Way		
D&C Path = Design Standards/RW/RW Line Exist	Right of Way DGN	Optional
Existing Right of Way Temporary Access		
D&C Path = Design Standards/RW/RW Temp Acc Ex	Right of Way DGN	Optional
Existing Right of Way Controlled Access		
D&C Path = Design Standards/RW/RW Cont Acc Ex	Right of Way DGN	Optional
Existing Right of Way No Right of Access		
D&C Path = Design Standards/RW/RW No Rt Ac Ex	Right of Way DGN	Optional
Proposed Right of Way		
D&C Path = Design Standards/RW/RW Line New	Right of Way DGN	Optional
Proposed Right of Way Temporary Access		
D&C Path = Design Standards/RW/RW Temp Access	Right of Way DGN	Optional
Proposed Right of Way Controlled Access		
D&C Path = Design Standards/RW/RW Cont Access	Right of Way DGN	Optional
Proposed Right of Way No Right of Access		
D&C Path = Design Standards/RW/RW No Rt Access	Right of Way DGN	Optional
Proposed Right of Way Permanent Easement		
D&C Path = Design Standards/RW/Easement Perm	Right of Way DGN	Optional
Proposed Right of Way Temporary Easement		
D&C Path = Design Standards/RW/Easement Temp	Right of Way DGN	Optional

### Reconstruction Existing Edge of Pavement

Used by reconstruction pavement typical sections ([DRecon](#), [NLtRRt](#), [NRtRLt](#), & [URECon](#)).

<u>ELEMENT</u>	<u>DGN DRAWING FILE</u>	<u>REQUIREMENT</u>
<b>Existing Edge of Pavement</b> D&C Path = Design Standards/Roadway/EOP Existing	Existing Topo DGN	<b>Required</b>

### Draw Existing Features

Used by Existing Features typical section ([ExFeat](#)).

<u>ELEMENT</u>	<u>DGN DRAWING FILE</u>	<u>REQUIREMENT</u>	<u>Link</u>
<b>Existing Edge of Pavement</b> D&C Path = Design Standards/Roadway/EOP Existing	Existing Topo DGN	Optional	<a href="#">Appendix 6 Reconstruction Existing Pavement</a>
<b>Existing Paved Shoulder</b> D&C Path = Design Standards/Roadway/EOS Existing	Existing Topo DGN	Optional	<a href="#">Existing Paved Shoulder</a>
<b>Existing Sidewalk</b> D&C Path = Design Standards/Roadside/Sidewalk Exist	Existing Topo DGN	Optional	<a href="#">Existing Sidewalks</a>
<b>Existing Paved Ditch</b> D&C Path = Design Standards/Drainage/Paved Ditch Ex	Existing Topo DGN	Optional	<a href="#">Existing Paved Ditches</a>
<b>Existing Paved Surface</b> D&C Path = Design Standards/Roadway/Edge of Surface	Existing Topo DGN	Optional	<a href="#">Existing Paved Surfaces</a>
<b>Existing Building</b> D&C Path = Design Standards/Property/Building	Existing Topo DGN	Optional	<a href="#">Existing Buildings</a>
<b>Existing Railroad</b> D&C Path = Design Standards/Utilities/Railroad Track	Existing Topo DGN	Optional	<a href="#">Existing Railroads</a>
<b>Existing Wall</b> D&C Path = Design Standards/Safety and Structures/Exist Retaining	Existing Topo DGN	Optional	<a href="#">Existing Wall</a>
<b>Existing Curb</b> D&C Path = Design Standards/Roadway/Curb Existing	Existing Topo DGN	Optional	<a href="#">Existing Curb and Gutter</a>



### Existing Ground

Used by Trace Existing Sub Layers ([SubLay](#)) & all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

<u>ELEMENT</u>	<u>DGN DRAWING FILE</u>	<u>REQUIREMENT</u>
<b>Existing Ground</b> D&C Path = Design Standards/Cross Sections/Existing Surfaces/Ground Existing	Cross-Section DGN	<b>Required</b>
<b>Existing Top of Rock</b> D&C Path = Design Standards/Cross Sections/Existing Surfaces/Rock Top	Cross-Section DGN	Optional
<b>Existing Bottom of Rock</b> D&C Path = Design Standards/Cross Sections/Existing Surfaces/Rock Bottom	Cross-Section DGN	Optional

### Special Sub Layers

Used by Trace Existing Sub Layers typical section ([SubLay](#)).

<u>ELEMENT</u>	<u>DGN DRAWING FILE</u>	<u>REQUIREMENT</u>
<b>Existing Sublayer 1</b> D&C Path = Design Standards/Cross Sections/Existing Surfaces/Sub Layer 1	Cross-Section DGN	Optional
<b>Existing Sublayer 2</b> D&C Path = Design Standards/Cross Sections/Existing Surfaces/Sub Layer 2	Cross-Section DGN	Optional
<b>Existing Sublayer 3</b> D&C Path = Design Standards/Cross Sections/Existing Surfaces/Sub Layer 3	Cross-Section DGN	Optional
<b>Existing Sublayer 4</b> D&C Path = Design Standards/Cross Sections/Existing Surfaces/Sub Layer 4	Cross-Section DGN	Optional

### Saw Cut

Used by reconstruction pavement typical sections ([DRecon](#), [NLtRRt](#), [NRtRLt](#), & [URECon](#)). Go to: [Appendix 6 Reconstruction](#)

<u>ELEMENT</u>	<u>DGN DRAWING FILE</u>	<u>REQUIREMENT</u>
<b>Proposed Saw Cut</b> D&C Path = Design Standards/Roadway/Saw Cut	Proposed Plan DGN	Optional

## Pavement and Shoulder

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

<u>ELEMENT</u>	<u>DGN DRAWING FILE</u>	<u>REQUIREMENT</u>	<u>Link</u>
<b>Edge of Pavement</b> D&C Path = Design Standards/Roadway/EOP New	Proposed Plan DGN	<b>Required</b>	<a href="#">Pavement</a> Details
<b>Concrete Shoulder</b> D&C Path = Design Standards/Roadway/EOS New Conc.	Proposed Plan DGN	Optional	
<b>Bituminous Shoulder</b> D&C Path = Design Standards/Roadway/EOS New Asph.	Proposed Plan DGN	Optional	
<b>Aggregate Shoulder</b> D&C Path = Design Standards/Roadway/EOS New Aggr.	Proposed Plan DGN	Optional	
<b>Earth Shoulder</b> D&C Path = Design Standards/Roadway/EOS New Earth	Proposed Plan DGN	Optional	
<b>U2 Earth Shoulder</b> D&C Path = Design Standards/Roadway/EOS U2 Earth	Proposed Plan DGN	Optional	
<b>U2 Bituminous Shoulder</b> D&C Path = Design Standards/Roadway/EOS U2 Asphalt	Proposed Plan DGN	Optional	

## Curb and Gutter

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

<u>ELEMENT</u>	<u>DGN DRAWING FILE</u>	<u>REQUIREMENT</u>	<u>Link</u>
<b>Curb &amp; Gutter Type A</b> D&C Path = Payitems/Roadway/Curb/609-10.51	Proposed Plan DGN	Optional	<a href="#">Curb &amp; Gutter</a> Details
<b>Curb &amp; Gutter Type B</b> D&C Path = Payitems/Roadway/Curb/609-10.52	Proposed Plan DGN	Optional	<a href="#">Curb &amp; Gutter</a> Details

Curb

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

<u>ELEMENT</u>	<u>DGN DRAWING FILE</u>	<u>REQUIREMENT</u>	<u>Link</u>
<b>Concrete Curb Type S 6 Inch And Under</b> D&C Path = Payitems/Roadway/Curb/609-10.10	Proposed Plan DGN	Optional	<a href="#">Separated Curb Details</a>
<b>Concrete Curb Type S Over 6 Inch</b> D&C Path = Payitems/Roadway/Curb/609-10.11	Proposed Plan DGN	Optional	<a href="#">Separated Curb Details</a>
<b>Integral Curb Type A 6 Inch And Under</b> D&C Path = Payitems/Roadway/Curb/609-20.11	Proposed Plan DGN	Optional	<a href="#">Integral Curb Types A, M, O, and E</a>
<b>Integral Curb Type B 6 Inch And Under</b> D&C Path = Payitems/Roadway/Curb/609-20.12	Proposed Plan DGN	Optional	<a href="#">Integral Curb Types B and N</a>
<b>Integral Curb Type M</b> D&C Path = Payitems/Roadway/Curb/609-20.13	Proposed Plan DGN	Optional	<a href="#">Integral Curb Types A, M, O, and E</a>
<b>Integral Curb Type N</b> D&C Path = Payitems/Roadway/Curb/609-20.14	Proposed Plan DGN	Optional	<a href="#">Integral Curb Types B and N</a>
<b>Integral Curb Type O</b> D&C Path = Payitems/Roadway/Curb/609-20.15	Proposed Plan DGN	Optional	<a href="#">Integral Curb Types A, M, O, and E</a>
<b>Integral Curb Type A Over 6 Inch</b> D&C Path = Payitems/Roadway/Curb/609-20.21	Proposed Plan DGN	Optional	<a href="#">Integral Curb Types A, M, O, and E</a>
<b>Integral Curb Type B Over 6 Inch</b> D&C Path = Payitems/Roadway/Curb/609-20.22	Proposed Plan DGN	Optional	<a href="#">Integral Curb Types B and N</a>
<b>Low Profile Curb Type E</b> D&C Path = Payitems/Roadway/Curb/609-20.31	Proposed Plan DGN	Optional	<a href="#">Integral Curb Types A, M, O, and E</a>
<b>Low Profile Curb Type F</b> D&C Path = Payitems/Roadway/Curb/609-20.32	Proposed Plan DGN	Optional	<a href="#">Separated Curb Details</a>

## Gutter

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

<u>ELEMENT</u>	<u>DGN DRAWING FILE</u>	<u>REQUIREMENT</u>	<u>Link</u>
<b>Gutter Type A</b> D&C Path = Payitems/Roadway/Curb/609-10.41	Proposed Plan DGN	Optional	<a href="#">Gutter Details</a>
<b>Gutter Type B</b> D&C Path = Payitems/Roadway/Curb/609-10.42	Proposed Plan DGN	Optional	<a href="#">Gutter Details</a>

## Concrete Barrier Curb and Guardrail

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

<u>ELEMENT</u>	<u>DGN DRAWING FILE</u>	<u>REQUIREMENT</u>
<b>Concrete Traffic Barrier Type A</b> D&C Path = Payitems/Safety/Barrier/617-10.00	Proposed Plan DGN	Optional
<b>Concrete Traffic Barrier Type B</b> D&C Path = Payitems/Safety/Barrier/617-20.00	Proposed Plan DGN	Optional
<b>Concrete Traffic Barrier Type B Modified</b> D&C Path = Payitems/Safety/Barrier/617-20.01	Proposed Plan DGN	Optional
<b>Concrete Traffic Barrier Type C</b> D&C Path = Payitems/Safety/Barrier/617-30.00	Proposed Plan DGN	Optional
<b>Concrete Traffic Barrier Type D</b> D&C Path = Payitems/Safety/Barrier/617-31.00	Proposed Plan DGN	Optional
<b>Concrete Traffic Barrier Type D Modified</b> D&C Path = Payitems/Safety/Barrier/617-31.01	Proposed Plan DGN	Optional
<b>Guardrail</b> D&C Path = Design Standards/Safety and Structures/Guardrail	Proposed Plan DGN	Optional

# Roadside

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

<u>ELEMENT</u>	<u>DGN DRAWING FILE</u>	<u>REQUIREMENT</u>
<b>Paved Private Approach w/ Adjoining C&amp;G</b> D&C Path = Design Standards/Roadway/Paved Private	Proposed Plan DGN	Optional
<b>Sideroad Approach w/ Adjoining C&amp;G</b> D&C Path = Design Standards/Roadway/Paved	Proposed Plan DGN	Optional
<b>Paved Private Approach No Adjoining C&amp;G</b> D&C Path = Design Standards/Roadway/Paved Private -	Proposed Plan DGN	Optional
<b>Sideroad Approach No Adjoining C&amp;G</b> D&C Path = Design Standards/Roadway/Paved Sideroad	Proposed Plan DGN	Optional
<b>Type 1 Driveway Back of Entrance</b> D&C Path = Design Standards/Roadway/Type 1 Driveway	Proposed Plan DGN	Optional
<b>Type 2 Driveway Back of Entrance</b> D&C Path = Design Standards/Roadway/Type 2 Driveway	Proposed Plan DGN	Optional
<b>Type 3 Driveway Back of Entrance</b> D&C Path = Design Standards/Roadway/Type 3 Driveway	Proposed Plan DGN	Optional
<b>Type 4 Driveway Back of Entrance</b> D&C Path = Design Standards/Roadway/Type 4 Driveway	Proposed Plan DGN	Optional
<b>Type 5 Driveway Back of Entrance</b> D&C Path = Design Standards/Roadway/Type 5 Driveway	Proposed Plan DGN	Optional
<b>Side Road Tie Down Line</b> D&C Path = Design Standards/Roadway/Force Side Road	Proposed Plan DGN	Optional
<b>Sidewalk</b> D&C Path = Design Standards/Roadside/Sidewalk (New)	Proposed Plan DGN	Optional
<b>Retaining Wall</b> D&C Path = Design Standards/Safety and Structures/New Retaining	Proposed Plan DGN	Optional

Side Slope and Drainage

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

ELEMENT	DGN DRAWING FILE	REQUIREMENT	Link
<b>Fill Slope 1 Break Line</b> D&C Path = Design Standards/Drainage/Slope Fill	<a href="#">GEOPAK Lines DGN</a>	Optional	<a href="#">Fill Slope 1 Details</a>
<b>Cut Slope 1 Break Line</b> D&C Path = Design Standards/Drainage/Slope Cut	GEOPAK Lines DGN	Optional	<a href="#">Ditch Fore Slope 1 Details</a>
<b>Berm Line</b> D&C Path = Design Standards/Roadway/Berm Line	GEOPAK Lines DGN	Optional	<a href="#">Berm Details</a>
<b>Force Tie Slope</b> D&C Path = Design Standards/Roadway/Force Tie Slope	GEOPAK Lines DGN	Optional	
<b>Match Line</b> D&C Path = Design Standards/Roadway/Matchline	GEOPAK Lines DGN	Optional	
<b>Top of Levee Inside Edge</b> D&C Path = Design Standards/Drainage/In Levee	GEOPAK Lines DGN	Optional	
<b>Top of Levee Outside Edge</b> D&C Path = Design Standards/Drainage/Out Levee	GEOPAK Lines DGN	Optional	

Paved Ditch

Used by the Proposed Paved Ditches typical section ([PDitch](#)).

ELEMENT	DGN DRAWING FILE	REQUIREMENT
<b>Proposed Paved Ditch</b> D&C Path = Design Standards/Drainage/Paved Ditch New	Proposed Plan DGN	<b>Required</b>
<b>Proposed Slopes</b> D&C Path = Design Standards/Cross Sections/Proposed Surfaces/Ground	Cross Section DGN	<b>Required</b>

## Appendix 2 Define Variables

### DGN File

These variables are used to define the name of the MicroStation file containing specific geometry used by the criteria files. **IMPORTANT**, if the file is not in the GEOPAK Project "Working Directory" then the complete drive letter and path **MUST** be specified. The plan element descriptions for each typical section state which elements need to be placed in which file. The following list gives all of the file variables and indicates which typical sections use a particular variable. Suggestions are also provided on what to include or exclude from a particular file.

### Existing TOPO DGN

Used by Existing Features ([ExFeat](#)) and all reconstruction typical section ([DRecon](#), [NLtRRt](#), [NRtRLt](#), & [URECon](#)).

Because many of the plan elements must cross the pattern line in pairs (edges of pavement, sidewalks, etc.) it is probably not a good idea to place all of the topographical information in this file. All that needs to be in this file are the items used to locate the existing features that are to be shown in the cross section.

Go to: [Existing Pavement](#)  
[Existing Paved Shoulder](#)  
[Existing Curb and Gutter](#)  
[Existing Paved Surfaces](#)  
[Existing Sidewalks](#)  
[Existing Paved Ditches](#)  
[Existing Buildings](#)  
[Existing Railroads](#)  
[Existing Wall](#)

### Right of Way DGN

Used by the Draw Right of Way Lines ([DrwROW](#)) and all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

This drawing contains the existing and proposed right of way Lines.

Go to: [Right of Way DGN Geometry Details](#)

## Cross Section DGN

Used by Proposed Paved Ditches ([PDitch](#)), Trace Existing Sub Layers ([SubLay](#)), and all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

This drawing contains the existing cross sections.

## Proposed Plan DGN

Used by Proposed Paved Ditches ([PDitch](#)) and all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

This drawing contains the proposed design elements.

Go to: [Appendix 5 Pavement](#)  
[Appendix 7 Rural Shoulders](#)  
[Appendix 8 Curbing With Urban Shoulders \(U1 & U2\)](#)  
[Appendix 13 Rock Benches](#)

[Appendix 14 Sidewalk](#)  
[Appendix 15 Retaining Walls](#)  
[Grass Infield Gore](#)

## GEOPAK Lines DGN

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

This drawing contains the proposed GEOPAK design elements that are not normally shown on the plan sheets but are needed to control the criteria while processing the proposed cross sections. An example of an element shown in this file would be [Fill Slope 1 Break Line](#). It is recommended to use the Pattern\_Shape.DGN as the GEOPAK Lines DGN.

Go to: [Berm Details](#)  
[Fill Slope 1 Details](#)  
[Match Lines](#)  
[Levee and Optional Interception Ditch](#)

[Ditch Fore Slope 1 Details](#)  
[Forced Closure using GEOPAK Lines DGN Element](#)  
[Typical Section Before Match Line Details](#)  
[Grass Infield Gore](#)



## Tapers File

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

This is the name of the tapers text file used to control tapering on the side slope as detailed later in this document. The variables will have default values. This is the original file copied to the working directory by the typical section generator. In the event the user chose to conduct tapering, it is recommended to rename this variable to a new file name and rename the actual file to match. This will prevent the user from over riding the text file when an additional typical section may be applied. **IMPORTANT**, if this file is not in the GEOPAK Project "Working Directory" then the complete drive letter and path **MUST** be specified.

### **Left Tapers File Name**

This is the name of the tapers text file for the left side slope and is defaulted to TapersLt.txt.

### **Right Tapers File Name**

This is the name of the tapers text file for the left side slope and is defaulted to TapersRt.txt.

Go to: [Tapering Procedure Details](#)  
[Tapering Example](#)

# **Plot Scale**

The plot scale variables are used to define the plot scale of various drawings that have items place in them by the criteria. The value is the plot scale in the formula: 1"=Plot Scale'. Consequently a plot scale of 10 is used for a 1"=10' scale sheet, 50 is used for a 1"=50' scale sheet, etc. The Define Variables section of each typical section gives information on the use of its plot scales. The following list contains all of the plot scale variables and indicates which typical sections use which variables.

## **XS Scale**

Used by Draw Right of Way Lines ([DrwROW](#)), Existing Features ([ExFeat](#)), and all pavement typical sections [DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

This is the scale of the cross section drawing. It is used in determining the text size for labeling slopes, elevations, and offsets on the proposed cross sections. For cross section plot scale of 1"=10' enter the number 10 as a value.

Go to: [Existing Buildings](#)  
[Existing Railroads](#)  
[Existing Wall](#)

## **Plan View Scale**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

This is the scale of the proposed plan drawing. It is used in determining the text size for labeling ditch slopes in the proposed plan view. For proposed plan plot scale of 1"=50' enter the number 50 as a value.

Go to: [Draw Ditches In Plan View Details](#)

## **Plan View Flow Arrow Scale**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

This will be the scale of the proposed plan drawing ditch flow arrows. It is used in determining the size of the ditch flow arrow cell in the proposed plan view. For proposed plan plot scale of 1"=50' enter the number 50 as a value.

Go to: [Draw Ditches In Plan View Details](#)

**GPB Element**

The GPB element variables are used to indicate the name of coordinate geometry objects that are used by the criteria. Typically they are used to draw to a particular location or elevation.

**Survey Baseline Name**

Used by all pavement typical sections (DNPAvt, DRecon, NLtRRt, NRtRLt, UNPAvt, & URECon).

If a survey baseline is used that is different from the proposed baseline, the user may enter the name and the proposed cross sections will draw the baseline and label its offset. The default of "none" will cause this variable to be ignored. This alignment must be previously stored in COGO before processing cross sections.

**Left Special Ditch Profiles and Right Special Ditch Profiles**

Used by all pavement typical sections (DNPAvt, DRecon, NLtRRt, NRtRLt, UNPAvt, & URECon).

These variables list the name(s) of the all of the optional **LEFT** & **RIGHT** special ditch profiles for a proposed cross section run. These profile(s) must be previously stored in COGO before processing cross sections. Commas must separate the profile names. Example: ltdit1,ltdit2,ltdit3 or rtdit1,rtdit2,rtdit3.

Go to: [Special Ditch Profiles](#)

**Left Ditch Alignment and Right Ditch Alignment**

Used by all pavement typical sections (DNPAvt, DRecon, NLtRRt, NRtRLt, UNPAvt, & URECon).

These variables list the name of the optional **LEFT** & **RIGHT** ditch alignments. It allows the user to control the location of the toe of the ditch resides, which is where the chain intersects the cross section. This is helpful when trying to match with an existing culvert for example. It overrides the ditch fore slope 2 variable and forces the ditch to have a varying foreslope. Only ONE alignment per side is allowed per cross section run. This alignment must be previously stored in COGO before processing the cross sections. Example: ltditch1 or rtditch1.

Go to: [Ditch Alignments](#)

### Left Match Line Profiles and Right Match Line Profiles

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

These variables list the name(s) of the optional **LEFT** & **RIGHT** match line profiles. A user may draw a match line in the GEOPAK lines file and the cross section will stop drawing at that location and label it as a match line. This variable expands on that concept and also allows the match line to be controlled vertically. For example, a user draws a match line through the fill slope 2 region. The fill slope 2 variable is set to a run:rise value of 3:-1. Without a match line profile, the fill slope 2 line would be drawn at a 3:-1 until intersecting the match line. This variable will force an "over ride" of the fill slope 2 variable and force the final fill slope 2 line to be drawn to the named match line profile. Commas must separate the profile names. Example: ml1lt,ml2lt,ml3lt or ml1rt,ml2rt,ml3rt.

Go to: [Typical Section Before Match Line Details](#)  
[Match Line Chain and Profile Details](#)

### Left Sidewalk Profiles and Right Sidewalk Profiles

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

These variables list the name(s) of the all of the optional **LEFT** & **RIGHT** sidewalk profiles for a proposed cross section run. The profile will be applied to the inside edge of the proposed sidewalk only when it is not adjacent to the back of curb. The profile(s) must be previously stored in COGO. The profile names are to be separated by commas. Example: ltsw1,ltsw2,ltsw3 or rtsw1,rtsw2,rtsw3

Go to: [Sidewalk Elevation](#)

### Left Interception Special Ditch Profiles and Right Interception Special Ditch Profiles

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

These variables list the name(s) of the all of the optional **LEFT** & **RIGHT** interception special ditch profiles located on the outside of the proposed levee. These profile(s) must be previously stored in COGO before processing cross sections. Commas must separate the profile names. Example: ltleve1,ltleve2,ltleve3 or rtleve1,rtleve2,rtleve3.

Go to: [Levee and Optional Interception Ditch](#)

## Median Ditch Profiles

Used by divided pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), & [NRtRLt](#)).

This variable lists the name(s) of the all of the optional median ditch profiles for a proposed cross section run. This profile will be applied to the median types 1 and 3 only, which are described within the redefinable variable [\\_s\\_MedianType](#). These profile(s) must be previously stored in COGO before processing cross sections. The profile names are to be separated by commas. Example: MD1,MD2,MD3

## Ramp Chain Names

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

This variable lists the name(s) of the all of the optional proposed ramp chain names. It is used for resolving paved gores. The ramp chain name spelling must exactly match the ramp profile name. For example, a user has a ramp chain named "ramp1". Then the profile name must also be "ramp1". The criteria will check to see if the pavement should continue from the edge of the mainline pavement to the ramp chain and profile. Commas must separate the profile names. Example: ramp1,ramp2,ramp3. **IMPORTANT:** The listing of the ramp chains MUST NOT include any blank spaces.

Go to: [Ramp Transition Chain and Profile Design Procedure](#)

## Match Line Chain Names

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

This variable lists the name(s) of the all of the optional proposed match line chain names. It is used for resolving grass gores. The match line chain name spelling must exactly match the match line profile name. For example, a user has a match line chain named "ML1". Then the profile name must also be "ML1". The criteria checks to see if the grass slopes are to draw to a match line chain and profile. Commas must separate the profile names. Example: ML1,ML2,ML3. **IMPORTANT:** The listing of the match line chains MUST NOT include any blank spaces.

Go to: [Match Line Chain and Profile Details](#)  
[Match Line Cross-Section Details for Non-Controlling Roadway](#)

### Left Top of Wall Profiles and Right Top of Wall Profiles

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

These variables list the name(s) of the all of the optional **LEFT** & **RIGHT** profiles to control the elevation of the top of retaining wall for a proposed cross section run. These profile(s) must be previously stored in COGO before processing cross sections. The profile names are to be separated by commas. Example: LTW1,LTW2,LTW3 or RTW1,RTW2,RTW3.

Go to: [Height Set by Elevation of the Top of the Wall](#)

### Left Top of Footing Profiles and Right Top of Footing Profiles

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

These variables list the name(s) of the all of the optional **LEFT** & **RIGHT** profiles to control the elevation of the top of the footing of retaining wall for a proposed cross section run. These profile(s) must be previously stored in COGO before processing cross sections. The profile names are to be separated by commas. Example: LTF1,LTF2,LTF3 or RTF1,RTF2,RTF3.

Go to: [Footing Cross-Section Details](#)

### Median Top of Footing Profiles

Used by divided pavement typical sections only ([DNPavt](#), [DRecon](#), [NLtRRt](#), & [NRtRLt](#)).

This variable lists the name(s) of the all of the optional **MEDIAN TOP OF FOOTING** retaining wall profiles for a proposed cross section run. This profile will be applied to the top of the proposed median retaining wall footing. These profile(s) must be previously stored in COGO before processing cross sections. The profile names are to be separated by commas. Example: MTF1,MTF2,MTF3

Go to: [Footing Cross-Section Details](#)

### Appendix 3 Redefinable Variables

This appendix lists the available redefinable variables with an example. They are grouped by type, reflecting what they do.

#### Show Existing Features Redefinable Variables

Used by Existing Features Typical Section ([ExFeat](#)). The show redefinable variables control whether or not a specific feature is drawn in the cross section. Specify ^Yes^ or ^No^ for each feature listed. The carets "^" are required. A generic example is shown to the right.

EXAMPLE:     if (Sta >= 0+00 R 1)  
                  {  
                    \_s\_VariableName = ^Yes^  
                  }

**\_s\_ShowShoulders**

Controls whether or not existing shoulders are drawn.

Go To: [Existing Paved Shoulder](#)

**\_s\_ShowSidewalk**

Controls whether or not existing sidewalks ditches are drawn.

Go To: [Existing Sidewalks](#)

**\_s\_ShowPavedDitch**

Controls whether or not existing paved ditches are drawn.

Go To: [Existing Paved Ditches](#)

**\_s\_ShowPavedSurface**

Controls whether or not existing paved surfaces are drawn.

Go To: [Existing Paved Surfaces](#)

**\_s\_ShowBuildings**

Controls whether or not the edges of existing building are marked.

Go To: [Existing Buildings](#)

**\_s\_ShowRailroadTracks**

Controls whether or not the location of existing railroad tracks are marked.

Go To: [Existing Railroads](#)

**\_s\_ShowRetainingWall**

Controls whether or not the location of existing retaining walls are marked.

Go To: [Existing Wall](#)

**\_s\_ShowCurbandGutter**

Controls whether or not existing curb and gutter are drawn.

Go To: [Existing Curb and Gutter](#)

## Draw Top of Rock Line Redefinable Variable

### **\_s\_DrawRockLine**

Used by Trace Existing Sub Layers Typical Section ([SubLay](#)).

Controls whether to draw the top of rock line when no top of rock is found on the current cross section. This has been implemented to allow the user to run earthwork when rock is present on some, but not all, of the cross sections. If rock is to be considered, a top of rock line must reside on ALL cross sections. If the variable is set to ^Yes^ and a rock line is NOT found on a section, a top of rock line will be drawn 100 feet below the existing ground. This will then allow earthwork to process normally. The options are ^Yes^ or ^No^. The carets "^" are required.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _s_DrawRockLine = ^Yes^
}
```

## Special Ditch Label Redefinable Variable

### **\_s\_SpecialDitchLabel**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

The special ditch text string redefinable variable controls the content of labels placed on all ditches that use a special ditch profile. Values are place between carets "^", which are required.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _s_SpecialDitchLabel = ^S.D.^
}
```

Go to: [Special Ditch Options](#)



## **Label Control Redefinable Variables**

The label control redefinable variables determine whether or not a specific label feature will be shown. Specify ^Yes^ or ^No^ for each feature listed. The carets "^" are required.

### **\_s\_LabelShoulderElevations**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

Controls whether to label edge of proposed shoulder elevations and offsets in the cross section view.

EXAMPLE:

Go to: [Shoulders In Cross Section](#)

```
if (Sta >= 0+00 R 1)
{
  _s_LabelShoulderElevations = ^Yes^
}
```

### **\_s\_DrawDitchesInPlanView**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

Controls whether to draw ditches in the Proposed Plan DGN while processing the proposed cross sections. If set to ^Yes^, the edges of the ditch, the average ditch slope between cross sections, and flow arrows are drawn.

EXAMPLE:

Go to: [Draw Ditches In Plan View Details](#)  
[Grass Infield Gore](#)

```
if (Sta >= 0+00 R 1)
{
  _s_DrawDitchesInPlanView = ^No^
}
```

## Draw Underdrain Redefinable Variables

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

The draw underdrain redefinable variables control whether or not to include edge underdrains. These options are given to conform to MoDOT practice as specified in the Project Development Manual (PDM) section 6-02.3:

Pavement edge drains are required for new rigid or flexible pavements on medium and heavy duty routes, and permeable base courses will be provided on all heavy duty pavements with the following exceptions. Pavement edge drains and permeable base courses are not required where a minimum of 2 ft. [0.6 m] of day lighted rock base can be furnished for the top of the subgrade or where hydraulically placed sand fill comprises the top 4 ft. [1.2 m] of the embankment with not more than 2 ft. [0.6 m] of soil cap on the slopes. Thin courses of permeable bases cannot be relied upon to provide permanent drainage when day lighted and should never be used without longitudinal edge drains (Rev. 7-1-98).

Separate variables are given for the left and right side. The variable value can be either ^Yes^ or ^No^ to draw the proposed pavement underdrain. When set to ^Yes^ the underdrain will be drawn for that side except for the following two conditions. An underdrain will NOT be drawn if the pavement slope is greater than zero because the pavement cross slope does not flow towards the shoulder. Secondly, an underdrain will not be drawn if the rock fill base is present and set to daylight. The carets "^" are required.

The examples below give the default values for the variables.

### **\_s\_DrawLeftUnderdrain**

Controls the left side.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _s_DrawLeftUnderdrain = ^No^
}
```

Go to: [Under Drain Details](#)

### **\_s\_DrawRightUnderdrain**

Controls the left side.

For an example see [\\_s\\_DrawLeftUnderdrain](#). The only difference is the name of the variable.

Go to: [Under Drain Details](#)

## Type Redefinable Variables

The type redefinable variables are used to select between different options within the criteria. All require a caret (^) before and after the type, since these are string variables and GEOPAK uses carets to designate that a value is a text string rather than a numeric value.

### **\_s\_PavementType**

Used by all pavement typical sections ([DNPAvt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPAvt](#), & [URECon](#)).

Controls proposed pavement type. Use ^C^ or ^B^ for concrete or bituminous pavement respectively. This will determine if the edge of pavement is closed vertically for concrete or 1:1 for bituminous.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _s_PavementType = ^B^
}
```

Go to: [Pavement Details](#)

### **\_s\_OutsideShoulderType**

Used by all pavement typical sections ([DNPAvt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPAvt](#), & [URECon](#)).

Determines the material type for the "outside" or non-median shoulder. The options are as follows:

^C^ = Concrete

^B^ = Bituminous

^A^ = Aggregate

^E^ = Earth

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _s_OutsideShoulderType = ^B^
}
```

Go to: [Determining Shoulder Width and Type](#)

Type Redefinable Variables (continued)

**\_s\_MedianType**

Used by divided pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), & [NRtRLt](#)).

Determines proposed median type. Types 1-4 are all rural grass medians with no thickness shown. Type 5 has a raised median, which is paved if the width of the median does not exceed the redefinable variable [\\_d\\_MaxPavedMedianWidth](#). Type 6 is flush paved median with a Type A or C concrete barrier, which may be flat on the bottom or stepped. It requires one and only one new edge of shoulder line is to be drawn between the median edges of pavement. This single shoulder line represents the centerline location of the concrete barrier. The Type 7 median has a retaining wall in the median. It requires two new edge of shoulder lines to be drawn between the median edges of pavement. The distance between the edges of shoulders controls the width of the retaining wall less a "hard coded" buffer distance of 1 inch on each side of the wall.

The options are as follows:

- [^1^](#) = Fixed slope and fixed depth with a variable ditch bottom width.
- [^2^](#) = Fixed slope and fixed ditch width with a variable ditch depth.
- [^3^](#) = Fixed ditch depth and fixed ditch bottom width with variable slopes.
- [^4^](#) = "V" Ditch with fixed slopes and a variable depth.
- [^5^](#) = Crowned median between curbs with the sloped controlled by the positive value of [\\_d\\_MedianSlope1](#). The optional variable [\\_d\\_PavedMedianThickness](#) may be set greater than zero to show a thickness for this median type assuming the width of the median does not exceed the variable named [\\_d\\_MaxPavedMedianWidth](#).
- [^6A^](#) or [^6C^](#) = Stepped Median Barrier using type A or type C barrier respectively
- [^7^](#) or [^7B^](#) = Retaining Wall median without barrier on top "7" or with Barrier on top "7B"

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
  _s_MedianType = ^3^
}
```

Go to: [Median Ditch Profiles](#)

## Type Redefinable Variables (continued)

### **\_s\_MedianShoulderType**

Used by all divided pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), & [NRtRLt](#)).

Determines the material type for the "median" shoulder. The options are as follows:

^C^ = Concrete

^B^ = Bituminous

^A^ = Aggregate

^E^ = Earth

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
  _s_MedianShoulderType = ^B^
}
```

Go to: [Determining Shoulder Width and Type](#)

### **\_s\_OverlayType**

Used by pavement reconstruction typical sections ([DRecon](#), [NLtRRt](#), [NRtRLt](#), & [URECon](#)).

Determines if the proposed overlay is for crown correction or is to match the existing pavement. The options are ^CC^ for Crown Correction, which uses proposed pavement shapes to correct the cross slope, and ^ME^ for Match Existing, which traces the existing ground line. The carets "^" are required.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
  _s_OverlayType = ^ME^
}
```

Go to: [Appendix 6 Reconstruction](#)

**Note:** If you are not doing crown correction it is recommended that the default pavement symbology in the Proposed Cross Sections run be modified so it is drawn on an otherwise unused level so that these lines can be deleted easily. To do this go to the Plot Parameters section of the dialog and modify the XS Lines placement level to one not being used.

**Slope Control Redefinable Variables**

The slope control redefinable variables are used to select between different options within the criteria. All require a caret (^) before after the variable value since these are string variables and carets designate that a value is a text string rather than a numeric value.

**\_s\_ExtensionSlope**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

Determines whether aggregate base extension slope matches pavement slope or shoulder slope. Options are:

^P^ = pavement slope

^S^ = shoulder slope

This only has an effect on light duty pavements on an aggregate base with ADT < 3500, as specified in PDM Figures 6-03.1 & 6-03.2, effective 10-10-03.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _s_ExtensionSlope = ^S^
}
```

- Go to: [Aggregate Base Details](#)
- [Type B Shoulders \(8" Aggregate Shoulders\)](#)
- [Type C Shoulders \(6" Aggregate Shoulders\)](#)
- [Type D Shoulders \(3" Minimum Aggregate Shoulders\)](#)
- [Type E Shoulders \(Earth Shoulders\)](#)

**\_s\_GutterSlopeInSuper**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

Controls high side super gutter pan slope. Options are:

^U^ for up

^D^ for down

Effects type A and B curb and gutter only. If ^D^ or "down" is selected then the gutter will hold water on the high side of super elevation. If ^U^ or "up" is selected then the gutter pan will not hold water in the high side of super elevation.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _s_GutterSlopeInSuper = ^U^
}
```

Go to: [Curb & Gutter Details](#)

## Slope Control Redefinable Variables (continued)

### **\_s\_OverlayOffsetLocation**

Used by pavement reconstruction typical sections ([DRecon](#), [NLtRRt](#), [NRtRLt](#), & [URECon](#)).

Denotes the elevation control point for the top of the overlay. It functions like the Profile Grade Line or Tie location used for new pavement drawn using shapes. Options are:

^L^ = Left edge of existing pavement

^R^ = Right edge of existing pavement

^C^ = Center of existing pavement

^P^ = Use proposed profile

Go to: [Appendix 6 Reconstruction](#)

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _s_OverlayOffsetLocation = ^P^
}
```

### **\_s\_WideningSlope**

Used by pavement reconstruction typical sections ([DRecon](#), [NLtRRt](#), [NRtRLt](#), & [URECon](#)).

Determines the slope for proposed pavement widening. ^ME^ = "Match Existing" and a number encompassed within carets represents a slope in percent format i.e. ^-2^ for a -2% slope.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _s_WideningSlope = ^ME^
}
```

Go to: [Appendix 6 Reconstruction](#)

## **Rock Fill Base Daylighting Redefinable Variables**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

The rock fill base daylighting redefinable variables control the extension of the rock fill base from under the pavement. These options are given to conform to MoDOT practice as specified in the Project Development Manual (PDM) section 6-03.7:

Rock base consists of 18 in. [0.45 m] of Class C excavation. It is placed full roadbed width and daylighted to the in-slope or fillslope, except on the high side of superelevated curves and when not economically feasible under light duty pavements, in which case the rock base is not daylighted to the ditch and soil is used as a fill material at these locations (Rev. 10-10-03).

The variable value can be either ^Yes^ or ^No^ to "daylight" the rock fill base. The carets "^" are required.

The examples below give the default values for the variables.

### **\_s\_RockFillBaseDaylight**

Controls whether or not to "daylight" the rock fill base. If the criteria determines that it is not possible to daylight the rock fill base then it will close off the rock fill base at a 1:1 slope beyond the shoulder or curb and gutter.

EXAMPLE:

Go to: [Rock Base Details](#)

```
if (Sta >= 0+00 R 1)
{
    _s_RockFillBaseDaylight = ^Yes^
}
```

### **\_s\_RockFillBaseDaylightHSS**

Controls whether or not to "daylight" the rock fill base in the high side of super elevation (HSS). This will be an "override" of the variable [\\_s\\_RockFillBaseDaylight](#) for high side super elevation only.

EXAMPLE:

Go to: [Rock Base Details](#)

```
if (Sta >= 0+00 R 1)
{
    _s_RockFillBaseDaylightHSS = ^No^
}
```



## Existing Features Dimension Redefinable Variables

Used by Existing Features Typical Section ([ExFeat](#)).

This set of variables controls the dimensions of existing features drawn in the cross sections. All values are in master units. The number **MUST** be greater than zero.

### **\_d\_ExistingFeatureLineHeight**

Defines the height of the line representing the location of the existing features.

EXAMPLE:

Go to: [Existing Buildings](#); [Existing Railroads](#); [Existing Wall](#)

```
if (Sta >= 0+00 R 1)
{
    _d_ExistingFeatureLineHeight = 10
}
```

### **\_d\_ExistPavtThick**

This is the thickness of the existing pavement structure.

EXAMPLE:

Go to: [Existing Pavement](#)

```
if (Sta >= 0+00 R 1)
{
    _d_ExistPavtThick = 1
}
```

### **\_d\_ExistShouldThick**

This is the thickness of the existing shoulder from the top of shoulder to the bottom.

EXAMPLE:

Go to: [Existing Paved Shoulder](#)

```
if (Sta >= 0+00 R 1)
{
    __d_ExistShouldThick = 6/12
}
```

## Existing Features Dimension Redefinable Variables (continued)

Used by Existing Features Typical Section ([ExFeat](#)).

### **\_d\_ExistSidewalkThick**

This is the total thickness of the existing sidewalk structure from the top of sidewalk to the bottom. See MoDOT Standard Plan 608.10.

EXAMPLE:

Go to: [Existing Sidewalks](#)

```
if (Sta >= 0+00 R 1)
{
    _d_ExistSidewalkThick = 4/12
}
```

### **\_d\_ExistPavedDitchThick**

This is the total thickness of existing paved ditches from the top of existing ground to the bottom of the paved ditch. See MoDOT Standard Plan 609.15.

EXAMPLE:

Go to: [Existing Paved Ditches](#)

```
if (Sta >= 0+00 R 1)
{
    _d_ExistPavedDitchThick = 6/12
}
```

### **\_d\_ExistPavedSurfaceThick**

This is the total thickness of existing paved surfaces from the top of existing ground to the bottom of the paved surface(s).

EXAMPLE:

Go to: [Existing Paved Surfaces](#)

```
if (Sta >= 0+00 R 1)
{
    _d_ExistPavedSurfaceThick = 4/12
}
```

## Existing Features Dimension Redefinable Variables (continued)

Used by Existing Features Typical Section ([ExFeat](#)).

### **\_d\_ExistCurbGutterThick**

This is the total thickness of existing curb and gutter from the top of existing surface to the bottom of the curb and gutter at the edge of existing pavement. See MoDOT Standard Plan 609.00.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_ExistCurbGutterThick = 7/12
}
```

Go to: [Existing Curb and Gutter](#)

### **\_d\_ExistCurbGutterWidth**

This is the total width of the existing curb and gutter from the edge of existing pavement to the back of curb. See MoDOT Standard Plan 609.00.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_ExistCurbGutterWidth = 9/12
}
```

Go to: [Existing Curb and Gutter](#)

## Right of Way Line Redefinable Variable

### **\_d\_RightofWayLineHeight**

Used by the Draw Right of Way Lines Typical Section ([DrwROW](#)).

This is the height of the line in master units drawn to represent the location of existing and proposed right of way. The number **MUST** be greater than zero.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
  _d_RightofWayLineHeight = 10
}
```

**Search Distance Redefinable Variables**

The search distance redefinable variables determine how far to search in the plan view for certain items. If the item is located within the search distance, it will be included in the cross section criteria process. If the item is beyond the search distance it will not be used by the criteria. Unless noted otherwise, the variables are required to avoid locating a plan view element from an adjacent or parallel roadway that might happen to cross the pattern line for the proposed cross section being drawn. All values are in master units. The number **MUST** be greater than zero.

**\_d\_OutsideShoulderSearchDistance**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

Used to locate an "outside" non-median shoulder line. The distance is measured from the proposed edge of pavement.

EXAMPLE:

Go to: [Determining Shoulder Width and Type](#)

```
if (Sta >= 0+00 R 1)
{
    _d_OutsideShoulderSearchDistance = 18
}
```

**\_d\_MedianShoulderSearchDistance**

Used by divided pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), & [NRtRLt](#)).

Used to locate an "outside" non-median shoulder line. The distance is measured from the proposed edge of pavement.

EXAMPLE:

Go to: [Determining Shoulder Width and Type](#)

```
if (Sta >= 0+00 R 1)
{
    _d_OutsideShoulderSearchDistance = 18
}
```

**Search Distance Redefinable Variables (continued)**

**\_d\_CurbSearchDistance**

Used by existing features ([ExFeat](#)) and all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

Used to locate a curb and or curb & gutter or gutter line. The distance is measured from the edge of pavement or shoulder depending on location. For existing curb, it is always measure from the edge of existing pavement.

EXAMPLE:      if (Sta >= 0+00 R 1)  
                  {  
                    \_d\_CurbSearchDistance = 3  
                  }

Go to: [Existing Curb and Gutter](#)  
[Curbing Plan View Geometry](#)  
[U2 Shoulder Details](#)

**\_d\_U2ShoulderSearchDistance**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

Allowable search distance in feet to locate an "outside" edge line of the U2 shoulder located behind the proposed curb and or curb and gutter. This distance is measured from the proposed back of curb.

EXAMPLE:      if (Sta >= 0+00 R 1)  
                  {  
                    \_d\_U2ShoulderSearchDistance = 10  
                  }

Go to: [U2 Shoulder Details](#)

**\_d\_RampChainSearchDistance**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

Defines the proposed ramp(s) search distance to locate the ramp chain(s) used for resolving paved gores. This distance is measured from the edge of the "mainline" pavement.

EXAMPLE:      if (Sta >= 0+00 R 1)  
                  {  
                    \_d\_RampChainSearchDistance = 25  
                  }

Go to: [Ramp Transition Chain and Profile Design Procedure](#)

**Search Distance Redefinable Variables (continued)**

**\_d\_MatchLineChainSearchDistance**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

Distance measured from the edge of shoulder, curb, or berm to look for a match line chain. Primarily used for grass gore resolution.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_MatchLineChainSearchDistance = 100
}
```

Go to: [Match Line Chain and Profile Details](#)  
[Match Line Cross-Section Details for Non-Controlling Roadway](#)

**\_d\_AdjacentWallSearchDistance**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

The purpose of this variable is **NOT** to avoid locating a plan view element from an adjacent or parallel roadway that might happen to cross the pattern line for the proposed cross section being drawn. **Rather**, it is used to determine if the retaining wall is adjacent to the shoulder or located in the grass side slope. If the wall is closer to the edge of shoulder than this distance the aggregate base(s) will draw directly to the face of the wall.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_AdjacentWallSearchDistance = 12/12
}
```

Go to: [Appendix 15 Retaining Walls](#)





## Default Width Redefinable Variables (continued)

### **\_d\_MedianSlope1Width**

Used by divided pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), & [NRtRLt](#)). Optional median slope 1 width. This is equivalent to the berm width, except it is on the median side.

EXAMPLE:      if (Sta >= 0+00 R 1)  
                  {  
                    \_d\_MedianSlope1Width = 0  
                  }

Go to: [Appendix 11 Medians](#)

### **\_d\_BermWidth\_Left**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)). LEFT berm slope width when no plan element is found designating the width. This is measured from the back of curb or edge of shoulder. **IMPORTANT:** In the event a sidewalk is required, the berm width must be set such that the back edge of the berm must be beyond the back of the sidewalk or the sidewalk will not be drawn.

EXAMPLE:      if (Sta >= 0+00 R 1)  
                  {  
                    \_d\_BermWidth\_Left = 0  
                  }

Go to: [Berm Details](#)

### **\_d\_BermWidth\_Right**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)). RIGHT berm slope width when no plan element is found designating the width. This is measured from the back of curb or edge of shoulder. **IMPORTANT:** In the event a sidewalk is required, the berm width must be set such that the back edge of the berm must be beyond the back of the sidewalk or the sidewalk will not be drawn.

EXAMPLE:      if (Sta >= 0+00 R 1)  
                  {  
                    \_d\_BermWidth\_Left = 0  
                  }

Go to: [Berm Details](#)

## Default Width Redefinable Variables (continued)

### **\_d\_DitchForeSlope1Width\_Left**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)). LEFT ditch slope 1 width when no plan element is found. This is measured from the back of curb, edge of shoulder, or edge of berm.

EXAMPLE:      if (Sta >= 0+00 R 1)  
                   {  
                     \_d\_DitchForeSlope1Width\_Left = 0  
                   }

Go to: [Ditch Fore Slope 1 Details](#)

### **\_d\_DitchForeSlope1Width\_Right**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)). RIGHT ditch slope 1 width when no plan element is found. This is measured from the back of curb, edge of shoulder, or edge of berm.

EXAMPLE:      if (Sta >= 0+00 R 1)  
                   {  
                     \_d\_DitchForeSlope1Width\_Right = 0  
                   }

Go to: [Ditch Fore Slope 1 Details](#)

### **\_d\_FillSlope1Width\_Left**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)). LEFT optional fill slope 1 width when no plan element is found, as measured from the back of curb, edge of shoulder, or edge of berm.

EXAMPLE:      if (Sta >= 0+00 R 1)  
                   {  
                     \_d\_FillSlope1Width\_Left = 24  
                   }

Go to: [Fill Slope 1 Details](#)

### **\_d\_FillSlope1Width\_Right**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)). RIGHT optional fill slope 1 width when no plan element is found, as measured from the back of curb, edge of shoulder or edge of berm.

For an example see [\\_d\\_FillSlope1Width\\_Left](#). The only difference is the name of the variable.

Go to: [Fill Slope 1 Details](#)

## Percent Slope Redefinable Variables

The percent slope redefinable variables are used to define the slope of a surface in percent format. Enter the value without the percent sign (-2% slope is entered as -2). Include the negative sign when applicable.

### **\_d\_NormalPavementSlope**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)). It represents the normal pavement crown slope and controls proposed pavement slope. This is typically -2% or similar. It directly affects the way super elevation transitions are handled.

Go to: [Pavement Details](#)

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_NormalPavementSlope = -2
}
```

### **\_d\_U2ShoulderSlope**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)). Defines proposed U2 shoulder slope in percent. This is typically a 2% or similar.

Go to: [U2 Shoulder Details](#)

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_U2ShoulerSlope = 2
}
```

### **\_d\_NormalOutsideShoulderSlope**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)). Controls proposed "outside" non-median shoulder slope. This is typically -4% or similar. It represents normal shoulder slope when no super elevation is present.

Go to: [Shoulders In Cross Section](#)  
page [125](#), [126](#), [127](#), or [128](#)

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_NormalOutsideShoulderSlope = -4
}
```

### **\_d\_NormalMedianShoulderSlope**

Used by divided pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), & [NRtRLt](#)). Proposed median shoulder slope. This is typically a -2% or similar. It represents normal shoulder slope when no super elevation is present.

Go to: [Shoulders In Cross Section](#)

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_NormalMedianShoulderSlope = -2
}
```



**Percent Slope Redefinable Variables (continued)**

**\_d\_Max\_Type2\_Driveway\_Slope**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)). Proposed maximum allowable Type 2 driveway slope. If the driveway slope exceeds this value a warning message is drawn.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_Max_Type2_Driveway_Slope = 5
}
```

**\_d\_Max\_Type3\_Driveway\_Slope**

Proposed maximum allowable Type 3 driveway slope. If the driveway slope exceeds this value a warning message is drawn.

For an example see [\\_d\\_Max\\_Type2\\_Driveway\\_Slope](#). The only difference is the name of the variable.

**\_d\_Max\_Type4\_Driveway\_Slope**

Proposed maximum allowable Type 4 driveway slope. If the driveway slope exceeds this value a warning message is drawn.

For an example see [\\_d\\_Max\\_Type2\\_Driveway\\_Slope](#). The only difference is the name of the variable.

**\_d\_Max\_Type5\_Driveway\_Slope**

Proposed maximum allowable Type 5 driveway slope. If the driveway slope exceeds this value a warning message is drawn.

For an example see [\\_d\\_Max\\_Type2\\_Driveway\\_Slope](#). The only difference is the name of the variable.

**\_d\_Max\_Type2\_Roll\_Over\_Slope**

Used by all pavement typ. sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)). Proposed maximum allowable Type 2 driveway rollover slope. If the difference in slope between the entrance pad and the tie down to ground exceeds this value, a vertical curve entrance is drawn with the length of the vertical curve controlled by [\\_d\\_EntranceVertCurveLength](#).

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_Max_Type2_Roll_Over_Slope = 10
}
```

**\_d\_Max\_Type3\_Roll\_Over\_Slope**

Proposed maximum allowable Type 3 driveway rollover slope. It functions [\\_d\\_Max\\_Type2\\_Roll\\_Over\\_Slope](#).

For an example see [\\_d\\_Max\\_Type2\\_Roll\\_Over\\_Slope](#). The only difference is the name of the variable.

**\_d\_Max\_Type4\_Roll\_Over\_Slope**

Proposed maximum Type 4 driveway rollover slope in percent. It functions [\\_d\\_Max\\_Type2\\_Roll\\_Over\\_Slope](#).

For an example see [\\_d\\_Max\\_Type2\\_Roll\\_Over\\_Slope](#). The only difference is the name of the variable.

**\_d\_Max\_Type5\_Roll\_Over\_Slope**

Proposed maximum Type 5 driveway rollover slope. It functions [\\_d\\_Max\\_Type2\\_Roll\\_Over\\_Slope](#).

For an example see [\\_d\\_Max\\_Type2\\_Roll\\_Over\\_Slope](#). The only difference is the name of the variable.

### **Pavement Thickness Redefinable Variables**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

The pavement thickness redefinable variables determine how the pavement is drawn. It is the distance from the top of the layer to the bottom of the layer. All values are in master units. The number for the first layer **MUST** be greater than zero. The number for all other layers may be greater than zero or zero but never less than zero. If it is set to zero that layer will not be drawn.

#### **\_d\_PavementLayer1Thick**

This is the thickness of the first of four possible pavement structure thicknesses.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_PavementLayer1Thick = 1.75/12
}
```

Go to: [Concrete Pavement Details](#)  
[Bituminous Pavement Details](#)  
[Integral Curb Types A, M, O, and E](#)

#### **\_d\_PavementLayer2Thick**

This is the thickness of the second of four possible pavement structure thicknesses.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_PavementLayer2Thick = 0/12
}
```

Go to: [Bituminous Pavement Details](#)

#### **\_d\_PavementLayer3Thick**

This is the thickness of the third of four possible pavement structure thicknesses.

For an example see `_d_PavementLayer2Thick = 0/12`. The only difference is the name of the variable.

#### **\_d\_PavementLayer4Thick**

This is the thickness of the fourth of four possible pavement structure thicknesses.

For an example see `_d_PavementLayer2Thick = 0/12`. The only difference is the name of the variable.

### Overlay Thickness Redefinable Variables

Used by pavement reconstruction typical sections ([DRecon](#), [NLtRRt](#), [NRtRLt](#), & [URECon](#)).

The overlay thickness redefinable variables determine how the reconstruction pavement overlay is drawn. It is the distance from the top of the layer to the bottom of the layer. All values are in master units. The number for all other layers may be greater than zero or zero but never less than zero. If it is set to zero that layer will not be drawn.

#### **\_d\_OverlayThickness1**

This is the thickness of the first of two possible overlay pavement layers. It **MUST** be greater than zero. If the reconstruction consists of a widening only set this value to two times the tolerance, which has a default value of 0.01. Thus if the default tolerance value is used set the variable to 0.02 if there is widening without an overlay.

EXAMPLE:

Go to: [Appendix 6 Reconstruction](#)

```
if (Sta >= 0+00 R 1)
{
    _d_OverlayThickness1 = 0/12
}
```

#### **\_d\_OverlayThickness2**

This is the thickness of the second of two possible overlay pavement layers. It may be greater than zero or zero but never less than zero. If it is set to zero the layer will not be drawn.

EXAMPLE:

Go to: [Appendix 6 Reconstruction](#)

```
if (Sta >= 0+00 R 1)
{
    _d_OverlayThickness2 = 0/12
}
```

**Shoulder Thickness Redefinable Variables**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

The shoulder thickness redefinable variables determine how the shoulder is drawn. It is the distance from the top of the layer to the bottom of the layer. All values are in master units. The number for the first layer **MUST** be greater than zero. The number for all other layers may be greater than zero or zero but never less than zero. If it is set to zero that layer will not be drawn. **Note:** If the thicknesses of the shoulder and the corresponding pavement layers match then no break will be drawn between the edge of pavement and the edge of shoulder. In essence, it will be one continuous layer of pavement spanning both the pavement and shoulder until a layer is reached for which the shoulder and pavement have different thicknesses.

**\_d\_ShoulderLayer1Thick**

This is the thickness of the first of four possible shoulder structure thicknesses.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_ShoulderLayer1Thick = 6/12
}
```

Go to: [Shoulders In Cross Section](#); page [125](#), [126](#), [127](#), or [128](#)  
[Integral Curb Types A, M, O, and E Details](#)  
[Integral Curb Types B and N Details](#)

**\_d\_ShoulderLayer2Thick**

This is the thickness of the second of four possible shoulder structure thicknesses.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_ShoulderLayer2Thick = 0/12
}
```

**\_d\_ShoulderLayer3Thick**

This is the thickness of the third of four possible shoulder structure thicknesses.

**\_d\_ShoulderLayer4Thick**

This is the thickness of the fourth of four possible shoulder structure thicknesses.



## U2 Shoulder Thickness Redefinable Variables

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

The U2 shoulder thickness redefinable variables determine how the U2 shoulder is drawn. It is the distance from the top to the bottom of the layer. All values are in master units. The number **MUST** be greater than zero or equal to zero. If it is set to zero the layer will not be drawn. See PDM Figure 6-04.1 for suggested values.

### **\_d\_U2ShoulderThickness**

This is the proposed U2 shoulder thickness.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_U2ShoulderThickness = 2/12
}
```

Go to: [U2 Shoulder Details](#)

### **\_d\_U2ShoulderAggbaseThickness**

This is the proposed U2 shoulder aggregate base thickness.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_U2ShoulderAggbaseThickness = 4/12
}
```

Go to: [U2 Shoulder Details](#)

### Base Layer Thickness Redefinable Variables

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

The base layer thickness redefinable variables determine how the pavement base is drawn. All values are in master units, which can be zero or greater than zero, except as noted below. If it is set to zero the layer will not be drawn.

#### **\_d\_Aggbase1Thickness**

Proposed aggregate pavement base 1 thickness. This number **MUST** be greater than zero **if** a thickness is specified for optional Aggbase 2 thickness. If an Aggbase 2 thickness is greater than zero, this layer will be drawn as a Stabilized Permeable Base.

EXAMPLE:

Go to: [Aggregate Base Details](#); [Rock Base Details](#)

```
if (Sta >= 0+00 R 1)
{
    _d_Aggbase1Thickness = 4/12
}
```

#### **\_d\_Aggbase2Thickness**

Proposed aggregate pavement base 2 thickness. If greater than zero, Aggbase 1 will be drawn as a Stabilized Permeable Base.

EXAMPLE:

Go to: [Aggregate Base Details](#); [Rock Base Details](#)

```
if (Sta >= 0+00 R 1)
{
    _d_Aggbase2Thickness = 0/12
}
```

#### **\_d\_RockFillBaseThickness**

Proposed rock fill base thickness.

Go to: [Rock Base Details](#)

For an example see [\\_d\\_Aggbase2Thickness](#). The only difference is the name of the variable.

#### **\_d\_CompensatingDepth**

Proposed compensating depth measured from the top of the proposed pavement.

Go to: [Compensating Depth Details](#)

For an example see [\\_d\\_Aggbase2Thickness](#). The only difference is the name of the variable.

## Roadside Features Thickness Redefinable Variables

The roadside features thickness redefinable variables determine the thickness for various non-roadway items. All values are in positive. This number **MUST** be greater than zero.

### **\_d\_SidewalkThickness**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

Provides the thickness of the proposed sidewalk.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_SidewalkThickness = 4/12
}
```

Go to: [Sidewalk Thickness Details](#)

### **\_d\_PavedDitchThickness**

Used by the Proposed Paved Ditches typical section ([PDitch](#)).

This is the total thickness of the proposed paved ditches from the top of proposed ground to the bottom of the paved ditch.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_PavedDitchThickness = 6/12
}
```

**Underdrain Dimension Redefinable Variables**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

The underdrain dimension redefinable variables control the size of the underdrains shown in cross section. The values **MUST** be in positive master units. See MoDOT Standard Plan 605.10

**\_d\_UnderdrainHeight**

Proposed underdrain height as measured from the bottom of the pavement.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_UnderdrainHeight = 12/12
}
```

Go to: [Under Drain Details](#)

**\_d\_UnderdrainWidth**

Proposed underdrain width.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_UnderdrainWidth = 1
}
```

Go to: [Under Drain Details](#)

**Standard Curb Dimension Redefinable Variable**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

The curb dimension redefinable variable controls the height of the curb shown in cross section. The values **MUST** be in positive master units. See MoDOT Standard Plan 609.00

**\_d\_IntegralCurbHeight**

Proposed curb height for type A, B, & S curbs only. It is the distance up from the gutter line to the top of the curb.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
  _d_IntegralCurbHeight = 6/12
}
```

Go to: [Type S Separated Barrier Curb](#)  
[Type A Integral Barrier Curb](#)  
[Type B Integral Barrier Curb](#)

### Nonstandard Curb & Gutter Redefinable Variables

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

**Important:** These curb dimension redefinable variables are used only for nonstandard curb and gutters that do not conform to MoDOT Standard Plan 609.00. They are not to be used on state routes and are only provided to allow for cross sections to be drawn using municipal and other entity's standards.

#### **\_d\_GutterSlope**

Defined the slope of the top of gutter in percent format. Do not include the percent sign.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_GutterSlope = -5.2
}
```

Go to: [User Defined Curb & Gutter](#)

#### **\_d\_GutterWidth**

Total width of curb and gutter in master units.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_GutterWidth = 2
}
```

#### **\_d\_CurbFaceWidth**

The horizontal width of curb face in master units as measured from the gutter line to the start of the top of the curb.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_CurbFaceWidth = 2/12
}
```

### Nonstandard Curb & Gutter Redefinable Variables (continued)

Used by all pavement typical sections (DNPavt, DRecon, NLtRRt, NRtRLt, UNPavt, & URECon).

#### **\_d\_TopCurbWidth**

The width of the top of the curb in master units as measured from the face to the back of the curb.

EXAMPLE:     if (Sta >= 0+00 R 1)  
                  {  
                    \_d\_TopCurbWidth = 6/12  
                  }

Go to: [User Defined Curb & Gutter](#)

#### **\_d\_CurbHeight**

The height of the curb in master units as measured from the gutter line to the top of the curb.

EXAMPLE:     if (Sta >= 0+00 R 1)  
                  {  
                    \_d\_CurbHeight = 6.17/12  
                  }

#### **\_d\_GutterThickness**

The thickness of the gutter in master units measured at the roadway face of the gutter.

EXAMPLE:     if (Sta >= 0+00 R 1)  
                  {  
                    \_d\_CurbHeight = 6.17/12  
                  }

#### **\_d\_GutterBaseSlope**

Defines the slope of the bottom of the gutter in percent format. Do not include the percent sign.

EXAMPLE:     if (Sta >= 0+00 R 1)  
                  {  
                    \_d\_GutterSlope = -5.2  
                  }

## **Raised Median Redefinable Variables**

Used by divided pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), & [NRtRLt](#)).

The raised median redefinable variables control how a raised median between curbs is drawn. They are used for Type 5 medians. The values **MUST** be in positive master units. See PDM Section 4-04.5 for design information on medians.

### **\_d\_PavedMedianThickness**

Controls the thickness of paved medians when the width of median is less than [\\_d\\_MaxPavedMedianWidth](#).

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_PavedMedianThickness = 6/12
}
```

Go to: [\\_s\\_MedianType](#)  
[Appendix 11 Medians](#)

### **\_d\_MaxPavedMedianWidth**

Controls the maximum width of a paved median. Any median width greater than this is drawn as a grass median.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_MaxPavedMedianWidth = 10
}
```

Go to: [\\_s\\_MedianType](#)  
[Appendix 11 Medians](#)



## Entrance Dimension Redefinable Variables

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

The entrance dimension redefinable variables control the way entrances are drawn in cross section. The values **MUST** be in positive master units greater than zero. See MoDOT Standard Plans 203.61-203.65.

### **\_d\_EntrancePadWidth**

Defines the distance from the edge of pavement to the entrance break point. If it less than the shoulder width, the shoulder width is used.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_EntrancePadWidth = 10
}
```

### **\_d\_EntranceVertCurveLength**

Defines the length of the vertical curve used for entrances. This variable is used only if the difference in slope between the entrance pad and the tie down to ground for type of entrance being drawn exceeds the maximum roll over slope as defined by the redefinable variables [\\_d\\_Max\\_Type1\\_Roll\\_Over\\_Slope](#), [\\_d\\_Max\\_Type2\\_Roll\\_Over\\_Slope](#), etc.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_EntranceVertCurveLength = 20
}
```

# Side Slope Redefinable Variables

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)), except as noted.

The side slope redefinable variables are used to define the slope of a side slope in Run:Rise format. Example, 6:-1. Make sure to include the colon. **Include the negative sign before the Rise when applicable.** The **Run must always be positive.**

## **\_d\_DitchForeSlope1\_Left**

Optional LEFT ditch fore slope 1 value. Rise is **ALWAYS** a negative number.

EXAMPLE: Go to: [Ditch Fore Slope 1 Details](#)  

```

if (Sta >= 0+00 R 1)
{
    _d_DitchForeSlope1_Left = 6:-1
}

```

## **\_d\_DitchForeSlope2\_Left**

Required LEFT ditch fore slope 2 value. Rise is **ALWAYS** a negative number.

EXAMPLE: Go to: [Ditch Fore Slope 2 Details](#)  
[Special Ditch Options](#)  

```

if (Sta >= 0+00 R 1)
{
    _d_DitchForeSlope2_Left = 6:-1
}

```

## **\_d\_DitchBackSlope\_Left**

Required LEFT ditch back slope value. Rise is **ALWAYS** a positive number.

EXAMPLE: Go to: [Ditch Back Slope Details](#)  

```

if (Sta >= 0+00 R 1)
{
    _d_DitchBackSlope_Left = 3:1
}

```

## **\_d\_DitchForeSlope1\_Right**

Optional RIGHT ditch fore slope 1 value. Rise is **ALWAYS** a negative number.

EXAMPLE: Go to: [Ditch Fore Slope 1 Details](#)  

```

if (Sta >= 0+00 R 1)
{
    _d_DitchForeSlope1_Right = 6:-1
}

```

## **\_d\_DitchForeSlope2\_Right**

Required RIGHT ditch fore slope 2 value. Rise is **ALWAYS** a negative number.

EXAMPLE: Go to: [Ditch Fore Slope 2 Details](#)  
[Special Ditch Options](#)  

```

if (Sta >= 0+00 R 1)
{
    _d_DitchForeSlope2_Right = 6:-1
}

```

## **\_d\_DitchBackSlope\_Right**

Required RIGHT ditch back slope value. Rise is **ALWAYS** a positive number.

EXAMPLE: Go to: [Ditch Back Slope Details](#)  

```

if (Sta >= 0+00 R 1)
{
    _d_DitchBackSlope_Right = 3:1
}

```

## Side Slope Redefinable Variables (continued)

### \_d\_FillSlope1\_Left

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)). Optional LEFT Fill Slope 1 value. Rise is **ALWAYS** a negative number.

EXAMPLE: Go to: [Fill Slope 1 Details](#)

```
if (Sta >= 0+00 R 1)
{
  _d_FillSlope1_Left = 6:-1
}
```

### \_d\_FillSlope2\_Left

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)). Required LEFT fill slope 2 value. Rise is **ALWAYS** a negative number.

EXAMPLE: Go to: [Fill Slope 2 Details](#)

```
if (Sta >= 0+00 R 1)
{
  _d_FillSlope1_Right = 3:-1
}
```

### \_d\_MedianSlope2

Used by divided pavement typical sections only ([DNPavt](#), [DRecon](#), [NLtRRt](#), & [NRtRLt](#)).

It is required and represents the slope beyond the shoulder or curb within the median when no median slope 1 is used. If a median slope 1 is used, this slope will begin at the end of the median slope 1. It is used for median types 1 and 2 only. Rise is **ALWAYS** a negative number.

EXAMPLE: if (Sta >= 0+00 R 1)

```
{
  _d_MedianSlope2 = 5.5:-1
}
```

Go to: [Appendix 11 Medians](#)

### \_d\_FillSlope1\_Right

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)). Optional RIGHT Fill Slope 1 value. Rise is **ALWAYS** a negative number.

EXAMPLE: Go to: [Fill Slope 1 Details](#)

```
if (Sta >= 0+00 R 1)
{
  _d_FillSlope1_Right = 6:-1
}
```

### \_d\_FillSlope2\_Right

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)). Required RIGHT fill slope 2 value. Rise is **ALWAYS** a negative number.

EXAMPLE: Go to: [Fill Slope 2 Details](#)

```
if (Sta >= 0+00 R 1)
{
  _d_FillSlope1_Right = 3:-1
}
```

## Ditch Dimension Redefinable Variables

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)), except as noted.

The ditch dimension redefinable variables control the way ditches are drawn in cross section. Values are in master units. Depths are considered positive and **MUST** be greater than zero. Widths may be zero for a "V" ditch or greater than zero for a flat bottom ditch.

### \_d\_StandardDitchDepth\_Left

Controls the depth of the LEFT standard ditch as measured from the edge of shoulder, back of curb or edge of berm.

EXAMPLE: if (Sta >= 0+00 R 1) Go to: [Standard Ditch Depth](#)

```
{
    _d_StandardDitchDepth_Left = 4
}
```

### \_d\_DitchWidth\_Left

Controls the width of LEFT standard ditch.

EXAMPLE: if (Sta >= 0+00 R 1) Go to: [Ditch Width](#)

```
{
    _d_DitchWidth_Left = 8
}
```

### \_d\_StdMedianDitchDepth

Used by divided pavement typical sections only ([DNPavt](#), [DRecon](#), [NLtRRt](#), & [NRtRLt](#)). Controls the depth of median standard ditches as measured from the edge of shoulder or back of curb and is used for median types 1 and 3 only.

EXAMPLE: if (Sta >= 0+00 R 1) Go to: [Medians](#)

```
{
    _d_StdMedianDitchDepth = 4
}
```

### \_d\_StandardDitchDepth\_Right

Controls the depth of the RIGHT standard ditch as measured from the edge of shoulder, back of curb or edge of berm.

EXAMPLE: if (Sta >= 0+00 R 1) Go to: [Standard Ditch Depth](#)

```
{
    _d_StandardDitchDepth_Right = 4
}
```

### \_d\_DitchWidth\_Right

Controls the width of RIGHT standard ditch.

EXAMPLE: if (Sta >= 0+00 R 1) Go to: [Ditch Width](#)

```
{
    _d_DitchWidth_Right = 8
}
```

### \_d\_MedianDitchWidth

Used by divided pavement typical sections only ([DNPavt](#), [DRecon](#), [NLtRRt](#), & [NRtRLt](#)). Controls the width of median standard ditches. This value is used for median types 2 and 3 only.

EXAMPLE: if (Sta >= 0+00 R 1) Go to: [Medians](#)

```
{
    _d_MedianDitchWidth = 8
}
```

# Force Closed Slope Redefinable Variables

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

The force closed slope redefinable variables allow the user to force slope closure to a specific offset or at a slope other than the standard slope. To control this behavior, set the **ForcedClosingSlopes** variable to either ^Yes^ or ^No^ for each side. When set to no, normal side slope conditions are used. When set to yes the slope is drawn from the edge of the shoulder or curb directly to the ground. The carets "^" are required.

The closure can be controlled by either a plan view element or a forced slope variable. If a plan view element is drawn representing the location of the forced slope tie, then the plan element will take precedence and control the location of the tie. If the plan element is not found, variables are used to locate the tie. If the section is in cut the **ForcedCutSlope** value for that side is used and if the section is in fill the **ForcedFillSlope** value for that side is used.

The closure can be controlled by either a plan view element or a forced slope variable. If a plan view element is drawn representing the location of the forced slope tie, then the plan element will take precedence and control the location of the tie. If the section is in cut the **ForcedCutSlope** value for that side is used and if the section is in fill the **ForcedFillSlope** value for that side is used.

The forced slope value is in Run:Rise format. Run is ALWAYS a positive number. Rise is ALWAYS a positive number in CUT and ALWAYS a negative number in FILL (Example, 2:-1). Make sure to include the colon.

## **\_s\_LeftForceClosingSlopes**

Used to force closing of LEFT side slopes.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _s_LeftForceClosingSlopes = ^No^
}
```

## **\_s\_RightForceClosingSlopes**

Used to force closing of RIGHT side slopes.

For an example see [\\_s\\_LeftForceClosingSlopes](#). The only difference is the name of the variable.

Go to: [Forced Closure using Redefinable Variables](#)

## Force Closed Slope Redefinable Variables (continued)

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

### **\_d\_LeftForcedCutSlope**

Optional LEFT forced cut slope value.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_LeftForcedCutSlope = 2:1
}
```

### **\_d\_RightForcedCutSlope**

Optional RIGHT forced cut slope value.

For an example see [\\_d\\_LeftForcedCutSlope](#). The only difference is the name of the variable.

### **\_d\_LeftForcedFillSlope**

Optional LEFT forced fill slope value.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_LeftForcedFillSlope = 2:-1
}
```

### **\_d\_RightForcedFillSlope**

Optional RIGHT forced fill slope value.

For an example see [\\_d\\_LeftForcedFillSlope](#). The only difference is the name of the variable.

Go to: [Forced Closure using Redefinable Variables](#)

# Right of Way Constrained Slope Redefinable Variables

The right of way constrained closing slope redefinable variables are used to force the slope to tie at or inside of the right of way line. An optional buffer distance from the right of way line may also be used. If the normal slope can fit within the right of way and buffer distance, a normal slope is used. If the normal slope will not fit within right of way and buffer distance, a steeper slope is drawn and labeled as such. This will allow the user to identify when the slopes were drawn steeper than the defaults.

## \_s\_LeftROWConstrainedSlope

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)). ^Yes^ or ^No^ to force the LEFT slope to tie inside of the allowed right of way.

EXAMPLE:      if (Sta >= 0+00 R 1)  
                  {  
                    \_s\_LeftROWConstrainedSlope = ^No^  
                  }

## \_s\_RightROWConstrainedSlope

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)). ^Yes^ or ^No^ to force the RIGHT slope to tie inside of the allowed right of way.

EXAMPLE:      if (Sta >= 0+00 R 1)  
                  {  
                    \_s\_RightROWConstrainedSlope = ^No^  
                  }

## \_d\_ROW\_Buffer\_Width

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)). Provides a minimum buffer distance in master units when forcing the side slope tie down point inside of the right of way.

EXAMPLE:      if (Sta >= 0+00 R 1)  
                  {  
                    \_d\_ROW\_Buffer\_Width = 1  
                  }

Go to: [Right of Way Constrained Slopes Cross-Section Details](#)

## Rock Benching Redefinable Variables

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

The rock benching redefinable variables are used to draw side slope benches in cross section. For additional information on using these redefinable variables go to: [Appendix 13 Rock Benches](#).

### **\_d\_BenchingBackSlope**

Rock benching backslope value in Run:Rise format. Rise is ALWAYS a positive number.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_BenchingBackSlope = .1:1
}
```

### **\_d\_BenchHeight**

Defines the rock bench height in master units. Once this value is exceeded, a new bench is drawn. This is a positive value and **MUST** be greater than zero.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_BenchHeight = 30
}
```

### **\_d\_BenchWidth**

Defines the rock bench width in master units. This is a positive value and **MUST** be greater than zero.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_BenchWidth = 10
}
```

### **\_s\_TopBenchWidth**

Defines the width of the top bench, which can either be to a line defined by the angle of repose or a specified width in master units. Set to ^RS^ for angle of repose slope or put in a number to specify a width --> i.e. ^10^. The carets "^" are required.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _s_TopBenchWidth = ^10^
}
```



## **Interception Ditch and Levee Redefinable Variables**

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

The [Levee and Optional Interception Ditch](#) redefinable variables are used to draw an interception ditch and / or levee in cross section.

### **\_s\_LeveeAdjacentToDitch**

^Yes^ or ^No^ to control whether the optional levee is adjacent to the proposed ditch or if it is separated. If set to ^Yes^, the levee starting point will coincide with the tie point of the backslope of the proposed ditch. If set to ^No^, the levee will be drawn if top of levee inside and outside edges are found in the defined GEOPAK Lines DGN.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _s_LeveeAdjacentToDitch = ^No^
}
```

### **\_d\_LeveeHeight**

Defines the height of the optional levee in mater units as measured (1) from the existing ground if an interception ditch profile is not defined for the cross section station or (2) from the interception ditch profile if it exists.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_LeveeHeight = 3
}
```

### **\_d\_LeveeForeslope**

Optional levee fore slope in Run:Rise format. Run and Rise are ALWAYS a positive number.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_LeveeForeslope = 2:1
}
```

## Interception Ditch and Levee Redefinable Variables (continued)

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

### **\_d\_LeveeBackslope**

Optional levee backslope value in Run:Rise format. Rise is ALWAYS a negative number.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_LeveeBackslope = 2:-1
}
```

### **\_d\_InterceptionDitchWidth**

Optional levee interception ditch width in master units. This is a positive value and **MUST** be greater than zero.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_InterceptionDitchWidth = 2
}
```

### **\_d\_InterceptionDitchBackslope**

Optional levee interception ditch backslope value in Run:Rise format. Rise is ALWAYS a positive number. Example, 2:1. Make sure to include the colon.

EXAMPLE:

```
if (Sta >= 0+00 R 1)
{
    _d_InterceptionDitchBackslope = 2:1
}
```

Go to: [Levee and Optional Interception Ditch](#)

## Retaining Wall Redefinable Variables

Used by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

The retaining wall dimension redefinable variables control the way walls are drawn in cross section. The values **MUST** be in positive master units greater than zero unless noted otherwise.

### **\_d\_WallWidth**

Defines the width of the wall.

EXAMPLE:     if (Sta >= 0+00 R 1)  
              {  
                  \_d\_WallWidth = 1  
              }

### **\_d\_TotalFootingWidth**

Defines the total width of the footing (toe to the heel distance).

EXAMPLE:     if (Sta >= 0+00 R 1)  
              {  
                  \_d\_TotalFootingWidth = 7  
              }

### **\_d\_KeyWidth**

Defines the width of the footing key.

EXAMPLE:     if (Sta >= 0+00 R 1)  
              {  
                  \_d\_KeyWidth = 1  
              }

### **\_d\_KeyHeight**

Defines the height of the retaining wall footing key.

EXAMPLE:     if (Sta >= 0+00 R 1)  
              {  
                  \_d\_KeyHeight = 2  
              }

### **\_d\_FootingThickness**

Defines the thickness of the retaining wall footing.

EXAMPLE:     if (Sta >= 0+00 R 1)  
              {  
                  \_d\_FootingThickness = 1.5  
              }

### **\_d\_BackFootingWidth**

Defines the width of the footing behind the wall (the distance from the back of the wall to the footing heel).

EXAMPLE:     if (Sta >= 0+00 R 1)  
              {  
                  \_d\_BackFootingWidth = 4.5  
              }

### **\_d\_KeyOffset**

Defines the footing key offset (Distance from the footing toe to the front of the key).

EXAMPLE:     if (Sta >= 0+00 R 1)  
              {  
                  \_d\_KeyOffset = 1.5  
              }

Go to: [Footing Cross-Section Details](#)

## Retaining Wall Redefinable Variables (continued)

### **\_s\_WallHeight**

Either the ground surface (existing or proposed) OR a fixed value may define the height of the wall. The options are:

<sup>^</sup>GS<sup>^</sup> = Use existing and proposed ground surfaces; or

<sup>^</sup>10<sup>^</sup> for a 10 foot high wall. ALWAYS use carets.

EXAMPLE:       if (Sta >= 0+00 R 1)  
                  {  
                    \_s\_WallHeight = <sup>^</sup>GS<sup>^</sup>  
                  }

### **\_d\_DepthBelowProposedGroundInCut**

Defines the distance the top of the footing is below proposed ground in cut.

EXAMPLE:  
          if (Sta >= 0+00 R 1)  
          {  
            \_d\_DepthBelowProposedGroundInCut = 2  
          }

### **\_d\_DepthBelowExistGroundInFill**

Defines the distance from existing ground to top of footing in fill.

EXAMPLE:  
          if (Sta >= 0+00 R 1)  
          {  
            \_d\_DepthBelowExistGroundInFill = 2  
          }

Go To: [DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)

### **\_d\_BackWallHeightInCut**

Defines the height of the retaining wall footing back wall.

EXAMPLE:  
          if (Sta >= 0+00 R 1)  
          {  
            \_d\_BackWallHeightInCut = 0.5  
          }

### **\_d\_HeightAboveExistGroundInCut**

Defines the distance from existing ground to the top of the wall in cut.

EXAMPLE:  
          if (Sta >= 0+00 R 1)  
          {  
            \_d\_HeightAboveExistGroundInCut = 0  
          }

### **\_d\_HeightAbovePropGroundInFill**

Defines the height of the wall above proposed ground in fill.

EXAMPLE:  
          if (Sta >= 0+00 R 1)  
          {  
            \_d\_TotalFootingWidth = 7  
          }

Go to: [Footing Cross-Section Details](#)  
[Height Set by Elevation of the Top of the Wall](#)  
[Height Set by a Fixed Value](#)  
[Height Varies With the Ground Surface](#)

## Appendix 4 Existing Features

### Roadway



#### Existing Pavement

Drawn by Existing Features Typical Section ([ExFeat](#)).

For the existing pavement to be drawn in the cross section, an [Existing Edge of Pavement](#) must be drawn in the designated [Existing TOPO DGN](#). The symbology must match the search criteria for that **D&C Manager** item. Both edges of the pavement must cross the pattern line for it to be drawn correctly. It is recommend that any existing edges of pavement that are not to be used for showing existing pavement in the cross section view be placed in a DGN other than the one defined as the Existing TOPO DGN.

The thickness (in master units) shown in the cross-section is controlled by the redefinable variable [\\_d\\_ExistPavtThick](#).

#### Example





### Existing Paved Shoulder

Drawn by Existing Features Typical Section (ExFeat).

For the existing paved shoulder to be drawn in the cross section, an [Existing Paved Shoulder](#) line must be drawn in the designated [Existing TOPO DGN](#) at the outside edge of the shoulder and the redefinable variable [\\_s\\_ShowShoulders](#) must be set to ^yes^ for the current station. The symbology must match the search criteria for that **D&C Manager** item. It must be on the outside of the corresponding Existing Edge of Pavement line since the paved shoulder will be drawn from the existing edge of pavement to the existing edge of shoulder as shown the figures below.

The thickness (in master units) shown in the cross-section is controlled by the redefinable [\\_d\\_ExistShouldThick](#).

Example





### Existing Curb and Gutter

Drawn by Existing Features Typical Section (ExFeat).

For the existing curb to be drawn in the cross section, an **Existing Curb** line (matching the search criteria for that **D&C Manager** item) must be drawn in the designated **Existing TOPO DGN** outside of an Existing Edge of Pavement line within the allowable search distance set by **\_d\_CurbSearchDistance**. In addition, the redefinable variable **\_s\_ShowCurbandGutter** must be set to ^yes^ for the current station. The Existing Curb line only indicates the presence of an existing curb. It **does not** indicate the offset of the curb. Rather, the existing curb is drawn using the following parameters: The Existing Edge of Pavement line determines the inside edge of the curb or curb & gutter (this point is marked with the text 'eop' in the cross section views in the figures shown below); **\_d\_ExistCurbGutterThick** determines the depth of the inside face, as measured down from the top of the existing surface (see the upper right cross section view); **\_d\_ExistCurbGutterWidth** locates the back of the curb as measured out from the edge of pavement (see the upper right cross section view); a vertical line is drawn from that point to existing ground. In most cases **the user will need to manually place the existing edge of pavement line** at the proper location for the criteria to work. If the existing curb line already exists in the drawing, the easiest way to place the existing edge of pavement line is to offset the existing curb line by the appropriate distance using the MicroStation **Copy Parallel** tool with the Existing Edge of Pavement line selected in **D&C manager** and **Place Influence** activated.

Example




## Existing Paved Surfaces

Drawn by Existing Features Typical Section ([ExFeat](#)).

For existing paved surfaces to be drawn in the cross section, [Existing Paved Surface](#) lines must be drawn in the designated [Existing TOPO DGN](#) and the redefinable variable [\\_s\\_ShowPavedSurface](#) must be set to ^yes^ for the current station. The symbology must match the search criteria for that **D&C Manager** item. Both edges of the existing paved surface must cross the pattern line for it to be drawn correctly. It is recommend that any existing paved surface lines that are not to be used for showing existing paved surface in the cross section view be placed in a DGN other than the one defined as the Existing TOPO DGN.


The thickness (master units) shown in the cross-section is controlled by the redefinable variable [\\_d\\_ExistPavedSurfaceThick](#).

Example



Topo View

(The existing edge of pavement and the existing paved surface lines are plotted on top of each other at their common location)



Cross-Section View



# Roadside



## Existing Sidewalks

Used by Existing Features Typical Section ([ExFeat](#)).

For an existing sidewalk to be drawn in the cross section, [Existing Sidewalk](#) lines must be drawn in the designated [Existing TOPO DGN](#) and the redefinable variable [\\_s\\_ShowSidewalk](#) must be set to ^yes^ for the current station. The symbology must match the search criteria for that **D&C Manager** item. Both edges of the sidewalk must cross the pattern line for it to be drawn correctly.

The thickness (in master units) shown in the cross-section is controlled by the redefinable variable [\\_d\\_ExistSidewalkThick](#).

Example



Cross-Section View

## Drainage



### Existing Paved Ditches

Drawn by Existing Features Typical Section ([ExFeat](#)).

For existing paved ditches to be drawn in the cross section, [Existing Paved Ditch](#) lines must be drawn in the designated [Existing TOPO DGN](#) and the redefinable variable [\\_s\\_ShowPavedDitch](#) must be set to ^yes^ for the current station. The symbology must match the search criteria for that **D&C Manager** item. Both edges of the existing paved ditch must cross the pattern line for it to be drawn correctly.

The thickness (in master units) shown in the cross-section is controlled by the redefinable variable [\\_d\\_ExistPavedDitchThick](#).

Example:



## Property

### Existing Buildings



Marked by Existing Features Typical Section (**ExFeat**).

For existing building edges to be marked in the cross sections; **Existing Building** lines must be drawn in the designated **Existing TOPO DGN** and the redefinable variable **\_s\_ShowBuildings** must be set to ^yes^ for the current station. The symbology must match the search criteria for that **D&C Manager** item.

The height of the line shown in the cross-section is controlled by the redefinable variable **\_d\_ExistingFeatureLineHeight**, which is specified in master units.

The variable **XS Scale** controls the size of the text “BLDG”.

Example



## Utilities

### Existing Railroads


Marked by Existing Features Typical Section ([ExFeat](#)).

For the center line of existing railroad tracks to be marked in the cross sections; [Existing Railroad](#) lines must be drawn in the designated [Existing TOPO DGN](#) and the redefinable variable [\\_s\\_ShowRailroadTracks](#) must be set to ^yes^ for the current station. The symbology must match the search criteria for that **D&C Manager** item.

The height of the line shown in the cross-section is controlled by the redefinable variable [\\_d\\_ExistingFeatureLineHeight](#), which is specified in master units.

The variable [XS Scale](#) controls the size of the text “EX\_RR”.

Example



# Safety and Structures

## Existing Wall


Marked by Existing Features Typical Section ([ExFeat](#)).

For existing retaining walls to be marked in the cross sections; [Existing Wall](#) lines must be drawn in the designated [Existing TOPO DGN](#) and the redefinable variable [\\_s\\_ShowRetainingWall](#) must be set to ^yes^ for the current station. The symbology must match the search criteria for that **D&C Manager** item.

The height of the line shown in the cross-section is controlled by the redefinable variable [\\_d\\_ExistingFeatureLineHeight](#), which is specified in master units.

The variable [XS Scale](#) controls the size of the text “EX\_WALL”.

Example



## Appendix 5 Pavement

Drawn by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

### Pavement

Up to seven different layers may be drawn within the pavement structure. They are four pavement layers (bituminous or concrete), two aggregate sub base layers and a rock fill base layer. Only the first pavement layer is required to have a value other than zero. In addition, a compensating depth line may be drawn. Lastly, optional underdrains may be shown on the cross-sections.

[Edge of Pavement](#) lines must be drawn in the designated [Proposed Plan DGN](#) for new pavement to be drawn in the cross sections.



How the pavement is closed is controlled by the redefinable variable [\\_s\\_PavementType](#), which must be set to either ^C^ for concrete pavement with a vertical closure or to ^B^ for bituminous pavement with a 1:1 closure.

The redefinable variable [\\_d\\_NormalPavementSlope](#) defines the normal pavement slope in percent on tangent sections. This is typically a -2 percent or similar. This value directly affects the way super elevation transitions are handled. It represents normal pavement crown slope when no super elevation is present. Do not include the percent sign. Do include the negative sign when applicable. The superelevation slope is obtained from the shape cluster in the DGN defined in the Shapes section of the Proposed Cross-Section run.

### Concrete Pavement

Since concrete pavement typically has only one layer of pavement, the redefinable variable [\\_d\\_PavementLayer1Thick](#) is set to the full pavement depth in master units. The bottom aggregate layer is drawn with the 18-inch extension as required by PDM section 6-03.7 paragraph (3).


Example




### Bituminous Pavement

Bituminous pavement can be drawn as one layer by assigning the full pavement depth to `_d_PavementLayer1Thick` (in master units) and leaving the other pavement layer thickness variables set to zero (0), as shown in Example 1 below. It can also be drawn with up to four (4) layers using `_d_PavementLayer1Thick`, `_d_PavementLayer2Thick`, `_d_PavementLayer3Thick`, and `_d_PavementLayer4Thick` for the top through bottom layers respectively, as shown in Example 2. See PDM Sec 6-03.4 for more information on pavement layer thicknesses for flexible (bituminous) pavement design. Any aggregate layers have a 1:1 closure.

Example 1



Example 2



Cross-Section View Showing Possibility of Having Up To Four (4) Pavement Layers


# Base Considerations

The pavement base material can be drawn using either an aggregate or a rock base. See PDM Section 6-03.7 for a full discussion of which base should be used for a project. The information provided here relates only to how the criteria draw the base, not which base should be used.


## Aggregate Base

One or two aggregate base layers may be drawn. If values greater than zero are assigned to both [\\_d\\_Aggbase1Thickness](#) and [\\_d\\_Aggbase2Thickness](#), two layers will be drawn and the upper layer will be drawn as a permeable base. If only one layer is needed, [\\_d\\_Aggbase1Thickness](#) must be greater than zero and [\\_d\\_Aggbase2Thickness](#) must be set to zero. All values are in master units.

Example 1: Aggregate base under concrete (rigid) pavement




Cross-Section View of One Aggregate Base




Cross-Section View of Two Aggregate Bases

Example 2: Aggregate base extension under concrete (rigid) pavement

For concrete pavement, the 18" aggregate extension can either be drawn at the pavement or the shoulder slope, as determined by the setting for the redefinable variable [\\_s\\_ExtensionSlope](#). Set it either to ^P^ for drawing the extension at the pavement slope or to ^S^ for drawing the extension at the shoulder slope. The carets "^" are required.




Aggregate Extension at Pavement Slope




Aggregate Extension at Shoulder Slope

Example 3: Aggregate base under bituminous (flexible) pavement



Cross-Section View of One Aggregate Base



Cross-Section View of Two Aggregate Bases




## Rock Base


For the rock base to be drawn correctly, both [\\_d\\_Aggbase1Thickness](#) and [\\_d\\_Aggbase2Thickness](#) must be set to zero.

There are three redefinable variables that control how the rock base is drawn. The rock thickness as measured down from the bottom of the pavement in master units is set by [\\_d\\_RockFillBaseThickness](#). Whether the rock base is daylighted on tangent sections and on the low side of super elevated sections is determined by [\\_s\\_RockFillBaseDaylight](#) (^Yes^ to daylight or ^No^ to not daylight). The last variable [\\_s\\_RockFillBaseDaylightHSS](#) determines if the rock base is to daylight on the high side of super elevated pavement, which according to current design practice should always be set to ^No^.


Example 1: Earth covered rock base on a superelevated section with [\\_s\\_RockFillBaseDaylight](#) set to ^No^.



Example 2: Daylighted rock base on a tangent section with [\\_s\\_RockFillBaseDaylight](#) set to ^Yes^.




Example 3: Daylighted rock base on a superelevated section with [\\_s\\_RockFillBaseDaylight](#) set to ^Yes^.



## Compensating Depth

A line can be drawn at a fixed distance below the pavement surface. This line is projected to proposed ground. To have this line included, set [\\_d\\_CompensatingDepth](#) to the desired depth in master units.

Example



# Under Drain

The only underdrains drawn by the criteria are the pavement edge drains required for medium and heavy duty routes without a daylighted rock base. See PDM Section 6.02 and MoDOT Standard Plan 605.10 for further design information.

The two redefinable variables `_s_DrawLeftUnderdrain` and `_s_DrawRightUnderdrain` control whether or not edge drains are drawn on the left and right side respectively. Set the variables as `^Yes^` to draw the drain and as `^No^` to not draw them. Even if the variable is set to `^Yes^`, the edge drain will **not** be drawn on the *high* side of super elevated pavement.


The width of the underdrain is determined by `_d_UnderdrainWidth`. Based on MoDOT Standard Plan 605.10, the width of an edge drain is always 1'; therefore leave this variable set to its default value of 1.

The depth of the drawn underdrain is controlled by the redefinable variable `_d_UnderdrainHeight` in master units and varies depending upon the number of aggregate layers, according to MoDOT Standard Plan 605.10. Each case is covered below:


## One Aggregate Layer

If there is one aggregate layer `_d_UnderdrainHeight` should be set to 8/12.

Example



Underdrain Under Concrete Pavement



Underdrain Under Bituminous Pavement

## Two Aggregate Layers

If there are two aggregate layers `_d_UnderdrainHeight` should be set to 12/12.

Example



Underdrain Under Concrete Pavement



Underdrain Under Bituminous Pavement

## Appendix 6 Reconstruction

Drawn by pavement reconstruction typical sections ([DRecon](#), [NLtRRt](#), [NRtRLt](#), & [URECon](#)).

The reconstruction criteria draw up to two overlay layers and an optional widening with bituminous or concrete pavement using either a "match existing" or "crown correction" approach, as controlled by the redefinable variables [\\_s\\_OverlayType](#) and [\\_s\\_WideningSlope](#).

Up to two overlay layers may be drawn between either the [Existing Edge of Pavement](#) or [Proposed Saw Cut](#) lines. The thickness of these layers is controlled by the redefinable variables [\\_d\\_OverlayThickness1](#) and [\\_d\\_OverlayThickness2](#), respectively. In addition, up to seven different layers within the proposed widening pavement structure are allowed. Only the first pavement layer is required to have a value other than zero for both the overlay section as well as the full depth widening section. Four pavement layers, two optional aggregate sub base layers, and the optional proposed rock fill base layer may be drawn within the widening pavement structure. Lastly, optional underdrain may be shown on the cross-sections.

Proposed widening starts at a proposed saw cut line if this line is inside the proposed edge of pavement. If no saw cut line is found, proposed widening starts at the existing edge of pavement if this line falls inside the proposed edge of pavement. If neither line is found inside the proposed edge of pavement the overlay extends to the proposed edge of pavement with no full depth widening.

**IMPORTANT:** An even number of edges of existing pavement are required in the 2D Topo file. If a cross section pattern line crosses an odd number of existing edges of pavement the criteria will not process and an error message is drawn.

When the overlay type CC (crown correction) is chosen, shapes are used to provide cross slope information only. The shapes can be very narrow (such as two feet wide for example). The proposed profile required for the shapes is only used as a vertical reference if the variable [\\_s\\_OverlayOffsetLocation](#) is set to ^P^ for profile. If this variable is set to any other option, the proposed profile is ignored. If the profile is ignored, only a straight-line profile containing a beginning and ending VPI is required. Make sure that the elevations for the proposed profile are close to the elevations of the project. These shapes are sometimes referred to as "dummy" shapes. They are drawn onto the cross sections and need to be deleted after the cross sections are processed. They are simply being used to provide cross slope information for the widening. No vertical references are utilized from these shapes if [\\_s\\_OverlayOffsetLocation](#) = ^L^ or ^C^ or ^R^ for left, center, or right respectively. Instead, the existing ground at the location specified by this variable sets the top of the pavement elevation. However, if this variable is set to ^P^, the proposed profile is used to dictate the elevation of the top of pavement at the profile grade location.

When the overlay type ME (match existing) is chosen "dummy shapes" are still required. They are required for the criteria to process.

## Appendix 7 Rural Shoulders

Drawn by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

For U1 Shoulders details see [Curbing With Urban Shoulders \(U1 & U2\)](#).


### Determining Shoulder Width and Type

The width and type of shoulder can be specified in two different ways. They can be determined either by an edge of shoulder line in the Proposed Plan DGN or from redefinable variables.


If used, the edge of shoulder lines must be drawn in the designated [Proposed Plan DGN](#). The symbology must match the search criteria for the respective type of shoulder in the **D&C Manager**. To draw the lines use the D&C Manager items **EOS New Conc.**, **EOS New Asph.**, or **EOS New Aggr.**, or **EOS New Earth** depending upon the type of shoulder to be drawn. These items are located in the D&C Manager path: "**Design Standards/Roadway**". For the line to be recognized by the criteria, it must be located within the search distance specified by the redefinable variables [\\_d\\_OutsideShoulderSearchDistance](#) and [\\_d\\_MedianShoulderSearchDistance](#) in master units. This distance is measured from the proposed edge of pavement. This variable is required to avoid locating a plan view shoulder element from an adjacent or parallel roadway. This number **MUST** be greater than zero.

If an edge of shoulder line is not found within the applicable search distance, redefinable variables are used to determine the width and type of shoulder. The variables [\\_d\\_OutsideShoulderWidth](#) and [\\_d\\_MedianShoulderWidth](#) control the width (master units) of the shoulder; while the shoulder type is controlled by [\\_s\\_OutsideShoulderType](#) or [\\_s\\_MedianShoulderType](#), which may be set to ^C^ for concrete, ^B^ for bituminous, ^A^ for aggregate, or ^E^ for earth shoulders. A plan element **ALWAYS** "overrides" these variables.

Example



Proposed Plan View with an Edge of Shoulder Line within Search Distance to Control Shoulder Width



Proposed Plan View without an Edge of Shoulder Line within Search Distance. Variable Controls Width

# Shoulders In Cross Section

The user has the option of whether to label the edge of shoulder elevation and offset by setting the value for the redefinable variable [\\_s\\_LabelShoulderElevations](#). Set it to either ^Yes^ or ^No^. Note that if the labels are drawn, they are drawn as part of graphic group to allow for easy manipulation. The carets "^" are required.

Five additional redefinable variables are provided to control how the shoulders are drawn in cross section. Their values need to be set by the user based on the type of shoulder drawn. The following sections give the values needed for the different types of shoulder used by MoDOT, based upon PDM Figures 6-03.1 thru 6-03.9. If the PDM should be updated, please use the values from the update rather than those given below.



## Type A and Type A1 Shoulders (Full Pavement Depth Shoulders)

Type A shoulder is used for all medium and heavy duty pavements as specified in PDM Figures 6-03.6 thru 6-03.9. Type A1 shoulder is used on all non-curbed medians (PDM Figures 6-03.4, 6-03.7, & 6-03.8). The shoulder type needs to be concrete or bituminous.

Both the outside and median shoulder slope is -2% on tangent, so the redefinable variables [\\_d\\_NormalOutsideShoulderSlope](#) and [\\_d\\_NormalMedianShoulderSlope](#) should both be set to -2.

The shoulder layer thickness values for [\\_d\\_ShoulderLayer1Thick](#), [\\_d\\_ShoulderLayer2Thick](#), [\\_d\\_ShoulderLayer3Thick](#), and [\\_d\\_ShoulderLayer4Thick](#) should match the values for the corresponding pavement layer thickness. This allows for a continuation of the pavement layers between the pavement and shoulder since the cross sections do not indicate the location of any joints. It is also required to have the aggregate base under the pavement extend under the shoulder as well.

## Examples



**Type A2 Shoulders (Partial Pavement Depth Bituminous Shoulders)**

Type A2 shoulder is used on the outside of light duty pavements with ADT greater than 3500 (PDM Figures 6-03.3 thru 6-03.5). The shoulder type must be bituminous to have the correct shoulder closure.

Since all paved shoulders have a -2% cross slope, [\\_d\\_NormalOutsideShoulderSlope](#) should both be set to -2.

To show each of the bituminous layers, [\\_d\\_ShoulderLayer1Thick](#) and [\\_d\\_ShoulderLayer2Thick](#) should be set to 1.75/12 and 4/12, respectively.

The shoulder aggregate layer obtains its thickness from [\\_d\\_ShoulderLayer3Thick](#). If the pavement has a rock base, it should be set to the total pavement thickness in master units minus 5.75/12 so that the shoulder aggregate extends down to the rock base. When a rock base is not present, [\\_d\\_ShoulderLayer3Thick](#) is 4/12. For this shoulder type [\\_d\\_ShoulderLayer4Thick](#) should always be zero (0).

**Example 1 Pavement and Shoulder Without Rock Base**




Concrete (Rigid) Pavement and Type A2 Shoulder



Bituminous (Flexible) Pavement and Type A2 Shoulder

**Example 2 Pavement and Shoulder on Rock Base**



Concrete (Rigid) Pavement and Type A2 Shoulder



Bituminous (Flexible) Pavement and Type A2 Shoulder

### Type B Shoulders (8" Aggregate Shoulders)

Type B shoulder is for light duty pavement & ADT of 1700-3500 (PDM Figure 6-03.2). The shoulder type must be aggregate and [\\_s\\_ExtensionSlope](#) should be set to ^S^ shoulder slope.


Since all non-paved shoulders have a -4% cross slope, [\\_d\\_NormalOutsideShoulderSlope](#) should both be set to -4.

Since the aggregate is 8" thick, [\\_d\\_ShoulderLayer1Thick](#) should be 8/12. The redefinable variable values for the rest of the layers are ignored ([\\_d\\_ShoulderLayer2Thick](#), [\\_d\\_ShoulderLayer3Thick](#), & [\\_d\\_ShoulderLayer4Thick](#)).

Example



Concrete (Rigid) Pavement and Type B Shoulder



Bituminous (Flexible) Pavement and Type B Shoulder


### Type C Shoulders (6" Aggregate Shoulders)

Type C shoulder is for light duty pavement & ADT of 750-1700 (PDM Figure 6-03.1). The shoulder type must be aggregate and [\\_s\\_ExtensionSlope](#) should be set to ^S^ shoulder slope.


Since all non-paved shoulders have a -4% cross slope, [\\_d\\_NormalOutsideShoulderSlope](#) should both be set to -4.

Since the aggregate is 6" thick, [\\_d\\_ShoulderLayer1Thick](#) should be 6/12. The redefinable variable values for the rest of the layers are ignored ([\\_d\\_ShoulderLayer2Thick](#), [\\_d\\_ShoulderLayer3Thick](#), & [\\_d\\_ShoulderLayer4Thick](#)).

Example



Concrete (Rigid) Pavement and Type C Shoulder



Bituminous (Flexible) Pavement and Type C Shoulder



### Type D Shoulders (3" Minimum Aggregate Shoulders)

Type D shoulder is for light duty pavement & ADT of 400-750 (PDM Figure 6-03.1). The shoulder type must be aggregate and [\\_s\\_ExtensionSlope](#) should be set to ^P^ Pavement slope.

Since all non-paved shoulders have a -4% cross slope, [\\_d\\_NormalOutsideShoulderSlope](#) should both be set to -4.

Since the minimum aggregate thickness is 3", [\\_d\\_ShoulderLayer1Thick](#) should be set to a minimum of 3/12. The redefinable variable values for the rest of the layers are ignored ([\\_d\\_ShoulderLayer2Thick](#), [\\_d\\_ShoulderLayer3Thick](#), & [\\_d\\_ShoulderLayer4Thick](#)).

Example





### Type E Shoulders (Earth Shoulders)

Type E shoulder is for light duty pavement & ADT < 400 (PDM Figure 6-03.1) and [\\_s\\_ExtensionSlope](#) should be set to ^P^ Pavement slope.

Since all non-paved shoulders have a -4% cross slope, [\\_d\\_NormalOutsideShoulderSlope](#) should both be set to -4.

The shoulder type should be set to earth so that the layer redefinable variables [\\_d\\_ShoulderLayer1Thick](#), [\\_d\\_ShoulderLayer2Thick](#), [\\_d\\_ShoulderLayer3Thick](#), & [\\_d\\_ShoulderLayer4Thick](#) are ignored.

Example





## Appendix 8 Curbing With Urban Shoulders (U1 & U2)

Drawn by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)).

### Plan View Geometry

#### Curbing


The **type** of curb drawn in a proposed cross section is determined by an element in the defined [Proposed Plan DGN](#). This line must have the attribute matching the pay item for the desired type of curb, which is obtained from the **Design and Computation Manager** item in the **Payitems/Roadway/Curb** folder shown in the figure to the right. The line must be located within a specified curb search distance from the proposed edge of paved surface. For curb and gutter (Types A & B) this may be the edge of pavement or the edge of shoulder. For all other curb types, the edge of paved surface must be a shoulder.

The specified curb search distance is obtained from the redefinable variable: [\\_d\\_CurbSearchDistance](#), which must be a positive number in master units.

The **location** of the curb in the proposed cross section is determined by the proposed edge of paved surface in the Proposed Plan DGN. This line indicates the start of the gutter section for a curb & gutter (Type A, B, or Misc. - Special) or the gutter line for an integral (Type A, B, F, M, N, or O) or a separated curb (Type F or S). Consequently, the curb line shown in the Proposed Plan DGN can be drawn at either the front or the back of the curb without affecting the location of the curb in the proposed cross section.

#### U1 Shoulder

U1 shoulders use the same parameters as Type A, A1, or A2 shoulders. As with rural shoulders, the width and type is obtained either from a plan view element or from the redefinable variables. See [Appendix 7 Rural Shoulders](#) for further details.



## U2 Shoulder


The presence of a U2 shoulder behind the curb can be indicated in two ways: either by placing an edge of U2 shoulder line in the Proposed Plan DGN or by defining a U2 shoulder width using a redefinable variable.

To draw U2 shoulder lines in the designated Proposed Plan DGN, use the **Design and Computation Manager** items EOS U2 Asphalt or EOS U2 Earth. These items (outlined in the figure to the right) are in the **Design Standards/Roadway** folder. For the line to be recognized by the criteria, it must be located within the search distance (master units) specified by the redefinable variable d\_U2ShoulderSearchDistance, as measured from the back of the curb.


If a U2 edge of shoulder line is not found within the applicable search distance, the criteria uses d\_U2ShoulderWidth to determine the width of the U2 shoulder in master units from the back of the curb. If a U2 shoulder is not needed, do not have a U2 shoulder line within the search distance in the Proposed Plan DGN and set d\_U2ShoulderWidth to zero. The plan element **ALWAYS** "overrides" this variable.

The slope of the U2 Shoulder is controlled by d\_U2ShoulderSlope.

If an EOS U2 Asphalt line or d\_U2ShoulderWidth is used to specify the width of the U2 shoulder, subsurface shoulder lines may be drawn in the proposed cross section by specifying the appropriate thicknesses (in master units) for the Redefinable Variables d\_U2ShoulderThickness (for the asphalt thickness) and d\_U2ShoulderAggbaseThickness (for the aggregate base thickness). If an EOS U2 Earth line is used to indicate the presence of a U2 shoulder, the values of the two thickness variables are ignored and only the surface line is drawn.



The only type of curb that can be drawn behind the U2 shoulder is Type S (Separated) curb. If this type of curb is desired, include a line in the Proposed Plan DGN using the appropriate D&C curb pay item on the outside of the U2 shoulder within the search distance defined by d\_CurbSearchDistance, which must be less than the width of the U2 shoulder and is measured from the outer edge of the U2 shoulder. The face of the curb will be drawn at the outer edge of the U2 shoulder in the proposed cross section.



## Curbing Cross-Section Details

### Curb & Gutter

Curb & gutter can be placed adjacent to any paved surface (pavement or shoulder), which can be either concrete or asphalt. If the curb & gutter is placed next to a shoulder, the shoulder thicknesses must match the pavement thickness for the pavement base aggregate to extend under the curb & gutter. The outer edge of paved surface locates the inner face of the gutter in the proposed cross section.

#### Type A (Mountable) Curb & Gutter


In the Proposed Plan DGN, the line for [Curb & Gutter Type A](#) needs to have the attribute of pay item 609-10.51.

#### Type B (Barrier) Curb & Gutter

In the Proposed Plan DGN, the line for [Curb & Gutter Type B](#) Type B Curb and Gutter needs to have the attribute of pay item 609-10.52.

#### User Defined Curb & Gutter


The user can define a special curb and gutter by placing a line in the Proposed Plan DGN having the attribute of pay item 609-99.03. If this line is within the search distance the criteria draws a non-standard curb and gutter using the redefinable variables shown in the figure to the right. The values for [\\_d\\_GutterSlope](#) and [\\_d\\_GutterBaseSlope](#) are in percent (%) and all other values are in master units.



#### Warning for Curb & Gutter

If the bottom of the pavement is not below the bottom of the curb and gutter, the criteria will not extend the aggregate under the curb and gutter. Instead, the aggregate layers will stop at the face of the gutter and the following note will be plotted in the cross-section:

**Warning, AggBase1 Depth Not Able to Extend Under Curb!** It is assumed that the pavement structure will be at least as thick and the gutter.



#### Gutter Slope on High Side of Super Elevation

Using the normal slope for curb and gutter on the high side of super elevation will result in the gutter holding water. If this is not desirable, set the redefinable variable [\\_s\\_GutterSlopeInSuper](#) to ^U^ for the gutter slope to be up on the side of super elevation. If it is permissible for it to hold water set the variable to ^D^ for the gutter slope to be down.



### Separated Curb

In the Proposed Plan DGN, the curb line with the appropriate pay item attribute can be anywhere within the curb search distance from the edge of a shoulder, which indicates where the gutter line will be drawn in the Proposed Cross-Section DGN.

**Note:** Even though the Standards Plans allow for the height of the curb below the paved surface to be less than the default value if the curb is keyed into rock, the default value is always used.


#### Type S Separated Barrier Curb

In the Proposed Plan DGN, the line for Type S Curb needs to have the attribute of pay item 609-10.10 [Concrete Curb Type S 6 Inch And Under](#) or 609-10.11 [Concrete Curb Type S Over 6 Inch](#), which can be placed after either a U1 or a U2 shoulder. If the criteria file finds a curb line having either pay item within the search distance, it will draw a Type S (Separated) Curb using the value of the Redefinable Variable [\\_d\\_IntegralCurbHeight](#) to specify the curb height in master units.



#### Type F (Separated) Low Profile Curb

In the Proposed Plan DGN, the line for the Type F Curb needs to have the attribute of pay item 609-20.32 [Low Profile Curb Type F](#).



### Gutter Details

Gutter may be drawn after a shoulder or a retaining wall in cut. The outer edge of the shoulder or the back of the retaining wall locates the start of the gutter. If a gutter line with the appropriate pay item attribute is found anywhere within the curb search distance in the Proposed Plan DGN, gutter will be drawn in the Proposed Cross-Section DGN.

#### Type A Gutter

In the Proposed Plan DGN, the line for the [Gutter Type A](#) needs to have the attribute of pay item 609-10.41.





#### Type B Gutter

In the Proposed Plan DGN, the line for the [Gutter Type B](#) needs to have the attribute of pay item 609-10.42.



## Integral Curb Types A, M, O, and E

In the Proposed Plan DGN, the curb line with the appropriate pay item attribute can be anywhere within the curb search distance from the edge of shoulder, which indicates where the gutter line will be drawn in the Proposed Cross-Section DGN. To be drawn correctly, all types of integral curb require a concrete U1 shoulder to be defined. The thickness of the U1 shoulder is controlled by the redefinable variable `_d_ShoulderLayer1Thick`. If its value matches `_d_PavementLayer1Thick`, the aggregate under the pavement will extend under both the shoulder and the curb. If the thickness of the U1 shoulder is different from the pavement, aggregate base(s) can be drawn under the shoulder and curb by specifying a value greater than zero (0) for the thickness of the appropriate shoulder layer(s) using the redefinable variables `_d_ShoulderLayer2Thick`, `_d_ShoulderLayer3Thick`, and `_d_ShoulderLayer4Thick`.



### Type A Integral Barrier Curb

In the Proposed Plan DGN, the line for the Type A Integral Curb needs to have the attribute of pay item 609-20.11 [Integral Curb Type A 6 Inch And Under](#) or 609-20.21 [Integral Curb Type A Over 6 Inch](#). If the criteria file finds a curb line having either pay item within the search distance, it will draw a Type A Integral Curb using the value of the Redefinable Variable `_d_IntegralCurbHeight` to specify the curb height in master units.

### Type E (Integral) Low Profile Curb

In the Proposed Plan DGN, the line for the Type E Integral Low Profile Curb needs to have the attribute of pay item 609-20.31 [Low Profile Curb Type E](#).

### Type M (Integral) Mountable Curb


In the Proposed Plan DGN, the line for the Type M Integral Curb needs to have the attribute of pay item 609-20.13 [Integral Curb Type M](#).

### Type O (Integral) Mountable Curb


In the Proposed Plan DGN, the line for the Type O Integral Mountable Curb needs to have the attribute of pay item 609-20.15 [Integral Curb Type O](#).

## Integral Curb Types B and N

In the Proposed Plan DGN, the curb line with the appropriate pay item attribute can be anywhere within the curb search distance from the edge of shoulder, which indicates where the gutter line will be drawn in the Proposed Cross-Section DGN. To be drawn correctly, all types of integral curb require a concrete U1 shoulder to be defined. The total thickness of the U1 shoulder is the algebraic sum of the redefinable variables [\\_d\\_ShoulderLayer1Thick](#) and [\\_d\\_ShoulderLayer2Thick](#), where the first variable controls the thickness of the overlay and the second controls the thickness of the concrete portion of the shoulder. For the aggregate base under the pavement to extend under the U1 shoulder and the curb, the thicknesses of the pavement and corresponding shoulder layers must be the same ([\\_d\\_PavementLayer1Thick](#) equals [\\_d\\_ShoulderLayer1Thick](#) and [\\_d\\_PavementLayer2Thick](#) equals [\\_d\\_ShoulderLayer2Thick](#) for that station). If the respective pavement and shoulder layers have different thicknesses, aggregate base(s) can be drawn under the shoulder and curb by specifying a value greater than zero (0) for the thickness of the appropriate shoulder layer(s) using the redefinable variables [\\_d\\_ShoulderLayer3Thick](#), and [\\_d\\_ShoulderLayer4Thick](#).



U1 Shoulder Thicknesses Equal  
Pavement Thicknesses



U1 Shoulder Thicknesses Do Not  
Equal Pavement Thicknesses

### Type B Integral Barrier Curb

In the Proposed Plan DGN, the line for the Type B Integral Curb needs to have the attribute of pay item 609-20.12 [Integral Curb Type B 6 Inch And Under](#) or 609-20.22 [Integral Curb Type B Over 6 Inch](#). If the criteria file finds a curb line having either pay item within the search distance, it draws a Type B Integral Curb using the value of the Redefinable Variable [\\_d\\_IntegralCurbHeight](#) to specify the curb height in master units.

### Type N (Integral) Mountable Curb

In the Proposed Plan DGN, the line for the Type N Integral Curb needs to have the attribute of pay item 609-20.14 [Integral Curb Type N](#).

## Appendix 9 Standard Side Slopes


All pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)) draw standard side slopes, which are **drawn without special profiles**.

### Standard Side Slope Closure Options

The side slope can close to existing ground using a standard section in cut and fill or a special forced closure section. These options are briefly described on the rest of this page with further details provided in the rest of this appendix. The typical section may also include other items, such as [Special Ditches](#), [Sidewalk](#) located in a [Berm](#), varying side slope values using a [Tapering Procedure](#), [Rock Benches](#), [Retaining Walls](#), [Gore Areas](#), a [Levee and Optional Interception Ditch](#). These options are described in other appendices. To stop a side slope at a match line, see [Appendix 12 Match Lines](#).


### Standard Cut Slope Options

A ditch fore slope and back slope are required if a standard cut section is used, which are labeled as Ditch Fore Slope 2 and Ditch Back Slope in the following figure. In addition the user can include a berm, an additional ditch fore slope, and a ditch width.



### Standard Fill Slope Options

A single fore slope is required if a standard fill section is used, which is labeled as Fill Slope 1 in the figure to the right. In addition the user can include a berm and an additional fore slope.



### Standard Forced Closure Slope Option

The user can force the side slope to close directly to existing ground from the edge of shoulder or back of curb by using this option.



Side Slope Details

Berm


Drawn by all pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), [NRtRLt](#), [UNPavt](#), & [URECon](#)). The optional berm is intended to be used for non-paved guardrail widening, grass areas for locating [Sidewalk](#), and other cases that require a slope defined by percent at the start of the side slope. It may be used in cut or fill and is drawn as part of the [Standard Side Slopes](#).

Berm Width


The width of the berm can be specified in two ways. It can be determined either by a berm line in the GEOPAK Lines DGN or by a redefinable variable.

Berm lines may be drawn in the designated [GEOPAK Lines DGN](#). To draw the lines use the **D&C Manager** item [Berm Line](#), which is located in the D&C Manager path: “**Design Standards/Roadway/**”.

If a berm line is not present, the redefinable variables [\\_d\\_BermWidth\\_Left](#) and [\\_d\\_BermWidth\\_Right](#) are used to determine the width of the berm in master units on the left and right side, respectively. A plan element **ALWAYS** "overrides" these variables.



GEOPAK Lines DGN with a Berm Line  
DGN Element Controls Berm Width



GEOPAK Lines DGN without a Berm Line  
Redefinable Variable Controls Berm Width

If a berm is not desired at a particular location, do not have a berm line crossing the pattern line on that side of the roadway and set the berm width redefinable variable for that location to zero.

Berm Slope

The berm slope on each side of the roadway is controlled by the redefinable variables [\\_d\\_BermSlope\\_Left](#) and [\\_d\\_BermSlope\\_Right](#) (in percent without the percent sign). Include the negative sign when applicable.



### Ditch Fore Slope 1 (Optional)

The ditch fore slope 1 option is provided if a change in the run:rise defined slope is required before the ditch.

The width of the ditch fore slope 1 can be specified in two ways. It can be determined either by a cut slope 1 break line in the GEOPAK Lines DGN or by a redefinable variable.

A [Cut Slope 1 Break Line](#) may be drawn in the designated [GEOPAK Lines DGN](#). To draw the line use the **D&C Manager** item **Slope Cut**, which is located in the D&C Manager path: "**Design Standards/Drainage**".

If a slope cut line is not present, the redefinable variables [\\_d\\_DitchForeSlope1Width\\_Left](#) and [\\_d\\_DitchForeSlope1Width\\_Right](#) are used to determine the width of the ditch fore slope 1 in master units on the left and right side, respectively. A plan element **ALWAYS** "overrides" these variables.

If a ditch fore slope 1 is not desired at a particular location, do not have a slope cut line crossing the pattern, set the ditch fore slope 1 width redefinable variable to zero, or make ditch fore slope 1 the same as ditch fore slope 2.

The ratio of ditch fore slope 1 is controlled by the redefinable variables [\\_d\\_DitchForeSlope1\\_Left](#) and [\\_d\\_DitchForeSlope1\\_Right](#) in Run:Rise format. Rise is ALWAYS a negative number. Example, 4:-1. Make sure to include the colon.

### Ditch Fore Slope 2 (Required)

The ratio of ditch fore slope 2 is controlled by the redefinable variables [\\_d\\_DitchForeSlope2\\_Left](#) and [\\_d\\_DitchForeSlope2\\_Right](#) in Run:Rise format. Rise is ALWAYS a negative number. Example, 4:-1. Make sure to include the colon. This slope will be continued from its start to the bottom of the ditch.

### Standard Ditch Depth

The depth a standard ditch is controlled by [\\_d\\_StandardDitchDepth\\_Left](#) and [\\_d\\_StandardDitchDepth\\_Right](#), which is measured from the start of the ditch fore slope in master units. This is a positive value and MUST be greater than zero.

### Ditch Width

The width of the ditch is controlled by the redefinable variables [\\_d\\_DitchWidth\\_Left](#) and [\\_d\\_DitchWidth\\_Right](#) in master units. Set the value of the variable to zero for a "V" ditch or greater than zero for a flat bottom ditch.

### Ditch Back Slope (Required)

The ratio of ditch back slope is controlled by the redefinable variables [\\_d\\_DitchBackSlope\\_Left](#) and [\\_d\\_DitchBackSlope\\_Right](#) in Run:Rise format. Rise is ALWAYS a positive number. Example, 3:1. Make sure to include the colon. This slope continues from bottom of the ditch to existing ground for standard ditches unless Right of Way constraints are used, which are described on the next page.

### Fill Slope 1 (Optional)

The fill slope 1 option is provided if a change in the run:rise defined slope is required in fill.

The width of fill slope 1 can be specified in two ways. It can be determined either by a fill slope 1 break line in the GEOPAK Lines DGN or by a redefinable variable.

A [Fill Slope 1 Break Line](#) may be drawn in the designated [GEOPAK Lines DGN](#). To draw the line use the **D&C Manager** item **Slope Fill**, which is located in the D&C Manager path: **"Design Standards/Drainage/"**.

If a slope fill line is not present, the redefinable variables [\\_d\\_FillSlope1Width\\_Left](#) and [\\_d\\_FillSlope1Width\\_Right](#) are used to determine the width of the fill slope 1 in master units on the left and right side, respectively. A plan element **ALWAYS** "overrides" these variables.

If fill slope 1 is not desired at a particular location, do not have a slope fill line crossing the pattern, set the fill slope 1 width redefinable variable to zero, or make the slope fill slope 1 the same as fill slope 2.

The ratio of fill slope 1 is controlled by the redefinable variables [\\_d\\_FillSlope1\\_Left](#) and [\\_d\\_FillSlope1\\_Right](#) in Run:Rise format. Rise is ALWAYS a negative number. Example, 4:-1. Make sure to include the colon.

### Fill Slope 2 (Required)

The ratio of fill slope 2 is controlled by the redefinable variables [\\_d\\_FillSlope2\\_Left](#) and [\\_d\\_FillSlope2\\_Right](#) in Run:Rise format. Rise is ALWAYS a negative number. Example, 4:-1. Make sure to include the colon. This slope continues from its start to the intersection with existing ground unless Right of Way constraints are used.

### **Draw Ditches In Plan View Details**

The ditches and the flow arrows can be drawn in the plan view while processing the proposed cross-sections. The redefinable variable [\\_s\\_DrawDitchesInPlanView](#) controls this behavior. The globally defined variables [Plan View Scale](#) and [Plan View Flow Arrow Scale](#) control the size of the text displaying the average ditch slope between cross sections and the size of the flow arrows, respectively. Set the scale to match the plan sheet plot scale. For a scale of 1"=50' enter the number 50 as a value. If you do not wish to see either the average ditch slope or flow arrows, set the value of its respective scale to a very small number, such as 0.001.


## Right of Way Constrained Tie Slopes

Tie slopes can be forced to stay within the right of way. This behavior is controlled by both plan view elements drawn in the defined [Right of Way DGN](#) and redefinable variables.

## Right of Way DGN Geometry


For right of way constrained tie slopes to work, a right of way line must be drawn in the defined [Right of Way DGN](#) using one of the eight items in the D&C Manager path: **“Design Standards/RW/”** shown below:

- RW Line Exist. – Right of Way Line (Existing)
- RW Line New – Right of Way Line (New)
- RW Temp Acc Ex – Right of Way Access Line (Existing)
- RW Temp Access – Right of Way Access Line (New)
- RW Cont Acc Ex – Right of Way Controlled Access Line (Existing)
- RW Cont Access – Right of Way Controlled Access Line (New)
- RW No Rt Ac Ex – Right of Way No Right of Access Line (Existing)
- RW No Rt Access – Right of Way No Right of Access Line (New)




### Right of Way Constrained Slopes Cross-Section Details

Three redefinable variables are also used to determine how tie slopes are constrained by the right of way lines discussed above. The variables, `_s_LeftROWConstrainedSlope` and `_s_RightROWConstrainedSlope` control whether or not the constraint is to be applied to the left and right sides respectively. To constrain the slope set the variable for that side to `^Yes^`. If normal closure is desired, set the variable to `^No^`. The carets `^` are required. An additional buffer can be applied that will force the tie to be within the right of way point by the buffer width set using the variable `_d_ROW_Buffer_Width` in master units. If the constraint is applied and the normal slope can fit within the right of way then the normal slope will be used. If the normal slope will not fit within right of way, then a steeper slope will be drawn and labeled as such. This will allow the user to identify when their slopes drawn were steeper than the defaults, as shown in the following two figures.



Right of Way Constrained Slope  
With Buffer Width Set to Zero





Right of Way Constrained Slope  
With Buffer Width Set to 3'

## Forced Closure Slopes

Whether or not the side slope closes directly to existing ground from the edge of shoulder or back of curb can be controlled in two ways. It can be controlled either by a **Force Tie Slope** line in the GEOPAK Lines DGN or by a redefinable variable.

### Forced Closure using GEOPAK Lines DGN Element


Force Tie Slope lines may be drawn in the designated **GEOPAK Lines DGN**. To draw the lines use the **D&C Manager** item **Force Tie Slope**, which is located in the D&C Manager path: "**Design Standards/Roadway**". If this line crosses the pattern line for a specific side slope, a single side slope line will be drawn from the edge of shoulder or back of curb to the location where the force tie slope line intersects the existing ground.



### Forced Closure using Redefinable Variables

If a force tie slope line is not used, **\_s\_LeftForceClosingSlopes** and **\_s\_RightForceClosingSlopes** can be used instead. To force the sloped closed set the variable for that side to **^Yes^**. If normal closure is desired, set the variable to **^No^**. The carets '^' are required.

The closure slope is controlled by redefinable variables using the Run:Rise format with the colon required. If the section is in cut Rise is ALWAYS positive and the variables **\_d\_LeftForcedCutSlope** and **\_d\_RightForcedCutSlope** control the slope for each side. If the section is in fill, Rise is ALWAYS a negative number (Example, 2:-1) and the closure slope for each side is controlled by **\_d\_LeftForcedFillSlope** and **\_d\_RightForcedFillSlope**.



The plan element will **ALWAYS** "override" these variables.

Cross-Section View Showing Force Closure Effect

## Appendix 10 Special Ditches


All pavement typical sections (DNpavt, DRecon, NLtRRt, NRtRLt, UNpavt, & URECon) draw special ditches, which are **drawn using profiles to set the ditch elevation**. These are used instead of the standard ditches drawn by the [Standard Side Slopes](#).

### Special Ditch Options


Special ditches allow the user to control the elevation of a ditch at any cross-section by defining a special ditch profile. Different profiles may be used for the left and right side. For the side slope to tie into a special ditch, either the offset to the ditch or the final ditch fore slope must be unconstrained. Note: The use of a special ditch profile **ALWAYS** "overrides" the standard ditch depth redefinable variables `_d_StandardDitchDepth_Left` and `_d_StandardDitchDepth_Right`.

If a ditch alignment is defined for the side slope condition, the offset to the ditch is fixed with the inside edge of the ditch starting at the ditch alignment and ditch fore slope 2 is unconstrained, consequently the redefinable variable for that side (`_d_DitchForeSlope2_Left` or `_d_DitchForeSlope2_Right`) is ignored. This condition is illustrated in the figure below and on the left.

If a ditch alignment is not defined for the side slope condition, ditch fore slope 2 for that side is fixed by `_d_DitchForeSlope2_Left` or `_d_DitchForeSlope2_Right` and the offset is unconstrained. This condition is illustrated in the figure below and on the right.



Special Ditch Location Constrained by Ditch Alignment  
Fore Slope Before Special Ditch Is Unconstrained



Fore Slope Before Special Ditch Is Constrained  
Offset to Special Ditch is Unconstrained

The above figures show the special ditches labeled "S.D." This lets the user know that a special ditch has been drawn on this side slope condition. The user can specify this label using the redefinable variable `_s_SpecialDitchLabel`, Example: `^S.D.^`. The carets "^" are required.

## Special Ditch Profile and Alignment Variables

The variables for the special ditch COGO elements are in the **Define Variables** section of a proposed cross-section run. The elements must be stored in COGO before processing the cross section run. The station range for both the profiles and the ditch alignments must include the cross-section station for them to be used by the criteria. These and other features are discussed in more detail below.

### Special Ditch Profiles

For a special ditch profile to be used it must be listed under the appropriate define variable and must exist for the cross-section station. Separate profiles may be created for the left and right side slope conditions and must be listed in the value for the variable [Left Special Ditch Profiles](#) and [Right Special Ditch Profiles](#) respectively. Commas must separate the profile names. Examples: ltdit1,ltdit2,ltdit3 or rtdit1,rtdit2,rtdit3.

The criteria use the following logic to determine the elevation for the special ditch: If the cross-section station is included in the station range for one of the special ditch profiles, the criteria checks to see if a ditch alignment is encountered. If the ditch alignment is found, the station where the pattern line crosses the ditch alignment is noted and the elevation from the profile at **the ditch alignment station** is used to set the ditch elevation. If a ditch alignment is not defined, the elevation from the profile at **the cross-section station** is used to set the ditch elevation. **In other words, the elevation from the profile at the ditch alignment station is used if there is a valid ditch alignment for the side slope condition; otherwise, the elevation at the cross-section station is used.**

### Ditch Alignments

For a ditch alignment to be used it must be listed under the appropriate define variable. Only one ditch alignment per side per cross-section run is allowed. The alignment for the left and right side slope condition must be listed in the value for the variable [Left Ditch Alignment](#) and [Right Ditch Alignment](#) respectively. Examples: ltditch or rtditch.

Because the cross-section station must be included in the special ditch profile station range, it is recommended that the mainline station where the ditch alignment begins be used as the ditch alignment beginning station. If this is done, the station for the ditch alignment will be similar to the station for the cross-section.

If a ditch alignment is used, the elevation from the profile at the ditch alignment station is used to set the ditch elevation and the inside edge of the ditch will be at the location of the ditch alignment. This is helpful when trying to match an existing culvert for example. This will vary the ditch fore slope 2 variable and force the ditch to have varying ditch fore slopes. **In other words, if a ditch alignment is used, the ditch fore slope redefinable variable is ignored.**

Go to: [Match Line Cross-Section Details for Non-Controlling Roadway](#)



## Appendix 11 Medians

Used by divided pavement typical sections ([DNPavt](#), [DRecon](#), [NLtRRt](#), & [NRtRLt](#)).

There are a total of seven types of medians. Types 1-4 are all rural grass medians with no thickness shown. Type 5 has a raised median, which is paved if the width of the median does not exceed the redefinable variable [\\_d\\_MaxPavedMedianWidth](#). Type 6 is flush paved median with a Type A or C concrete barrier, which may be flat on the bottom or stepped. It requires one and only one new edge of shoulder line is to be drawn between the median edges of pavement. This single shoulder line represents the centerline location of the concrete barrier. The Type 7 median has a retaining wall in the median. It requires two new edge of shoulder lines to be drawn between the median edges of pavement. The distance between the edges of shoulders controls the width of the retaining wall less a "hard coded" buffer distance of 1 inch on each side of the wall. See [Appendix 15 Retaining Walls](#) for an explanation of the variables used to draw the wall.

The different types are:

1 = Fixed slope and fixed depth with a variable ditch bottom width.

2 = Fixed slope and fixed ditch width with a variable ditch depth.

3 = Fixed ditch depth and fixed ditch bottom width with variable slopes.

4 = "V" Ditch with fixed slopes and a variable depth.

5 = Crowned median between curbs with the sloped controlled by the positive value of [\\_d\\_MedianSlope1](#). The optional variable [\\_d\\_PavedMedianThickness](#) may be set greater than zero to show a thickness for this median type assuming the width of the median does not exceed the variable named [\\_d\\_MaxPavedMedianWidth](#).

6A or 6C = Stepped Median Barrier using type A or type C barrier respectively

7 or 7B = Retaining Wall median without barrier on top "7" or with Barrier on top "7B"

One or two slopes may be used for the proposed ground surface to a median ditch for grass medians. The variable [\\_d\\_MedianSlope1](#) controls the first slope, which is optional, and [\\_d\\_MedianSlope2](#) controls the second slope, which is required. The width of the optional first slope is controlled by the redefinable variable [\\_d\\_MedianSlope1Width](#). For median types 1 and 3, [\\_d\\_StdMedianDitchDepth](#) controls the fixed ditch depth and [\\_d\\_MedianDitchWidth](#) controls the fixed ditch bottom width for median types 2 and 3.


## Appendix 12 Match Lines

Drawn by all pavement typical sections (DNPavt, DRecon, NLtRRt, NRtRLt, UNPavt, & URECon).


### Match Line Options

Match lines allow the criteria to terminate a proposed ground side slope at a specific location and draw a vertical line from that location to existing ground, as shown in both of the figures below. This option is needed when the outside edge of a proposed side slope condition is adjacent to another proposed cross-section run, which occurs at interchanges and at any other situations where another proposed alignment runs along side the current run. Typically one of the alignments will control the elevation at the match line. The proposed cross-sections for the controlling alignment should be run first with a fixed final side slope. This is shown on the left below. Once the first set of cross sections is run, the Profile Grade Report may be used to create a profile and optional chain from these cross sections at the location of the match line. This profile and optional chain can be used to vary the slope of the proposed ground element by forcing it to end at the elevation obtained from the profile. This is shown on the right below.

There are two very different ways that the proposed ground surface can be modeled before the match line location is reached. Either a standard typical section can be used prior to the match line (as shown in the left figure below) or a straight line can be from the edge of shoulder, curb, or berm to a specific elevation at the location of the match line, which is the method shown in the right figure below.



Typical Section Before Match Line



Single Element Before Match Line


To draw a typical section prior to the match line (the case on the left above) a graphic element in the designated [GEOPAK Lines DGN](#) must be used to locate the match line. For this option, the redefinable variables described in the [Appendix 9 Standard Side Slopes](#) are used to draw the proposed ground elements prior to the match line. The final proposed ground element may be drawn either at a fixed or a variable slope. The variable slope for the final element is used if a specific elevation is desired at the match line.

The easiest way to have a single proposed ground element before the match line is to use a match line chain to indicate the location of the match line and a match line profile to determine the elevation desired.


Each of these cases is treated separately below.

### Typical Section Before Match Line Details


For any of the standard side slopes redefinable variables to be used by the criteria for this option, a graphic element is needed in the designated [GEOPAK Lines DGN](#) to indicate the location of the match line. This line must be drawn using the **D&C Manager** item **Matchline**, which is located in the D&C Manager path: **Design Standards/Roadway/**. An example is shown in the figure to the right.



The slope on the final proposed ground element before the match line may be either a fixed value (as shown below in the figure on the left) or it can be variable with the element ending at an elevation obtained from a profile (as shown below in the figure on the right). To use a fixed slope for the final element, do NOT define a match line profile for that cross-section. If a match line profile is defined for the cross-section station, the final proposed ground element is drawn to the profile elevation. The match line profiles are defined for each side by using the Define Variables [Left Match Line Profiles](#) and [Right Match Line Profiles](#). Commas must separate the profile names. Example: "ml1lt,ml2lt,ml3lt"; or "ml1rt,ml2rt,ml3rt". **Note:** The stationing of the profile must match the cross-section stationing.



Fixed Slope Option Used for Vertex at the Match Line  
A Match Line Profile Is NOT Defined for the XS Station



Profile Used for Vertex at the Match Line  
A Match Line Profile Is Defined for the XS Station


While the above examples are in fill, the same process works in cut. The only difference is the redefinable variables used.

## Match Line Chain and Profile Details

If a single proposed ground element is to be drawn from the edge of shoulder, curb, or berm to a specified elevation at the match line, the use of a match line chain to locate where the match line profile elevation is to be applied is the best option. The chain and profile can be easily obtained using the Profile Grade Report. **Note:** The use of a match line chain is not required; it is just the easiest option. To use the typical section option, the appropriate slope width redefinable variable would need to be large enough to extend past the match line location.

The Define Variables [Match Line Chain Names](#), [Left Match Line Profiles](#) and [Right Match Line Profiles](#) list the chains and profiles to be used with match lines. The match line chain names must exactly match the corresponding profile name. Commas must separate the profile and the chain names. Example: "ml1lt,ml2lt,ml3lt"; or "ml1rt,ml2rt,ml3rt". Up to eight match line chain names are permissible per cross-section run. **IMPORTANT:** The list of the match line chains MUST NOT include any blank spaces. The stationing of the match line chain and corresponding profile must be the same. Also, the presence of a defined match line chain **ALWAYS** "overrides" a graphic match line.

The Redefinable Variable [\\_d\\_MatchLineChainSearchDistance](#) sets the distance to look for a match line chain. The distance is measured in master units from the edge of shoulder, curb, or berm. This is a positive value and **MUST** be greater than zero.



Example Using a Match Line Chain and Profile

### Appendix 13 Rock Benches


Drawn by all pavement typical sections (DNPavt, DRecon, NLtRRt, NRtRLt, UNPavt, & URECon) as part of the [Standard Side Slopes](#).

#### Cross-Section Geometry Required


If the proposed ground is below a top of rock line in the cross-section, rock benches are drawn starting at the back of the ditch. For this to work, the top of rock line must be drawn in the designated [Cross Section DGN](#) using symbology matching the search parameters for the **D&C Manager** item **Rock Top**, which is located in the path: “**Design Standards/Cross Sections/Existing Surfaces**”.

#### Rock Bench Redefinable Variables

Four redefinable variables control how the rock benches are drawn. The bench width and the bench height are set by [\\_d\\_BenchWidth](#) and [\\_d\\_BenchHeight](#), respectively, in master units, which must be greater than zero. The rock face can either be vertical or drawn at an inclined slope, which is set by [\\_d\\_BenchingBackSlope](#), in Run:Rise format. Rise is ALWAYS a positive number. For a vertical face set [\\_d\\_BenchBackSlope](#) to 0:1. For an inclined face the Run value is the percent of slope from vertical divided by 100. Consequently, to have a 10% slope to the incline, use a value of 0.1:1, as shown in the following figures




Vertical Rock Face (`_d_BenchBackSlope = 0:1`)




Inclined Rock Face (`_d_BenchBackSlope = Run:Rise`)

The fourth rock bench redefinable variable is [\\_s\\_TopBenchWidth](#), which locates the toe of the slope for the Class A material above the rock. Two options are available. The toe can be located either at the angle of repose, which is the angle of the ditch back slope

projected from the back of the ditch as shown in the figure on the left below, or at a specified horizontal distance (in master units) from the rock face as depicted in the figure on the right. Set `_s_TopBenchWidth = ^RS^` for angle of repose slope or put the horizontal distance between carets (example `^10^`) to specify an actual width. The carets `"^"` are required. **Note:** For the slope to be drawn correctly, the existing ground line must extend far enough for the proposed ground line to intersect it. Inconsistent results will occur if the existing ground line is not wide enough.



Example: `_s_TopBenchWidth = ^RS^`  
Toe of Slope at Angle of Repose Slope



Example: `_s_TopBenchWidth = ^10^`  
Toe of Slope at 10' From Rock Face

## Appendix 14 Sidewalk

Drawn by all pavement typical sections (DNPavt, DRecon, NLtRRt, NRtRLt, UNPavt, & URECon).


### Plan View Geometry

Two conditions need to be met for sidewalk to be drawn in a cross-section. The first is that the edge of sidewalk is drawn in the designated [Proposed Plan DGN](#). The line must be drawn using the **D&C Manager** item **Sidewalk** located in the D&C Manager path: **“Design Standards/Roadside/”**. The second condition is that the sidewalk is located within the [Berm](#) in the [Standard Side Slopes](#).


If the sidewalk is adjacent to the back of a curb, only one edge of sidewalk line away from the back of the curb is to be drawn. However, if the sidewalk is not adjacent to a back of curb, both edge of sidewalk lines need to be present. The sidewalk will not be drawn if the criteria cannot match up an edge of sidewalk line with either a curb line or another edge of sidewalk line. The required lines and the results are given in the following examples (**Note:** The width of the sidewalk is determined by the plan view geometry):

#### Example 1: Sidewalk Adjacent to Back of Curb

The sidewalk is drawn between the back of curb and a single sidewalk line:




Plan View Geometry With One Sidewalk Line




Cross-Section View

#### Example 2: Sidewalk Away from Back of Curb

The sidewalk is drawn between two matching sidewalk lines:




Plan View Geometry With Two Sidewalk Lines




Cross-Section View

### Sidewalk Elevation

The elevation of the sidewalk in the cross-section view is set by the elevation assigned to the inside edge of the sidewalk. This elevation can be determined either by the slope of the berm or by a previously defined profile. The Define Variables [Left Sidewalk Profiles](#) and [Right Sidewalk Profiles](#) list the profiles to be used with a sidewalk for each side of the cross-section. If a sidewalk profile is defined for the cross-section station and side, the inside edge of the sidewalk is started at the profile elevation for that station, as shown in the figure on the left below. If a sidewalk profile is NOT defined for the cross-section station and side, the elevation of the inside edge of the sidewalk is set by the cross-section geometry. If the sidewalk starts at the back of a curb, the inside edge of the sidewalk is drawn at the elevation of the back of the curb. If the sidewalk is drawn between two sidewalk lines, the berm slope is projected to the inside sidewalk edge, which is the starting elevation for the sidewalk, as shown below in the figure on the right.



Cross-Section With a Sidewalk Profile Defined




Cross-Section Without a Sidewalk Profile Defined

The elevation of the outside edge of the sidewalk is controlled by the redefinable variable [\\_d\\_SidewalkSlope](#), which sets the proposed sidewalk cross slope in percent format from the inside edge to the outside edge, as shown in the figure below. Do not include the percent sign. Do include the negative sign when applicable.

### Sidewalk Thickness

The redefinable variable [\\_d\\_SidewalkThickness](#) sets the sidewalk thickness in master units, as shown in the following figure. This is a positive value and MUST be greater than zero. **Note:** The width of the sidewalk is determined by the plan view geometry.



Sidewalk Dimension Redefinable Variables




## Appendix 15 Retaining Walls

Drawn by all pavement typical sections (DNPavt, DRecon, NLtRRt, NRtRLt, UNPavt, & URECon).


### Plan View Geometry

Retaining walls are located in the proposed side slope by placing a new retaining wall line in the designated [Proposed Plan DGN](#) at the location of the face of the wall closest to the roadway. The line must be drawn using the **D&C Manager** item **New Retaining Wall** located in the D&C Manager path: “**Design Standards/Safety and Structures**”, as shown in the figure to the right. The retaining wall may be located either adjacent to a shoulder or proposed ground. A gutter can be placed behind the wall by locating a Concrete Cutter line at the backside of the wall in cut (D&C Manager path: “**Payitems/Roadway/Curb**”). See [Appendix 11](#) for placing a retaining wall in [Medians](#).



### Proposed Surfaces Adjacent to the Wall

If the retaining wall is to be placed adjacent to the shoulder, two conditions must be met for the cross-section to be drawn correctly. The first is that there must be a gap between the retaining wall and the shoulder as drawn in the cross-section. This is required for the criteria to recognize the retaining wall line in the plan view. Typically, joint filler is placed between the retaining wall and the shoulder and the width of the gap can be used to represent the joint filler thickness. For non-earth shoulders, the second condition is that the shoulder must be recognized by the criteria as concrete regardless of the actual material used. This is required so that the outer edges of the shoulder layers are drawn vertically next to the wall. If the edge of the shoulder is within the distance in master units set for the redefinable variable [\\_d\\_AdjacentWallSearchDistance](#), the aggregate layer will be extended to the wall as shown in the figure to the right. Use a positive number.



If proposed ground is adjacent to the retaining wall, a maximum of two different slopes are permitted before the retaining wall. The value of these slopes are the slope assigned to the berm (if one is drawn) and to the first fore slope after the berm that is actually drawn. The fore slope that is applied depends on whether the side slope is in cut or fill and the side slope parameters applied to the cross-section.


Go to: [Standard Side Slopes](#)

### Footing Cross-Section Details

The dimensions for drawing the retaining wall footing are set by the redefinable variables [\\_d\\_WallWidth](#) (measured from the retaining wall line in the plan dgn in a direction away from the roadway), [\\_d\\_BackFootingWidth](#) (measured from the edge of the wall with the deepest fill to the back or heel of the footing), [\\_d\\_TotalFootingWidth](#) (measured from the back or heel of the footing to the front or toe of the footing), [\\_d\\_FootingThickness](#) (measured down from the top of the footing), [\\_d\\_KeyHeight](#) (measured down from the bottom of the footing), [\\_d\\_KeyOffset](#) (measured from the front or toe of the footing to the front edge of the key), and [\\_d\\_KeyWidth](#) (measured from the front of the key to the back of the key), as shown in the following figure. All values are in master units and may be zero or greater than zero. The back footing width will always be drawn on the side of the wall with the deepest fill above the footing.

The elevation of the top of the footing can be set by either defining a top of footing profile or by a minimum depth below ground. To specify a top of footing elevation, create a profile based on the cross-section station. Different profiles may be used for the median, left, and right side and are listed using the define variables [Median Top of Footing Profiles](#), [Left Top of Footing Profiles](#) and [Right Top of Footing Profiles](#) respectively. These profiles must be previously stored in COGO before processing the cross sections. The profile names are to be separated by commas. Example: LTF1,LTF2,LTF3 or RTF1,RTF2,RTF3. If the top of footing profile exists for the cross-section station, the elevation for that station will be used as the top of footing elevation.

If a top of footing profile does not exist for the station, the top of footing is drawn at a specified depth below either the proposed or existing ground line, whichever is lower. If the proposed ground is lower, the wall is in cut and the top of footing is below proposed ground by the distance specified by the redefinable variable [\\_d\\_DepthBelowProposedGroundInCut](#). However, if existing ground is lower, the wall is in fill and the top of footing below existing ground by the distance specified by the redefinable variable [\\_d\\_DepthBelowExistGroundInFill](#). Both values are in positive master units.



Retaining Wall Footing Dimensions


### Retaining Wall Height

The height of the retaining wall may be set by specifying the elevation of the top of the wall, by defining a specific height, or by letting it vary with the ground surface. A profile is used to set a specific elevation for the top of the wall based on the cross-section station. If a top of wall profile does not exist for the cross-section station, the redefinable variable `_s_WallHeight` controls the height of the wall. This variable can be set to specify a fixed value for the height of the wall or it can be set to allow the height of the wall to vary with the ground surface.

#### Height Set by Elevation of the Top of the Wall

To set the wall height by specifying a top of wall elevation, create a profile based on the cross-section station. Different profiles may be used for the left and right side and are listed using the define variables `Left Top of Wall Profiles` and `Right Top of Wall Profiles` respectively. These profiles must be previously stored in COGO before processing the cross sections. The profile names in the list need to be separated by commas. Example: `LTW1,LTW2,LTW3` or `RTW1,RTW2,RTW3`.


If the top of wall profile exists for the cross-section station, the elevation for that station is used as the top of wall elevation and the wall is drawn between the top of the footing and the top of wall elevation, as shown in the figure to the right. The proposed ground settings are used to connect the retaining wall to the existing and the proposed ground. The rest of the parameters for the wall and footing dimensions are the same as those shown on the previous page.



#### Height Set by a Fixed Value

The redefinable variable `_s_WallHeight` controls the height of the wall if a top of wall profile is not used. As a string redefinable variable (as defined by the beginning “\_s\_”), it is used to control whether the height of the wall is a fixed height or variable. If a fixed height is desired, set the variable to a numeric value inside of carets (^). Example: Assign it the value of `^10^` for a 10 foot high wall. **ALWAYS** use the carets.

The fixed height of the wall is measured up from the top of the footing in master units, as shown in the figure to the right. The proposed ground settings are used to connect the retaining wall to the existing and the proposed ground. The rest of the parameters for the wall and footing dimensions are the same as those shown on the previous page.



## Height Varies With the Ground Surface


To let the height of the wall vary with the ground surface, set **\_s\_WallHeight** to **^GS^** for ground surface. **ALWAYS** use the carets. With the variable set to this value, different parameters are allowed for cut and fill. Each of these cases is considered separately.

### Variable Wall Height in Cut

If **\_s\_WallHeight** is set to **^GS^** and the wall is in cut, the redefinable variable **\_d\_HeightAboveExistGroundInCut** controls the top of the wall by specifying the distance in master units that the top of the wall is above the existing ground on the back side of the wall, as shown in the figure to the right.

If a gutter is to be drawn on the backside of the retaining wall the redefinable variable **\_d\_BackWallHeightInCut** controls the distance in master units that the top the gutter is below existing ground, as shown to the right.


If a profile is not used to locate the top of the footing, the redefinable variable **\_d\_DepthBelowProposedGroundInCut** controls the depth of the footing below the proposed ground surface as indicated in the figure to the right. This distance is in master units.



### Variable Wall Height in Fill

If **\_s\_WallHeight** is set to **^GS^** and the wall is in fill, the redefinable variable **\_d\_HeightAbovePropGroundInFill** controls the top of the wall by specifying the distance in master units that the top of the wall is above the proposed ground on the roadway side of the wall, as shown in the figure to the right.

If a profile is not used to locate the top of the footing and the wall is in fill, the redefinable variable **\_d\_DepthBelowExistGroundInFill** controls the depth of the footing in master units below existing ground as indicated in the figure to the right. Both sides of the wall are checked and the lower elevation is used.



The rest of the dimensions for the retaining wall are the same as those used in the section dealing with the retaining wall footing.

## Appendix 16 Tapering Procedure

Drawn by all pavement typical sections (DNPavt, DRecon, NLtRRt, NRtRLt, UNPavt, & URECon).

In certain design situations a designer may need to "Taper" ditch widths or ditch slopes over a certain distance. For example, a design requires the slope of the side embankment to transition from a default [Standard Side Slopes](#) value to another one that is used for a short section of the project. This can be done using tapering files. When a typical section is applied two special files are copied to the working directory. Initially these file names are TapersLT.txt and TapersRT.txt for the left and right sides respectively. These files can be renamed as long as the new file names are assigned to the variables [Left Tapers File Name](#) and [Right Tapers File Name](#).

### Taper File Content

The original content of one these files is as follows:

```
BL,Station,Reg,#BW,#FS1W,#DFS1W,#DW,#BrmS(%,FS1(Rn:-Rs),FS2(Rn:-Rs),DFS1(Rn:-Rs),DFS2(Rn:-Rs),BkS(Rn:Rs),FCS(Rn:Rs),FFS(Rn:-Rs)
$End
```

The abbreviation definitions are as follows:

- BL = Shape Cluster Baseline Name;
- Station = Station at which the values of the current line are to be applied;
- Reg = Region;
- BW = Berm Width;
- FS1W = Fill Slope 1 Width;
- DFS1W = Ditch Fore Slope 1 Width;
- DW = Ditch Width;
- BrmS(%) = Berm Slope in percent format with the percent sign;
- FS1(Rn:-Rs) = Fill Slope 1;
- FS2(Rn:-Rs) = Fill Slope 2;
- DFS1(Rn:-Rs) = Ditch Fore Slope 1;
- DFS2(Rn:-Rs) = Ditch Fore Slope 2;
- DkS(Rn:Rs) = Ditch Back Slope;
- FCS(Rn:Rs) = Forced Cut Slope; and
- FFS(Rn:-Rs) = Forced Fill Slope.

For the user to utilize tapering, the left or right or both file(s) need to be edited. This can be done with a standard text editor or a Visual Basic Application (VBA) launched from D&C Manager (v8 only). The values put into this file over ride the values set by the redefinable variables in the proposed cross section run. An example using at text editor is presented first, followed by one using the VBA.

## Tapering Example

This example use standard slopes and only tapers the width of the bottom of the ditch and ditch foreslope 1 for the LEFT ditch only. The taper specifics are as follows:

Baseline Name = Prop

Region = 1

station 24+00 ditch width =2 and ditch foreslope 1 = 6:-1

station 26+00 ditch width =4 and ditch foreslope 1 = 4:-1

station 28+00 ditch width =2 and ditch foreslope 1 = 6:-1

The “rules” for the file are as follows: Enter zeros for items that are not changing and nonzero values for the items that are changing. Place a common, without a space, between the values. Only the station ranges through the tapered area are in the file. If a particular element is not to taper then zeros are used as placeholders. When using the zeros you must however keep with the format of using the colon and showing both the run and rise i.e. "0:0". The file format **MUST** not be altered. The "+" sign for the station is **REQUIRED**. The "-" minus sign for the rise value of ditch fore slopes and fill slopes are **REQUIRED**. The ":" colons between the run and rise are **REQUIRED**. There are **NO BLANK SPACES** allowed in this file. The default first and second lines **MUST NOT** be deleted. The data must go in between the default lines as shown above. All fields **MUST** be present. Lastly, note that the baseline name, station, and region are **ALWAYS** required.

### File edited using a text editor

Great care needs to be taken if a regular text editor is used to edit the tapers file. The format of the file is **VERY** specific and the following example **MUST** be followed precisely for it to work. For the example, the original file needs to be edited by adding three lines between the first and last lines, one for each station at which the tapering transitions. The contents of the edited file are shown below:


```
BL,Station,Reg,#BW,#FS1W,#DFS1W,#DW,#BrmS(%),:FS1(Rn:-Rs),:FS2(Rn:-Rs),:DFS1(Rn:-Rs),:DFS2(Rn:-Rs),:BkS(Rn:Rs),:FCS(Rn:Rs),:FFS(Rn:-Rs)
prop,24+00,1,0,0,0,2,0,0:0,0:0,6:-1,0:0,0:0,0:0,0:0
prop,26+00,1,0,0,0,2,0,0:0,0:0,4:-1,0:0,0:0,0:0,0:0
prop,28+00,1,0,0,0,2,0,0:0,0:0,6:-1,0:0,0:0,0:0,0:0
$End
```

Notice in the above example how only the value of the ditch width and ditch fore slope 1 change. These are shown in red, while the commons that separate the values and the placeholders for the items that are not tapering are in black.

Once the file has been edited, it should be saved using a different file name. This prevents the user from over riding the text file when an additional typical section is applied. The saved file name is entered as the value for the [Tapers File](#) define variable.



File edited using VBA

The second way that the tapers file can be edited is by running a VBA launched from the Design and Computation Manager (v8 only). In the design mode, double click on **Taper File Editor**, which is in the 3PC category, as shown in the figure to the right. This launches the **Cross Section Taper Table** dialog shown to the left.




To begin working on tapers file, click on the **Open** file button, which is the one outlined in the figure. The user has two options for selecting the first tapers file to be edited for the project. It may be selected from either the working directory for job or from the t:\gpk\_std\Typicals folder.

If the typical section was applied using GEOPAK 2004 or later, one of the tapers files in the working directory may be used. However, if this option is chosen, the user will need to enter all of the values for the initial line to be added to the text file. This is because this file contains only two lines, which are the header and the end lines. As shown in the following figure:








To keep from adding all of the information, a tapers template file has been created. It is **t:\Gpk\_Std\Typicals\tapers\_template.txt**. This file has three lines of text with the middle line containing default values. Loading this file causes that additional line to be included in the list box with its values displayed in the edit boxes at the bottom of the dialog, as shown in the following figure. Noted that the required plus sign “+” and colons “:” have been added.



To edit the file, enter the cross section baseline chain in the **Baseline** field, as shown above. This baseline will be added to all of the lines containing tapering information. To add the rest of the information to an individual line, change the information in the boxes at the bottom of the dialog to the required values. The boxes line up vertically with the header information at the top of the dialog. After entering the information for an individual field, the tab key moves the cursor to the next field and selects the text in that field.

Once the boxes are correct, that information can be added to the list box using the buttons on the right edge of the dialog. They function as follows:

-  Adds a new line after the current line.
-  Inserts a new line above the current line.
-  Modifies the highlighted or current line.
-  Deletes the highlighted or current line.
-  Deletes all rows from the list box.



The required information for the first line of the example has been added to the loaded file and the Modify icon used to update the information in the current line in the list box, as shown below:

Cross Section Taper Table - T:\Gpk\_Std\Typicals\tapers\_template.txt

Baseline:

Station	Reg	BW	FS1W	DFS1W	DW	BrmS(%)	FS1(Rn:-Rs)	FS2(Rn:-Rs)	DFS1(Rn:-Rs)	DFS2(Rn:-Rs)	BkS(Rn:Rs)	FCS(Rn:Rs)	FFS(Rn:-Rs)
24+00	1	0	0	0	2	0	0:0	0:0	6:-1	0:0	0:0	0:0	0:0

24+00   1   0   0   0   2   0   0:0   0:0   6:-1   0:0   0:0   0:0   0:0

After adding the rest of the information for the example, the completed dialog is shown in the following figure:

Cross Section Taper Table - T:\Gpk\_Std\Typicals\tapers\_template.txt

Baseline:

Station	Reg	BW	FS1W	DFS1W	DW	BrmS(%)	FS1(Rn:-Rs)	FS2(Rn:-Rs)	DFS1(Rn:-Rs)	DFS2(Rn:-Rs)	BkS(Rn:Rs)	FCS(Rn:Rs)	FFS(Rn:-Rs)
24+00	1	0	0	0	2	0	0:0	0:0	6:-1	0:0	0:0	0:0	0:0
26+00	1	0	0	0	4	0	0:0	0:0	4:-1	0:0	0:0	0:0	0:0
28+00	1	0	0	0	2	0	0:0	0:0	6:-1	0:0	0:0	0:0	0:0

28+00   1   0   0   0   2   0   0:0   0:0   6:-1   0:0   0:0   0:0   0:0

Two icons are provided to save the file. They are located next to the Open file Icon and perform the following functions:



Save



Save As

Since the template file was used for this example, the **Save As** button is required to be used so that the edited file can be saved to the working directory. After navigating to the working directory, the file is saved as `tapers_example.txt`. The application displays the following dialog to confirm that the file has been saved. Click on **OK** to close this **Save Table File** dialog.




## Appendix 17 Gore Areas

Drawn by all pavement typical sections (DNPavt, DRecon, NLtRRt, NRtRLt, UNPavt, & URECon) as an option in [Standard Side Slopes](#).

### Paved Gore

There are some restrictions on the "Main Line" pavement shapes and pattern lines. The shapes should not take into account the ramp transition but the pattern lines should. The main line pattern lines needed to be line strings with a kink in the pattern line located where the change in slope from mainline cross slope to ramp cross slope takes place with each segment of the line string perpendicular to its respective chain. The ramp shape and pattern lines, which should not be generated until later, will begin at the ramp nose, which is at the end of the ramp transition where the ramp pavement separates from the main line pavement, as shown in the following figure.



### Ramp Transition Chain and Profile Design Procedure

Based on MoDOT standards, the outside elevation of the ramp transition is controlled by the main line profile, the main line cross slope out to the kink in the pattern line, the cross slope of the ramp from the kink to the ramp chain, and the location of the ramp chain. Moreover, the cross slope of the ramp is in transition from the start of the ramp chain (where it matches the cross slope of the mainline) to the ramp nose (where it matches the full superelevation required by the ramp curve). For this reason, a point to point profile needs to be created for this region along the ramp chain. This is best done using the **Shape Analyst** and **Shape Profiler** in **Superelevation Shape Manager Tools**, as described in the **Ramp Transition Exercise**, which is located at the following link:


External MoDOT Web: [http://www.modot.mo.gov/business/GEOPAK\\_HELP2.htm](http://www.modot.mo.gov/business/GEOPAK_HELP2.htm)

The name of the profile needs to be exactly the same as the name of the chain created along the outside edge of the ramp. If, for instance, the ramp chain is called RAMP2PR, the ramp transition profile needs to be named Ramp2PR as well. The name given to the ramp transition chain and profile needs to be included in the value for the variable **Ramp Chain Names**. Also, for the criteria to find the chain, the distance from the outside edge of the mainline to the ramp chain must be less than the value of the redefinable variable **\_d\_RampChainSearchDistance**.

There are two ways to prevent the criteria from finding the ramp chain past the ramp nose. One is to create a unique chain and profile for just the ramp transition that are a portion of the chain and profile for the entire ramp. The other is to limit the value of the variable **\_d\_RampChainSearchDistance** so it is less than the distance from the mainline edge of pavement to the ramp chain after the nose.

### Cross-Section Details

The pavement structure for the ramp transition is the same as the main line pavement, as show below.




## Grass Infield Gore

A grass infield gore is required when there are two roadways close enough to each other so that it is not possible for the side slopes for both roadways to tie to existing ground. This often is the case between a main line alignment and a ramp or outer road, as shown below. The first issue that needs to be resolved is which roadway controls the elevation of the ditch between the two roadways. In most cases this can be determined from a comparison of the two profiles and the required ditch depths. Subtracting a roadway's ditch depth and the difference in elevation between the profile and the start of the side slope from the profile elevation gives the maximum elevation of the ditch for that roadway. The controlling roadway is the one with the lower maximum ditch elevation. If this comparison does not give a clear indication of which roadway controls, a set of preliminary cross sections can be run for each roadway with the redefinable `_s_DrawDitchesInPlanView` set to `^Yes^`. This will not only give the ditch elevation for each roadway but will also plot the location of the ditch in the designated **Proposed Plan DGN**.

## Plan View Geometry


Once it has been decided which roadway controls, the next step is to use Draw Transition or another tool to draw a line in the **GEOPAK Lines DGN** at the controlling out ditch using the **D&C Manager** item **Matchline**, which is located in the D&C Manager path: "**Design Standards/Roadway**", as indicated in the following figure.



Although the figure on the previous page does not show it, it is a good idea to add pattern lines for the controlling roadway where the graphical match line intersects the pattern lines for the non-controlling roadway. This is because the proposed cross-sections for the non-controlling roadway are drawn to a match line chain and profile created from the out ditch points for the controlling roadway. To draw directly to those points it is necessary for the match line profile to be accurately defined at those locations using the procedure outlined below.

### Cross-Section Details for the Controlling Roadway




With the match line plotted, a final set of cross-sections can be drawn for the controlling roadway. The proposed cross-section are drawn normally out to the match line. At that point the proposed ground is drawn vertically (up or down) until it intersects with existing ground. See the following figure.



Also plotted with the geometry that is shown on the final cross section sheets, the typical section generator criteria file also draws text at several locations that can be used to generate a Profile Grade report. This report is used to create a match line chain and profile for the non-controlling roadway as described next.

## Creating a Match Line Chain and Profile Using the Profile Grade Report


While in the cross-section file just created, the Profile Grade, which is one of the XS Reports (figure on the left), is used to create a match line chain and profile at the out ditch location. The Profile Grade Report, as set up in the middle figure, searches each cross-section for the word “orditr” and creates a chain and profile based upon the location of the text in the cross-section (figure on the right).



## Match Line Cross-Section Details for Non-Controlling Roadway

Once the match line chain and profile are created, they are be used to terminate the proposed side slope for the non-controlling roadway. For this to work, the name given to the match line chain and profile (ML1 in this example) must be listed in the value for the variable [Match Line Chain Names](#). The distance from the edge of shoulder, curb, or berm to the match line chain must be less than the value of the redefinable variable [\\_d\\_MatchLineChainSearchDistance](#) for the criteria to find the chain.

The proposed side slope is drawn from the edge of shoulder, curb, or berm to the match line chain and profile. An example of what that might look like in a fill situation is shown below:



**Notes:** [Special Ditch Profiles](#) may also be used to control the slope of the ditch that is drawn between the two roadways. This will affect the location and elevation of the match line and should be included in the set of cross-sections created prior to using the Profile Grade Report.

A Match Line example using the Profile Grade Report with MoDOT classic criteria is available at the following link:

External MoDOT Web: [http://www.modot.mo.gov/business/GEOPAK\\_HELP2.htm](http://www.modot.mo.gov/business/GEOPAK_HELP2.htm)



## Appendix 18 Levee and Optional Interception Ditch


Drawn by all pavement typical sections (DNPAvt, DRecon, NLtRRt, NRtRLt, UNPAvt, & URECon) as an option in [Standard Side Slopes](#).

### Plan View Geometry

The levee can be located either adjacent to the roadway ditch or at some location beyond that. This behavior is controlled by the redefinable variable [\\_s\\_LeveeAdjacentToDitch](#). Set its value to ^Yes^ to start the levee foreslope at the end to the ditch back slope (as shown in the following figure) or to ^No^ to have its location controlled by graphic elements drawn in the [GEOPAK Lines DGN](#).

No matter where the levee is located, two plan view elements must be drawn outside of the ditch back slope tie down location using the **D&C Manager** items **In Levee** and **Out Levee**. These items are located in the D&C Manager path: “**Design Standards/Drainage**”. If [\\_s\\_LeveeAdjacentToDitch](#) is set to ^Yes^, these lines control only the width of the top of the levee and not its location. However, if [\\_s\\_LeveeAdjacentToDitch](#) is set to ^No^, the plan elements control both the “levee Width” and its horizontal location.

Go to: [Standard Side Slopes](#)



### Cross-Section Details

The designer has the option of including an interception ditch behind the levee. If a ditch is desired, a bottom of ditch elevation profile must be defined for the cross-section station. Separate profiles may be created for each side and they must be listed in the variables [Left Interception Special Ditch Profiles](#) and [Right Interception Special Ditch Profiles](#), respectively. If an interception ditch is not desired, do not define an interception ditch profile for that station. Four redefinable variables control the dimensions of the levee and interception ditch. They are [\\_d\\_LeveeForeslope](#), [\\_d\\_LeveeBackslope](#), [\\_d\\_InterceptionDitchWidth](#), [\\_d\\_InterceptionDitchBackslope](#), and [\\_d\\_LeveeHeight](#), (which is measured from the bottom of the ditch profile as defined for the station or is measured from existing ground if a profile is not defined).

### Appendix 19 Profile Grade Report Text

Text is plotted in the proposed cross sections that can be used with the Cross Section Profile Grade Report. The following subsections list the text that is plotted and what it represents. This information is listed twice. The first listing is organized by what is being marked. The second is organized by the text plotted, arranged in alphabetical order. All of this text is plotted on the same level and is graphically grouped. This text is part of the electronic deliverables and should not be deleted for cross sections that are not manually modified. For the cross sections that are modified, it would be best to move the text along with the elements that are modified. Placing the text in a MicroStation selection set overrides the graphic grouping. Also, turning the graphic group lock off allows the user to work with each piece of text separately.

#### Points Marked by Text in the Proposed Cross Sections

<u>Point Being Marked</u>	<u>Text Plotted</u>	
	<u>Left</u>	<u>Right</u>
Edge of Pavement	ep1t	ep1r
Edge of Shoulder	eos1t	eos1r
Curb Flow Line	fl1t	fl1r
Back of Curb Next to Pavement	boc1t	boc1r
Back of Curb After U2 Shoulder	boc21t	boc21r
Berm	brm1t	brm1r
Bottom of Aggregate Base Daylight Point on Outside Slope	bd1slp1t	bd1slp1r
Bottom of Aggregate Base Daylight Point on Median Slope	bd1med1t	bd1med1r
Rock Fill Base Daylight Point on Outside Slope	rfd11t	rfd11r
Rock Fill Base Daylight Point on Median Slope	rfd1med1t	rfd1med1r
Compensating Depth Daylight on Outside Slope	compd11t	compd11r
Compensating Depth Daylight on Median Slope	compd1med1t	compd1med1r
Cut/Fill Slope Break Point	slp11t	slp11r
Inside Edge of Ditch/Bottom of Fill Slope	slp21t	slp21r
Outside Edge of Ditch	od1t1t	od1t1r
Median Flow Line at Center of Median	mfl	
Tie Stake	ti1t	ti1r

**Profile Grade Report Text Arranged in Alphabetical Order**


<b><u>Text Plotted</u></b>		
<b><u>Left</u></b>	<b><u>Right</u></b>	<b><u>Point Being Marked</u></b>
bdlmedlt	bdlmedrt	Bottom of Aggregate Base Daylight Point on Median Slope
bdlspllt	bdlsprtr	Bottom of Aggregate Base Daylight Point on Outside Slope
boclt	bocrt	Back of Curb Next to Pavement
boc2lt	boc2rt	Back of Curb After U2 Shoulder
brmlt	brmrt	Berm
compdlmedlt	compdlmedrt	Compensating Depth Daylight on Median Slope
compdllt	compdllrt	Compensating Depth Daylight on Outside Slope
eoslt	eosrt	Edge of Shoulder
eplt	eptr	Edge of Pavement
fllt	flrt	Curb Flow Line
mfl		Median Flow Line at Center of Median
oditlt	oditrt	Outside Edge of Ditch
fbdlmedlt	rfdlmedrt	Rock Fill Base Daylight Point on Median Slope
rfdllt	rfdllrt	Rock Fill Base Daylight Point on Outside Slope
slp1lt	slp1rt	Cut/Fill Slope Break Point
slp2lt	slp2rt	Inside Edge of Ditch/Bottom of Fill Slope
tielt	tiert	Tie Stake

## Appendix 20 Troubleshooting Redefinable Variable Syntax Errors

One of the problems that can occur while using the Typical Section Generator is to have a redefinable variable syntax error. If there is an error and you run the proposed cross sections, the process quickly ends and an error message is displayed in the Process Cross Sections Display ending in the phrase **“Incomplete input data,”** as shown below. There are three common causes for this error. They are: 1) an undefined variable, 2) a missing or misspelled key word, and 3) a missing closing braces “}” at the end of an if-statement. The rest of this appendix gives information on how to determine which of these errors is the cause of the failed run and how to fix the problem. If there are multiple errors you need to repeat the error checking until all of them are removed.


### Variable Is Not Defined

One of the errors is an undefined variable. This can be identified in two ways. The first is to notice the carets “^” under the variable name. The second way to identify this error is to look at the entire error message, which can be done by expanding the Display dialog. This has been done on the following page.





below and click on the **Edit** button. When the **Redefinable Variables Editor** is opened, the problem becomes readily apparent as shown below in the figure on the right. For this example the entry for `_d_Aggbase2Thickness` was saved with the information for `_d_Aggbase1Thickness` instead of the correct variable.




To complete the fix, edit the if-statement so that the correct variable is named and defined with the correct information. The needed changes for the example are shown below. **Note:** The information in the header above the actual if-statement does not need to be modified for the cross sections to run. It is there only for the user's benefit.


```
if (Sta >= 0+00 R 1) then
{
  _d_Aggbase2Thickness = 0/12
}
```

Missing or Misspelled Key Word

Another error is a missing or misspelled key word. From the expanded **Process Cross Sections Display** dialog shown below it can be noted that for this example shown, the “i” from the word “if” is missing. However, the dialog only shows the line with the syntax error and not the line indicating the variable being defined. To determine which variable it is, close the Process Cross Sections Dialog by clicking on either the **Next Run** or **Exit** button.




Determining which variable is being affected is a two-step process. The first is to run the proposed cross sections again, creating a log file. To do this switch the **To Log File** option from “**To Screen**” to “**To Log File**,” as shown in the dialog to the right. This dialog appears when you go to **Files > Run** in the **Proposed Cross Sections** dialog. You may either leave the name of the file to the default value of “temp.log” or rename it. In either case the log file is a text-formatted file written to the working directory.



The second step is to open the log file in UltraEdit or another text editing program and scroll all the way to the end of the file. **Note:** The log file contains all of the information processed during the run and is more complete than the information written to the screen.

The relevant portion of the file is shown in the figure to the right. The numbered lines end with the line containing the syntax error. Two lines above that is the line with the variable definition, which indicates which variable needs to be modified. For example this it is `_d_Aggbase2Thickness`.



```


3743 1 252 225 /*-----
3744 1 253 226 /* Proposed aggregate pavement base 2 thickness.
3745 1 254 227 /* Positive distance in feet. This number is optional
3746 1 255 228 /* and can be zero or greater than zero. If set to
3747 1 256 229 /* zero this layer will not be drawn.
3748 1 257 230 /*
3749 1 258 231 /* EXAMPLE:
3750 1 259 232 /*
3751 1 260 233 /* if (Sta >= 0+00 R 1) then
3752 1 261 234 /* {
3753 1 262 235 /*     _d_Aggbase2Thickness = 0/12
3754 1 263 236 /* }
3755 1 264 237 /*-----
3756 1 265 238 if (Sta >= 0+00 R 1) then
3757 1 266 239 {
3758 1 267 240 _d_Aggbase2Thickness = 0/12
3759 1 268 241 }
3760 1 269 242 f (Sta >= 490+00 R 1) then
3761
3762 *****
3763 *      %PARSE-E-UNRKNW, Check string validity/syntax at location indicated      *
3764 *                                                                              *
3765 *      f (Sta >= 490+00 R 1) then
3766 *      ^
3767 *                                                                              *
3768 *****
  
```

For Help, press F1 Ln 1, Col. 1, C0 DOS Mod: 12/16/2004 12:55:40PM File Size: 181682 INS





**Missing Brace**

Another common error is to leave off the closing brace in one of the if-statement. Looking at the entire error message can also identify this error. This type of error begins with the line “Missing a closing brace ‘}’”, as shown below.




Finding the source of this error is a little bit more involved than the previous one. Like it, however, the first step is to create a log file as described above. The second step is to open the file in UltraEdit and use the programs ability to match braces, parentheses, and other types of opening and closing symbols. Information on using this ability is covered in **UltraEdit Help** under **Search Menu Commands \ Find Matching Brace**. The tool is activated by going to **Search > Match Brace** in the UltraEdit menu path or by doing a **Ctrl + B** keystroke.

To fine the missing brace, the user needs to go to the end of the section of the log file containing the redefinable variable definitions. The easiest way to do this is to go to the start of the file and use the UltraEdit Find tool (Menu path: **Search > Find**). This brings up the following dialog. Type “**End Redefinable Variables**” in the **Find What** field and click on **Find Next**. This takes the user to the part of the file shown in the bottom figure on the page.



Place the cursor in front of the last closing brace before the End Redefinable Variables text, as shown above, and activate the **Match Brace** tool in UltraEdit by either going to **Search > Match Brace** or doing a **Ctrl + B** combination. This highlights everything between the matching braces and take you to the start of the selected text as shown in the figure on the following page.

A screenshot of a text editor window titled 'T:\de-proj\Cole\j5p0100\data\temp.log'. The window displays a code snippet with line numbers 272 through 282 on the left margin. The code is as follows:

```
272      /*  }                                     */  
273      /*-----*/  
274      if (Sta >= 0+00 R 1) then  
275      {  
276          _d_Aggbase2Thickness = 0/12  
277      } if (Sta >= 0+00 R 1) then  
278      {  
279          _d_Aggbase2Thickness = 0/12  
280      }  
281      /*-----*/  
282      /* Proposed rock fill base thickness. Positive distance */
```

Lines 278 and 279 are highlighted in yellow. Line 280 is highlighted in dark blue. Lines 281 and 282 are also highlighted in dark blue. The code shows an 'if' statement starting at line 274, followed by a block of code between lines 275 and 277, and then another 'if' statement starting at line 277. The code between lines 278 and 279 is the second 'if' statement's block, but it is missing a closing brace '}' at the end of line 279.

An examination of the text at the start of the selected portion in the figure above indicates that the closing brace for the second if-statement for the redefinable variable `_d_Aggbase2Thickness` is missing. To fix the error, simply return to the Proposed Cross Sections dialog and edit the redefinable variable to add the missing brace.